

SCHEDULES

DATE: _____ BY: _____
 PLAN: _____
 REVISIONS: _____
 CHECKED: _____
 ALIGNED: _____
 PLOTTED: _____
 NO. _____
 FILE NAME: _____

DATE: _____ BY: _____
 PROFILE: _____
 REVISIONS: _____
 CHECKED: _____
 ALIGNED: _____
 PLOTTED: _____
 NO. _____
 FILE NAME: _____

FILE NAME: s:\rockford\1038988\indep\w\sch\dls\dls.dgn

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (SPECIAL)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
INDEPENDENCE AVE STA. 799+58.00 TO 813+21.00	85	64	30	34
STA. 799+58.00 TO 813+21.00	210	0	0	210
TOTALS	295	64	30	244

*EARTH EXCAVATION (SPECIAL) INCLUDES THE FOLLOWING ITEMS: (ITEMS TO BE REMOVED AS INDICATED BY CROSS-HATCHING ON PLAN AND PROFILE SHEETS)

EXISTING PAVEMENT & CURB (8" ESTIMATE) 184 CU. YD.
 EXISTING DRIVEWAY (6" ESTIMATE) 17 CU. YD.
 EXISTING SIDEWALK (4" ESTIMATE) 9 CU. YD.
 210 CU. YD. *

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		
STATION	CU YD	REMARKS
INDEPENDENCE AVE.		
CONTINGENCY ITEM	150	AS DIRECTED BY ENGINEER
PROJECT TOTAL	150	

CHANNEL EXCAVATION		
STATION	CU YD	REMARKS
INDEPENDENCE AVE.		
ENTIRE PROJECT	96	
PROJECT TOTAL	96	

TRENCH BACKFILL		
STATION	CU YD	REMARKS
INDEPENDENCE AVE.		
18+44	4	
19+03 TO 19+36	8	
PROJECT TOTAL	12	

SEEDING, CLASS 1 (SPECIAL)		
STATION	ACRE	REMARKS
INDEPENDENCE AVE.		
ENTIRE PROJECT	0.28	
PROJECT TOTAL	0.28	

HEAVY DUTY EROSION CONTROL BLANKET		
STATION	SQ YD	REMARKS
INDEPENDENCE AVE.		
SOUTHEAST BANK OF CHANNEL	147	
NORTHEAST BANK OF CHANNEL	134	
SOUTHWEST BANK OF CHANNEL	149	
NORTHWEST BANK OF CHANNEL	173	
PROJECT TOTAL	603	

PERIMETER EROSION BARRIER		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
LT. 18+30 TO 20+00	241	
RT. 18+30 TO 20+00	102	
LT. 20+00 TO 21+20	82	
RT. 20+00 TO 21+20	110	
PROJECT TOTAL	535	

INLET AND PIPE PROTECTION		
STATION	EACH	REMARKS
INDEPENDENCE AVE.		
18' LT. 18+44	1	
12' RT. 18+44	1	
16' LT. 21+95	1	
15' RT. 21+95	1	
PROJECT TOTAL	4	

STONE RIPRAP, CLASS A5		
STATION	SQ YD	REMARKS
INDEPENDENCE AVE.		
RT. 19+72 TO 20+33	57	
PROJECT TOTAL	57	

FILTER FABRIC		
STATION	SQ YD	REMARKS
INDEPENDENCE AVE.		
RT. 19+72 TO 20+33	57	
PROJECT TOTAL	57	

AGGREGATE BASE COURSE, TYPE A		
STATION	TON	REMARKS
INDEPENDENCE AVE.		
18+30 TO 19+74	121	4" - EXTENDS 1' BEYOND CURB
20+27 TO 21+20	80	4" - EXTENDS 1' BEYOND CURB
PROJECT TOTAL	201	

PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)		
STATION	SQ YD	REMARKS
INDEPENDENCE AVE.		
18+30 TO 19+74	438	
20+27 TO 21+20	292	
PROJECT TOTAL	729	

PROTECTIVE COAT		
STATION	SQ YD	REMARKS
INDEPENDENCE AVE.		
18+20 TO 19+47	883	
20+27 TO 21+20	466	
PROJECT TOTAL	1349	

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6 INCH, SPECIAL		
STATION	SQ. YD.	REMARKS
INDEPENDENCE AVE.		
17' LT. 18+90	289	
15' RT. 19+20	65	
26' LT. 20+57	106	
PROJECT TOTAL	460	

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL		
STATION	SQ FT	REMARKS
INDEPENDENCE AVE.		
LT. 19+26 TO 19+72	251	6' SIDEWALK
LT. 20+25 TO 21+00	236	6' SIDEWALK
PROJECT TOTAL	487	

STORM SEWERS, CLASS A, TYPE 1 15"		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
18+44	34	
PROJECT TOTAL	34	

STORM SEWERS, CLASS A, TYPE 2 15"		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
RT. 18+44 TO 19+74	130	
PROJECT TOTAL	130	

STORM SEWERS, CLASS A, TYPE 2 24"		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
RT. 20+27 TO 20+51	24	
PROJECT TOTAL	24	

STORM SEWER REMOVAL 15"		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
19+01 TO 19+74	127	
PROJECT TOTAL	127	

STORM SEWER REMOVAL 24"		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
19.8' RT. 20+26 TO 20+51	25	
PROJECT TOTAL	25	

INLETS SPECIAL, NO. 2		
STATION	EACH	REMARKS
INDEPENDENCE AVE.		
18.1' LT. 18+44	1	
12.3' RT. 18+44	1	
PROJECT TOTAL	2	

REMOVING INLETS		
STATION	EACH	REMARKS
INDEPENDENCE AVE.		
14.5' RT. 19+01	1	
30' LT. 19+38	1	
PROJECT TOTAL	2	

COMBINATION CONCRETE CURB & GUTTER, TYPE M - 6.18 (MODIFIED)		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
LT. 18+30 TO 19+72	142	
RT. 18+30 TO 19+75	145	
LT. 20+25 TO 21+20	95	
RT. 20+28 TO 21+20	92	
PROJECT TOTAL	474	

TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)		
STATION	EACH	REMARKS
INDEPENDENCE AVE.		
RT. 19+44 TO 19+78	1	
PROJECT TOTAL	1	