RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 20	06-00275-00-PV	LaSALLE	218	23
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 87352

STORM SEWER

STATION	OFFSET (FT.)	TYPE	STANDARD	STORM SEWER																INLETS						MANHOLES													
				CLASS A, TYPE 1									CLASS A, TYPE 2							TYPE A			TYPE B			4' DIAMETER			5' DIAMETER			6' DIAMETER		9' DIA.	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	TRENCH BACKFILL
				8"	10"	12"	15"	18"	24"	36"	42"	48"	12"	15"	18"	24"	30"	36"	48"	TYPE 3 F & G	TYPE 8 GRATE	TYPE 11 F & G	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 1 FRAME CLID, RES. PLATE	TYPE 1 FRAME CLID					
				FOOT																EACH																			CU YD
56+85.00	28.00 RT	MANHOLE	602401, 604001, 602601																							1													
56+65.00	28.58 LT	INLET	602301, 604036																		1																		
		SS					12																																
56+75.00	22.00 LT	INLET	602306, 604006, 602601																					1															
		SS												44																									9
56+75.00	22.00 RT	INLET	602306, 604006, 602601																					1															
		SS												10																									4
		SS												238																									116
59+25.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1													
59+15.00	27.58 RT.	INLET	602301, 604036																		1																		
		SS				10																																	
59+25.00	22.00 LT	INLET	602306, 604006, 602601																					1															
		SS											44																										8
59+25.00	22.00 RT	INLET	602306, 604006, 602601																					1															
		SS												10																									3
		SS													240																								
61+68.45	34.00 RT	MANHOLE	602401, 604001, 602601																							1													
61+05.00	28.58 LT	INLET	602301, 604036																		1																		
		SS											10																										
61+15.00	22.00 LT	INLET	602306, 604006, 602601																					1															
		SS											34																										6
61+50.00	22.00 LT	INLET	602306, 604006, 602601																					1															
		SS												16																									3
61+68.45	22.00 LT	MANHOLE	602401, 604006, 602601																								1												
61+68.45	40.00 LT	INLET BOX	542546																																1				
		SS												16																									
62+59.89	51.04 LT	INLET	602301, 604036																		1																		
		SS											94																										
		SS														44																							11
61+68.45	22.00 RT	MANHOLE	602401, 604006, 602601																								1												
61+15.00	22.00 RT	INLET	602301, 604006																	1																			
		SS				34																																	5
61+50.00	22.00 RT	INLET	602306, 604006, 602601																					1															
		SS				16																																	2
		SS														10																							5
		SS															60																						
62+30.00	34.00 RT	MANHOLE	602401, 604001, 602601																										1										
C.H. 20 (CHAMPLAIN ST.)																																							
158+38.00	15.00 RT	INLET	6021301, 604006																	1																			
		SS											34																										5
158+55.00	15.00 LT	MANHOLE	602401, 604006, 602601																								1												
158+55.00	29.50 LT	END SECTION	542301																																	1			
		SS				14																																	1
		SS					118																																17
159+75.00	15.00 LT	MANHOLE	602401, 604006, 602601																								1												
159+75.00	29.50 LT	END SECTION	542301																																	1			
		SS				14																																	1
		SS						72																															6
160+50.00	15.00 LT	MANHOLE	602401, 604006, 602601																								1												
160+60.00	15.00 RT	INLET	6021301, 604006																	1																			
		SS											30																										5
		SS							6																														2
160+55.00	21.08 LT	MANHOLE	602401, 604001, 602601																							1													
		SS														108																							69
161+65.00	21.08 LT	MANHOLE	602401, 604001, 602601																										1										
161+60.00	15.00 LT	INLET	6021301, 604006																	1																			
		SS											6																										1
162+00.00	34.00 LT	INLET BOX	542546																																1				
		SS													32																								
161+65.00	28.27 LT	MANHOLE	602401, 604001, 602601																							1													
		SS													4																								1
		SS														142																							122
163+10.00	26.00 LT	MANHOLE	602401, 604001, 602601																										1										
162+85.00	15.00 LT	INLET	602301, 604006																	1																			
		SS				24																																	3
163+10.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											8																										2

STORM SEWER SCHEDULE CONTINUED ON NEXT SHEET