

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	ITEM	UNIT	FUND CODE	FUND CODE	NON-PARTICIPATING	TOTAL QUANTITY
			1000	X081-2A		
			ROADWAY QUANTITY	BRIDGE QUANTITY		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT			346	346
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT			476	476
20100500	TREE REMOVAL, ACRES	ACRES	1.16			1.16
* 20200100	EARTH EXCAVATION	CU YD	7.011		14,040	21,051
* 20200910	GRADING & SHAPING ROADWAY	STATIONS	5.58			5.58
* 20700220	POROUS GRANULAR EMBANKMENT	CU YD	25.20		41.84	67.04
△* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRES	4.90		7.68	12.58
△ 25100125	MULCH, METHOD 3	ACRES	4.90		7.68	12.58
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	490		768	1,258
28000300	TEMPORARY DITCH CHECKS	EACH	53		47	100
28000400	PERIMETER EROSION BARRIER	FOOT	5,559		13,259	18,818
28000500	INLET & PIPE PROTECTION	EACH	6		18	24
* 28100707	STONE DUMPED RIP RAP, CLASS A4	SQ YD	20	714	591	1,325
35100100	AGGREGATE BASE COURSE, TYPE A	TON	4,018		13,497	17,515
* 35101400	AGGREGATE BASE COURSE, TYPE B	TON			200	200
* 40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,350		7,754	10,104
* 40300300	BITUMINOUS MATERIALS (COVER & SEAL COATS)	GALLON			15,640	15,640
* 40300500	COVER COAT AGGREGATE	TON			375	375
* 40300600	SEAL COAT AGGREGATE	TON			188	188
* 40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,369		760	2,129
* 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	585		260	845
* 44000100	PAVEMENT REMOVAL	SQ YD			99	99
* 48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD			710	710
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,937		233	2,170
* 50100100	REMOVAL OF EXISTING STRUCTURES	EACH		1		1
50200100	STRUCTURE EXCAVATION	CU YD		52		52
50300225	CONCRETE STRUCTURES	CU YD		119.5		119.5
* 50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DP)	SQ FT		7,200		7,200
50800105	REINFORCEMENT BARS	POUND		8,530		8,530
△* 50900205	STEEL RAILING, TYPE S1	FOOT		481		481

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	ITEM	UNIT	FUND CODE	FUND CODE	NON-PARTICIPATING	TOTAL QUANTITY
			1000	X081-2A		
			ROADWAY QUANTITY	BRIDGE QUANTITY		
51201400	FURNISHING STEEL PILES HP10X42	FOOT		720		720
51202305	DRIVING PILES	FOOT		720		720
51203400	TEST PILE STEEL HP10X42	EACH		4		4
51204650	PILE SHOES	EACH		42		42
51500100	NAME PLATES	EACH		1		1
* 542C0223	PIPE CULVERTS, CLASS C, TYPE 1, 18"	FOOT			90	90
* 542C0229	PIPE CULVERTS, CLASS C, TYPE 1, 24"	FOOT	62		122	184
* 542C5497	PIPE CULVERTS, CLASS C, TYPE 1, EQUIVALENT ROUND SIZE 42"	FOOT	52			52
* 542C5521	PIPE CULVERTS, CLASS C, TYPE 1, EQUIVALENT ROUND SIZE 66"	FOOT	60			60
* 542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	60		512	572
* 542D0229	PIPE CULVERTS, CLASS D, TYPE 1, 24"	FOOT	175			175
* 58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD		800		800
* 60100905	PIPE DRAINS, 4"	FOOT			12	12
60100925	PIPE DRAINS, 8"	FOOT			18	18
* △ 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT		162.5	100	262.5
△ 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH		4		4
66600105	FURNISH & ERECT R.O.W. MARKERS	EACH	26		7	33
* 67100100	MOBILIZATION	L SUM	0.5		0.5	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	347			347
△* 78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH		4		4
△* A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	12			12
△* LR634020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH		4		4
* XX004566	CONCRETE CUT-OFF WALL	CU YD		8.5		8.5

* SEE SPECIAL PROVISIONS
 △ SPECIALTY ITEMS