

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 48	85-00221-00-BR	KANKAKEE	56	9
CONTRACT NO. 87374				

TREE REMOVAL			
STATION	6-15 UNITS DIA.	OVER 15 UNITS DIA.	ACRES
14+73, 30' LT		31	
14+99, 30' LT	10	16	
14+99, 30' LT	10	18	
14+99, 30' LT	15		
15+16, 32' LT	10		
15+36, 33' LT	14		
15+55, 27' LT		18	
15+74, 27' LT	8		
15+94, 33' LT		19	
16+12, 32' LT	8		
16+12, 32' LT	10		
16+49, 33' LT		38	
16+71, 29' LT	7		
16+71, 29' LT	8		
16+71, 29' LT	8		
17+06, 34' LT	9		
17+06, 34' LT	10		
17+06, 34' LT	13		
17+64, 32' LT		21	
17+96, 32' LT	13	17	
17+96, 32' LT		19	
27+18, 34' LT	6		
27+18, 34' LT	7		
27+18, 34' LT	9		
27+18, 35' LT	7		
27+18, 35' LT	8		
27+18, 35' LT	10		
35+15, 20' LT		24	
40+30, 11' LT		29	
47+04, 8' LT		30	
48+52, 12' LT		30	
49+37, 10' LT		48	
56+82, 16' LT	8		
56+82, 16' LT	10		
67+97, 28' LT	10		
69+13, 33' LT		24	

TREE REMOVAL			
STATION	6-15 UNITS DIA.	OVER 15 UNITS DIA.	ACRES
69+53, 26' LT	10		
69+53, 26' LT	12		
69+64, 25' LT	10	20	
69+81, 24' LT	12		
69+92, 23' LT	12		
69+97, 23' LT	10	24	
71+41, 24' LT	10		
71+50, 21' LT	15		
71+72, 21' LT	15		
71+88, 24' LT	6		
71+88, 24' LT	6		
72+00, 24' LT		24	
72+28, 23' LT		24	
17+47N - 20+26N			0.44
20+53N - 25+00N			0.72
TOTALS	346	474	1.16

EARTHWORK SUMMARY			
STA. - STA.	EARTH EXCAVATION CU. YD.	EMBANKMENT-CU. YD. (INCLUDES 30% SHRINKAGE)	BALANCE - CU. YD. WASTE (+) OR SHORTAGE (-)
13+73 - 25+00	1427	1018	409
25+00 - 37+00	3271	637	2634
37+00 - 49+00	2209	726	1483
49+00 - 61+00	1182	3444	-2262
61+00 - 72+71.08	3074	370	2704
2+25N - 14+00N	5430	2593	2837
14+00N - 15+85N	212	2842	-2630
18+27N - 26+00N	774	8542	-7768
26+00N - 36+93N	3403	404	2999
5000N ROAD	69	90	-21
TOTALS	21,051	20,666	385

* ALL WASTE SHALL BE REMOVED FROM THE JOBSITE AT NO ADDITIONAL COMPENSATION TO THE CONTRACTOR.