

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL	80% FEDERAL	80% FEDERAL	80% FEDERAL
				20% STATE ROADWAY 1000-2A	20% STATE STRUCT X081-2A	20% STATE BOX CULVERT X028-2A	20% STATE HWY LIGHTING Y030-1E
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	18606	18606			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1381	1381			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20			
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	16	16			
40300600	SEAL COAT AGGREGATE	TON	4	4			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	64.2	64.2			
40600300	AGGREGATE (PRIME COAT)	TON	388	388			
40600895	CONSTRUCTING TEST STRIP	EACH	4	4			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	816	816			
40600990	TEMPORARY RAMP	SQ YD	140	140			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4368	4368			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4351	4351			
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	8672	8672			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	423	423			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	114	114			
42001200	PAVEMENT FABRIC	SQ YD	1333	1333			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	116	116			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	47	47			
44000100	PAVEMENT REMOVAL	SQ YD	20285	20285			
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	1734	1734			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	58056	58056			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	52503	52503			

* SPECIALTY ITEM

FILE NAME = mscsheets.dgn	USER NAME = ghdineam	DESIGNED -	REVISED -
		DRAWN -	REVISED -
PLOT SCALE = 100.0000 / IN.		CHECKED -	REVISED -
PLOT DATE = 3/17/2009		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE. 665	SECTION 136,137W&RS-3136R109BR-2	COUNTY HENDERSON	TOTAL SHEETS	SHEET NO. 3
			CONTRACT NO. 88773	
ILLINOIS FED. AID PROJECT				