SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE		
				ROADWAY I000-2A	STRUCT X081-2A	BOX CULVERT X028-2A	HWY LIGHTING Y030-1E		
542D5470	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	145	145					
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	381	381					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	181	181					
55100900	STORM SEWER REMOVAL 18"	FOOT	47	47					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	77		77				
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	13.6	13.6					
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	52	52					
60107600	PIPE UNDERDRAINS 4"	FOOT	1000	1000					
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	440	440					
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	180		180				
60237480	INLETS, TYPE A, TYPE 37 GRATE	EACH	1	1					
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1	1					
60241900	INLETS, TYPE G-1, SPECIAL	EACH	6	6					
60500060	REMOVING INLETS	EACH	3	3					
60500065	REMOVING INLETS, SPECIAL	EACH	2	2					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	13.7	13.7					
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	745	745					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1790	1790					
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	160	160					
60625600	ISLAND PAVEMENT (6")	SQ YD	95	95					
61139900	STORM SEWERS, SPECIAL 6"	FOOT	40	40					
61140000	STORM SEWERS, SPECIAL 8"	FOOT	20	20					

* SPECIALTY ITEM