

DRIVEWAY PAVEMENT REMOVAL		
LOCATION	TYPE	SQ. YD.
Lt. Sta. 42+92.1	F.E.	17
Lt. Sta. 99+78.13	P.E.	21
Lt. Sta. 107+79.2	P.E. & M.T.	42
Rt. Sta. 116+69.85	P.E.	22
Lt. Sta. 128+00	F.E.	6
Rt. Sta. 139+87.18	P.E.	36
Lt. Sta. 145+07.11	P.E.	101.5
Rt. Sta. 168+79.42	C.E.	29
Rt. Sta. 169+88.96	C.E.	24
Rt. Sta. 171+11.11	C.E.	33
Rt. Sta. 172+89.30	C.E.	28
Rt. Sta. 179+05.31	F.E.	18
Rt. Sta. 184+31.09	P.E.	43
Lt. Sta. 184+32	M.T.	29
Rt. Sta. 213+03.13	P.E.	21
TOTAL		470

GUARDRAIL REMOVAL	
LOCATION	FOOT
LT. STA. 111+12 TO 113+52	240
TOTAL	240

PAVEMENT REMOVAL				
LOCATION	# OF LANES	LENGTH FOOT	WIDTH FOOT	SQ. YD.
IL 94				
STA. 291+57 TO 292+86		129.0	26.0	373
SOUTH RAMP OF WYE				
STA. 0+00 TO 7+94.84				1490
IL 116				
(NORTH RAMP) STA. 0+00 TO 8+08.4				1646
RT. & LT. STA. 8+08.4 TO 11+91				954
RT. & LT. STA. 11+91 TO 12+18	SEE STAGING DETAIL FOR QUANTITY			
RT. & LT. STA. 12+18 TO 44+07*	2	3189.0	3.00	2126
RT. STA. 44+58 TO 50+17	1	559.0	1.00	62
LT. STA. 44+07 TO 50+17	1	610.0	1.00	68
RT. & LT. STA. 50+17 TO 78+66.19*	2	2849.2	3.00	1899
RT. STA. 78+66.19 TO 86+25.38*	1	759.2	3.00	253
LT. STA. 78+66.19 TO 86+25.38*	1	759.2	6.00	506
RT. & LT. STA. 86+25.38 TO 105+59.58*	2	1934.2	3.00	1289
RT. STA. 105+59.58 TO 117+56.93*	1	1197.4	6.00	798
LT. STA. 105+59.58 TO 117+56.93*	1	1197.4	3.00	399
RT. & LT. STA. 117+56.93 TO 121+66	2	409.0	1.00	91
RT. & LT. STA. 121+66 TO 126+78*	2	512.0	1.00	114
RT. & LT. STA. 126+78 TO 131+39	2	461.0	1.00	102
RT. & LT. STA. 131+39 TO 157+35*	2	2596.0	3.00	1731
RT. & LT. STA. 157+35 TO 162+84	2	549.0	1.00	122
RT. & LT. STA. 162+84 TO 186+85*	2	2401.0	3.00	1601
RT. & LT. STA. 186+85 TO 211+67*	2	2482.0	3.00	1655
LT. STA. 211+67 TO 215+72	1	405.2	3.00	135
LT. STA. 215+72 TO 217+00	1	128.0	1.00	14
RT. STA. 211+67 TO 213+31.96	1	165.0	3.00	55
RT. STA. 213+31.96 TO 217+00	1	368.0	1.00	41
RT. & LT. STA. 217+00 TO 222+00	measured in cadd			1076
RT. & LT. STA. 222+00 TO 223+63.16	2	163.0	1.00	36
1700 E				
NORTH LEG (STA. 10+14.8 TO 11+35)	measured in cadd			301
SOUTH LEG (STA. 9+54.5 TO 9+86.5)	measured in cadd			120
TOTAL				19058

*SEE TYPICALS

HMA SURFACE REMOVAL								
LOCATION	LENGTH	WIDTH	HMA SURFACE REMOVAL- BUTT JOINT	TEMPORARY RAMP	PAVEMENT BREAKING	HMA SURFACE REMOVAL, 1/2"	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, VARIABLE DEPTH
	FOOT	FOOT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
IL 94								
STA. 284+70 TO 285+00	30.0	26.0	87	29				
STA. 285+00 TO 291+06	606.0	26.0				1734		
STA. 291+06 TO 291+30.2	24.0	26.0						69
STA. 291+30 TO 291+57	EXISTING PAVEMENT STAYS IN PLACE- SEE DETAIL FOR BUILD UP							
STA. 292+86 TO 294+18.7 (Both Pavement and Gutter)	132.7	32.0			472			
STA. 294+18.7 TO 298+50	EXISTING PAVEMENT & GUTTER STAYS IN PLACE- PROPOSED PAVEMENT GREATER THEN 3 FEET ABOVE EXISTING							
IL 116								
STA. 11+91 TO 12+18								393
STA. 12+18 TO 13+26	BUILD UP AREA- SEE DETAIL							
STA. 13+27 TO 14+78	151.0	26.0						436
STA. 14+78 TO 103+87	8909.0	26.0						25737
STA. 103+47 TO 103+87	40.0	26.0	116	29				
STA. 103+87 TO 186+85	8298.0	26.0						23972
STA. 186+85 TO 187+25	40.0	22.0	98	24				
STA. 187+25 TO 211+27 (IN TOWN)	2402.0	22.0					5872	
STA. 211+27 TO 211+67	40.0	26.0	116	29				
STA. 211+67 TO 217+00	533.0	26.0						1540
STA. 222+00 TO 223+23.16	123.2	26.0						356
STA. 223+23.16 TO 223+63.16	40.0	26.0	116	29				
DETOUR ROUTE								
SEE DETOUR TABLE			50					52185
GRAND TOTAL			581	140	472	1734	58057	52503

FENCE		
LOCATION	FENCE REMOVAL	TEMPORARY FENCE, SPECIAL
	FOOT	FOOT
WILLIAM & SHIRLEY GULLBERG TRUST	3069	1535
WENDELL & HAZEL FOX	495	248
MARGARET ROTH, ET. AL.	2673	1337
EVA MARIE LINK TRUST	2706	1353
MEREDITH & BONNIE FLATT	3135	1568
POGUE TRUST	3795	1898
INGHRAM TRUST	2409	1205
TOTAL	18282	9141

TEMPORARY FENCE QUANTITY IS 1/2 OF THE REMOVAL QUANTITY.

PAVEMENT REMOVAL (SPECIAL)				
LOCATION	# OF LANES	LENGTH FOOT	WIDTH FOOT	SQ. YD.
NORTH RAMP OF WYE				
LT. STA. 0+00 TO 5+00	1	500.0	2.67	148
IL 116				
RT. STA. 44+58 TO 50+17	1	559.0	2.67	166
LT. STA. 44+07 TO 50+17	1	610.0	2.67	181
RT. & LT. STA. 117+56.93 TO 121+66	2	409.1	2.67	243
RT. & LT. STA. 121+66 TO 126+78	2	512.0	2.00	228
RT. & LT. STA. 126+78 TO 131+39	2	461.0	2.67	274
RT. & LT. STA. 157+35 TO 162+84	2	549.0	2.67	326
TOTAL				1565

REMOVAL INCLUDES BURIED GUTTER AND HMA OVERLAYS. (SEE TYPICALS)

LOCATION	GUTTER REMOVAL	CCC & G REMOVAL
	FOOT	FOOT
IL 94		
RT. STA. 289+42 TO 292+86	344	
LT. STA. 291+66 TO 292+86	120	
IL 116		
LT. STA. 0+00 TO 5+00	557	
LT. STA. 5+50 TO 7+77.6	211	
LT. STA. 44+07 TO 50+17	610	
RT. STA. 44+81 TO 50+17	537	
LT. STA. 117+56.93 TO 121+66	409	
RT. STA. 117+92.8 TO 121+66	374	
LT. STA. 121+66 TO 126+78	512	
RT. STA. 121+66 TO 126+78	512	
LT. STA. 126+78 TO 131+39	461	
RT. STA. 126+78 TO 131+39	461	
LT. STA. 157+35 TO 162+84	549	
RT. STA. 157+35 TO 162+84	549	
RT. STA. 213+31.96 TO 217+00	368	
LT. STA. 215+72.22 TO 217+00		128
RT. STA. 217+00 TO 222+00	500	
LT. STA. 217+00 TO 222+00		500
RT. STA. 222+00 TO 223+63.16	163	
LT. STA. 222+00 TO 223+63.16		163
TOTAL	7237	791