



UTILITY CONTACTS:

BP AMOCO	FRANK ACOUSTA OR MARCIE FOSTER	630-836-3461
	LOCAL FIELD REPRESENTATIVE, CRAIG CALVERT	217-620-9621
BUCKEYE PARTNERS, L.P.	JANA OLTHOFF	708-426-4170
	GREG RAMSEY	815-448-2491 OR 815-651-9472

MIN. DEPTH	UTILITY	COMPANY
4'-0"	PETROLEUM	BUCKEYE PARTNERS, L.P.
40"	OIL	BP AMOCO
2'-6"	TELEPHONE	FRONTIER COMMUNICATIONS
2'-0"	CABLE T.V.	MEDIACOM COMMUNICATIONS
3'-0"	ELECTRIC	AMEREN IP
2'-6"	NATURAL GAS	NICOR
4'-0"	WATER	DALLAS RURAL WATER DIST.

PLAN NOTES

- *REMOVAL OF SAPLINGS, BUSHES AND ROOTS SHALL BE REMOVED AND DISPOSED OF AS REQUIRED BY ARTICLE 201
- *SEE TREE REMOVAL TABLE FOR STATIONING AND QUANTITY
- *REFER TO THE GENERAL NOTE AND/OR THE UNDERDRAIN, SPECIAL DETAIL IF ANY PIPE UNDERDRAINS OR FIELD TILE ARE ENCOUNTERED DURING CONSTRUCTION
- *DUE TO THE POOR CONDITION OF THE EXISTING E.O.P ALONG BOTH SIDES OF IL ROUTE 116, QUANTITIES WERE INCLUDED FOR THE CONTRACTOR TO SAW CUT AND REMOVE PAVEMENT AT THE LOCATIONS AND WIDTHS SPECIFIED IN THE EXISTING TYPICALS. THIS WORK SHALL BE PAID FOR AS EITHER PAVEMENT REMOVAL AND/OR PAVEMENT REMOVAL, SPECIAL.

LEGEND

	PAVEMENT REMOVAL
	PAVEMENT BREAKING
	HMA SURFACE REMOVAL-BUTT JOINT

STA. 217+00 TO 222+00
 PAVEMENT REMOVAL= 1,076 SQ. YD.
 (SEE SPECIAL PROVISION)
 GUTTER REMOVAL= 500 FEET

LT. & RT. STA. 211+27 TO 223+65
 (LIMIT FROM E.O.P. TO R.O.W., P.E. & T.E.)
 TREE REMOVAL= 0.5 ACRES

FILE NAME =	USER NAME = russellsm	DESIGNED -	REVISED -
sh01.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/28/2009	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

EXISTING UTILITY INFORMATION AND REMOVAL ITEMS

SCALE: 1"=50'	SHEET NO. OF SHEETS	STA. 216+00 TO STA. 223+63.16
---------------	---------------------	-------------------------------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	(136,137)W&RS-3(136R)109BR-2	HENDERSON		106
CONTRACT NO. 88773				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				