

EARTHWORK SCHEDULE								
LOCATION (STATION TO STATION)		CHANNEL EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE FACTOR (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)	
ILLINOIS RT. 94								
298+50.00	TO	300+91.47		372	279.0	4,413	-4,134	3,384
300+91.47	TO	302+30.00		169	126.8	946	-819	927
SN: 036-0069		378						
302+30.00	TO	303+55.89		229	171.8	612	-440	990
303+55.89	TO	306+76.65		1,539	1,154.3	377	777	2,448
309+20.00	TO	309+80.00		2	1.5	44	-43	0
<b>TOTAL:</b>		<b>378</b>		<b>2,311</b>	<b>1,733</b>	<b>6,392</b>	<b>-4,659</b>	<b>7,749</b>

TEMPORARY FENCE SCHEDULE				
LOCATION (STATION TO STATION)				TEMPORARY FENCE (FOOT)
ILLINOIS RT. 94				
298+50.00	TO	305+87.98	RT	759.00
299+80.86	TO	307+47.53	LT	758.00
<b>TOTAL:</b>				<b>1,517</b>

SEEDING SCHEDULE							
LOCATION (STATION TO STATION)		SEEDING CLASS 2A (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	TEMP. EROSION CONTROL SEEDING (ACRE) (6 APPL.)	
ILLINOIS ROUTE 94							
298+50.00	TO	300+91.47	0.7	63.0	63.0	4.2	
300+91.47	TO	302+30.00	0.2	17.1	17.1	1.1	
302+30.00	TO	303+55.89	0.2	18.0	18.0	1.2	
303+55.89	TO	306+76.65	0.5	45.9	45.9	3.1	
309+20.00	TO	309+80.00	0.0	0.0	0.0	0.0	
<b>TOTAL:</b>		<b>1.6</b>	<b>144.0</b>	<b>144.0</b>	<b>144.0</b>	<b>9.6</b>	
<b>PAY TOTAL:</b>		<b>1.6</b>	<b>150.0</b>	<b>150.0</b>	<b>150.0</b>	<b>9.6</b>	

GEOTECHNICAL FABRIC-MIDDLE CREEK	
LOCATION	GEOTECH. FABRIC FOR GRND. STAB.
IL 94	SQ. YD.
STA. 298+50 TO 301.01.17	930
STA. 302+39.17 TO 306+76.65	1418
<b>TOTAL</b>	<b>2348</b>

ROW MARKER SCHEDULE				
LOCATION (STATION TO STATION)				FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS (EACH)
ILLINOIS ROUTE 94				
299+00.00	93.00	RT		1
300+00.00	81.00	RT		1
300+95.00	95.00	LT		1
301+00.00	81.00	RT		1
302+00.00	68.00	LT		1
302+00.00	70.00	RT		1
302+50.00	90.00	LT		1
303+00.00	65.00	RT		1
303+25.00	90.00	LT		1
303+50.00	70.00	LT		1
303+50.00	73.00	RT		1
304+15.00	73.00	RT		1
304+35.00	50.00	RT		1
305+00.00	50.00	RT		1
305+85.00	33.00	RT		1
307+00.00	70.00	LT		1
307+50.00	55.00	LT		1
<b>TOTAL:</b>				<b>17</b>

PERMANENT SURVEY MARKERS SCHEDULE		
LOCATION		PERMANENT SURVEY MARKERS, TYPE I (EACH)
ILLINOIS ROUTE 94		
301+70.17	CL	1
303+00.00	CL	1
<b>TOTAL:</b>		<b>2</b>

FENCE REMOVAL SCHEDULE							
LOCATION (STATION TO STATION)						FENCE REMOVAL (FOOT)	
ILLINOIS RT. 94							
298+50.00	35.27	TO	299+54.26	35.66	RT	104.26	
299+54.26	35.66	TO	299+90.17	33.23	RT	35.99	
299+90.17	33.23	TO	300+73.30	56.23	RT	86.25	
300+73.30	56.23	TO	301+21.32	72.36	RT	50.66	
301+21.32	72.36	TO	301+17.56	44.94	RT	27.68	
301+17.56	44.94	TO	301+66.23	44.76	RT	48.67	
302+20.18	69.10	TO	302+16.09	38.00	RT	31.37	
302+16.09	38.00	TO	305+87.98	40.00	RT	371.90	
299+80.86	111.37	TO	299+85.22	73.92	LT	37.70	
299+85.22	73.92	TO	300+00.35	60.17	LT	20.44	
300+00.35	60.17	TO	300+31.00	61.72	LT	30.69	
300+31.00	61.72	TO	301+36.20	54.02	LT	105.48	
301+36.20	54.02	TO	301+48.18	54.96	LT	12.02	
301+48.18	54.02	TO	303+74.61	58.59	LT	180.04	
303+74.61	58.59	TO	307+47.53	57.85	LT	372.92	
<b>TOTAL:</b>						<b>1,517</b>	