

ITEM NO. 28000300
TEMPORARY DITCH CHECKS

LOCATION	EACH
RT STA 18+50.99	1
RT STA 19+90.82	1
RT STA 19+72.08	1
RT STA 20+23.28	1
RT STA 21+07.97	1
RT STA 21+57.97	1
LT STA 18+49.22	1
LT STA 18+86.21	1
LT STA 19+70.40	1
LT STA 20+24.17	1
LT STA 21+07.97	1
LT STA 21+57.97	1
TOTAL =	12

ITEM NO. 28000400
PERIMETER EROSION BARRIER

LOCATION	FOOT
RT STA 18+50 TO 19+87	137
RT STA 20+03 TO 21+50	147
LT STA 18+50 TO 19+86	136
LT STA 20+02 TO 21+50	148
TOTAL =	568

ITEM NO. #4001878
HOT MIX ASPHALT BINDER COURSE
IL-9.5, N50 SPECIAL

LOCATION	THICKNESS	TON
STA 18+70.17 TO 21+26.26	VAR. 3/4" - 1 1/2"	54

ITEM NO. 40600215
POLYMERIZED BITUMINOUS MATERIALS
(PRIME COAT)

LOCATION	TON
STA 18+70.17 TO 21+26.26	0.5

ITEM NO. 40600982
HOT-MIX ASPHALT SURFACE REMOVAL

LOCATION	SQ. YD.
STA 18+70.17 TO 19+00.17	74
STA 20+96.26 TO 21+26.26	74
TOTAL =	148

ITEM NO. 40603335
HOT-MIX ASPHALT SURFACE COURSE
MIX "D", N50

LOCATION	THICKNESS	TON
STA 18+70.17 TO 21+26.26	1 1/2"	54

ITEM NO. 48101200
AGGREGATE SHOULDERS, TYPE B

LOCATION	TON
RT STA 21+00.89 TO 21+26.26	4
LT STA 18+70.17 TO 18+94.66	4
TOTAL =	8

ITEM NO. 48203029
HOT-MIX ASPHALT SHOULDERS, 8"

LOCATION	SQ. YD.
RT STA 18+70.17 TO 21+00.89	102
LT STA 18+94.66 TO 21+26.26	103
TOTAL =	205

ITEM NO. X0301512
GUARDRAIL AGGREGATE EROSION CONTROL

LOCATION	TON
RT STA 18+70.17 TO 21+00.89	41
LT STA 18+94.66 TO 21+26.26	41
TOTAL =	82

ITEM NO. 44201747
CLASS "D" PATCH, TYPE IV, 8"

LOCATION	SQ. YD.
STA 19+32.22 TO 20+57.69	147

ITEM NO. 78001110
PAINT PAVEMENT MARKING - LINE 4"

LOCATION	FEET
STA 18+70.17 TO 21+26.26	512

GUARDRAIL SCHEDULE		
ITEM	LOCATION	QUANTITY
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6.75 FT POSTS (ITEM NO. 63000002)	RT STA 19+59.88 TO STA. 19+84.88	25 LF
	LT STA 20+11.13 TO 20+36.13	25 LF
STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE (ITEM NO. 63000025)	RT STA 19+84.88 TO 20+11.13	26.25 LF
	LT STA (SAME AS ABOVE)	26.25 LF
TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TAN) (ITEM NO. 63100167)	RT STA 19+09.88 TO 19+59.88	1 EA
	RT STA 20+11.13 TO 20+61.13	1 EA
	LT STA 19+34.88 TO 19+84.88	1 EA
	LT STA 20+36.13 TO 20+86.13	1 EA
GUARDRAIL REMOVAL (ITEM NO. 63200310)	RT STA 19+63.29 TO 19+88.01	24.72 LF
	RT STA 20+10.78 TO 20+36.07	25.29 LF
	LT STA 19+63.11 TO 19+88.40	25.29 LF
	LT STA 20+11.05 TO 20+36.20	25.15 LF
TERMINAL MARKER - DIRECT APPLIED (ITEM NO. 78201000)	RT STA 19+09.88	1 EA
	RT STA 20+61.13	1 EA
	LT STA 19+34.88	1 EA
	LT STA 20+86.13	1 EA
GUARDRAIL MARKERS, TYPE A (ITEM NO. 78200410)	RT STA 19+59.88 TO 20+11.13	4 EA
	LT STA 19+84.88 TO 20+36.13	4 EA

FILE NAME = quanttsyschedulsheet.dgn	USER NAME = .USER.	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -
FUHRMANN ENGINEERING, INC.	PLOT DATE = 2/19/2009 2:15:07 PM		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES
COUNTRY ROAD 8 (1900 E) OVER BRANCH OF HONEY CREEK
SCALE: SHEET NO. 2 OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	136.137W&RS-3;136R109BR-2	Henderson	490	172
FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT				CONTRACT NO. 88773