

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1E	1F
CODE NO.	ITEM	CONSTRUCTION CODE	TOTAL QUANTITY	I000	Y030	Y031
		UNIT		ROADWAY	ROADWAY LIGHTING	TRAFFIC SIGNALS
Δ*	88800100 PEDESTRIAN PUSH-BUTTON	EACH	2	0	0	2
Δ	89000100 TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	0	0	1
Δ*	89500100 RELOCATE EXISTING SIGNAL HEAD	EACH	2	0	0	2
Δ*	89500200 RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2	0	0	2
Δ*	89502205 MODIFY EXISTING CONTROLLER (SPECIAL)	EACH	1	0	0	1
Δ*	89502380 REMOVE EXISTING HANDHOLE	EACH	4	0	0	4
Δ*	89502385 REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	0	0	9
*	X0301430 PRECAST CONCRETE PARKING BLOCK	EACH	5	5	0	0
Δ*	X0321558 SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2	0	0
*	X0321566 MULCH, SPECIAL	SQ YD	1,544	1,544	0	0
*	X0321905 STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	307	307	0	0
*	X0321906 STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	12	12	0	0
*	X0321908 STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	4	4	0	0
Δ*	X0321973 MODIFY EXISTING SERVICE INSTALLATION	EACH	1	0	0	1
Δ*	X0322464 ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	1	1	0	0
*	XX007744 CONCRETE ENCASEMENTS	EACH	1	1	0	0
*	X0322748 BICYCLE LANE MARKING	EACH	44	44	0	0
*	X0322795 REMOVE AND RELOCATE EXISTING MONUMENT	EACH	1	1	0	0
*	X0322923 SEGMENTAL CONCRETE BLOCK WALL	SQ FT	155	155	0	0
Δ*	X0323200 SANITARY SEWER, DUCTILE IRON, 12"	FOOT	30	30	0	0
Δ*	X0325815 REMOVE EXISTING CABLE	FOOT	1,900	0	1,900	0
Δ*	X0962500 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1	0	0	1
Δ*	XX001866 LIGHTING CONTROLLER, LOCATION NO. 1	L SUM	1	0	1	0
Δ*	X8430100 REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE	FOOT	40	0	40	0
Δ*	X8730027 ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,330	0	0	1,330
Δ*	X8730250 ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELDED	FOOT	970	0	0	970
Δ*	X8760200 ACCESSIBLE PEDESTRIAN SIGNALS	EACH	8	0	0	8
Δ*	X8760250 VIBROTACTILE FEATURE	EACH	8	0	0	8
Δ*	X8850106 INDUCTIVE LOOP DETECTOR, RACK MOUNTED	EACH	16	0	0	16
*	XX000880 SEEDING, CLASS 1, SPECIAL	SQ YD	1,544	1,544	0	0
Δ*	XX002184 PHOTOELECTRIC CONTROL	EACH	1	0	0	1
Δ*	XX002208 6" DIAMETER PIPE BOLLARD, CONCRETE FILLED	EACH	3	3	0	0
Δ*	XX002895 SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW FRAME AND LID	EACH	1	1	0	0
Δ*	XX002943 CONCRETE FOUNDATION, SPECIAL	EACH	1	0	1	0
*	XX003313 REMOVE AND REINSTALL BRICK PAVER	SQ FT	1,060	1,060	0	0
Δ*	XX003581 ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 1C	FOOT	660	0	0	660

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1E	1F
CODE NO.	ITEM	CONSTRUCTION CODE	TOTAL QUANTITY	I000	Y030	Y031
		UNIT		ROADWAY	ROADWAY LIGHTING	TRAFFIC SIGNALS
Δ*	B1100605 CONDUIT Attached to Structure, 2" Dia., PVC coated Galvanized Steel	FOOT	84	0	84	0
*	XX004688 BRICK PAVER SIDEWALK	SQ FT	220	220	0	0
*	XX004735 RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0	0
Δ*	XX006163 REMOVE ELECTRIC CABLE FROM CONDUIT (SPECIAL)	L SUM	1	0	0	1
*	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1	0	0
*	Z0026700 FURNISHING AND SETTING STEEL POSTS	EACH	36	36	0	0
*	Z0036700 PARKING METER POSTS TO BE REMOVED	EACH	53	53	0	0
*	Z0038700 PERMANENT BENCH MARKS	EACH	1	1	0	0
*	Z0042300 PORTLAND CEMENT CONCRETE SIDEWALK CURB	FOOT	60	60	0	0
*	Z0050900 REMOVE CONCRETE FOUNDATION	EACH	1	0	1	0
*	Z0051500 REMOVING AND RESETTING STREET SIGNS	EACH	14	14	0	0
*	XX007863 RESTRICTED DEPTH INLET TYPE B, TYPE 11 FRAME AND GRATE	EACH	5	5	0	0
Δ*	XX007864 SANITARY SEWER, DUCTILE IRON, 8"	FOOT	6	6	0	0
*	XX007865 STORM SEWERS, TYPE 3, WATER MAIN QUALITY PIPE, 12"	FOOT	6	6	0	0

* SEE SPECIAL PROVISIONS
Δ SPECIAL ITEMS

REVISED 4-6-09

FILE NAME = p:\u0070052\plans\sheets\04-SumQuantities.dgn	DESIGNED - JAJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.U. RTE. 7175	SECTION 07-00456-00-RS	COUNTY CHAMPAIGN	TOTAL SHEETS 75	SHEET NO. 6
PLOT DATE = 2/27/2009 3:21:07 PM	DRAWN - JAJ	REVISED -					GOODWIN AVENUE		CONTRACT NO. 91392		
	CHECKED - RLH	REVISED -					ILLINOIS FED. AID PROJECT				
	DATE - 01-2009	REVISED -									
			SCALE : NONE		SHEET NO. 6 OF 75 SHEETS		STA. TO STA.				