

SUMMARY OF QUANTITIES			SAFETY CODE		2A	1E	1F
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	I000	Y030	Y031
					ROADWAY	ROADWAY LIGHTING	TRAFFIC SIGNALS
Δ*	88800100 PEDESTRIAN PUSH-BUTTON	EACH	2		0	0	2
Δ	89000100 TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		0	0	1
Δ*	89500100 RELOCATE EXISTING SIGNAL HEAD	EACH	2		0	0	2
Δ*	89500200 RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2		0	0	2
Δ*	89502205 MODIFY EXISTING CONTROLLER (SPECIAL)	EACH	1		0	0	1
Δ*	89502380 REMOVE EXISTING HANDHOLE	EACH	4		0	0	4
Δ*	89502385 REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		0	0	9
*	X0301430 PRECAST CONCRETE PARKING BLOCK	EACH	5		5	0	0
Δ*	X0321558 SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2		2	0	0
*	X0321566 MULCH, SPECIAL	SQ YD	1,544		1,544	0	0
*	X0321905 STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	307		307	0	0
*	X0321906 STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	12		12	0	0
*	X0321908 STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 15"	FOOT	4		4	0	0
Δ*	X0321973 MODIFY EXISTING SERVICE INSTALLATION	EACH	1		0	0	1
Δ*	X0322464 ABANDON AND FILL EXISTING SANITARY MANHOLE	EACH	1		1	0	0
*	XX001744 CONCRETE ENCASEMENTS	EACH	1		1	0	0
*	X0322748 BICYCLE LANE MARKING	EACH	44		44	0	0
*	X0322795 REMOVE AND RELOCATE EXISTING MONUMENT	EACH	1		1	0	0
*	X0322923 SEGMENTAL CONCRETE BLOCK WALL	SQ FT	155		155	0	0
Δ*	X0323200 SANITARY SEWER, DUCTILE IRON, 12"	FOOT	30		30	0	0
Δ*	X0325815 REMOVE EXISTING CABLE	FOOT	1,900		0	1,900	0
Δ*	X0962500 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1		0	0	1
Δ*	XX007866 LIGHTING CONTROLLER, LOCATION NO. 1	L SUM	1		0	1	0
Δ*	X8430100 REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE	FOOT	40		0	40	0
Δ*	X8730027 ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,330		0	0	1,330
Δ*	X8730250 ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELDED	FOOT	970		0	0	970
Δ*	X8760200 ACCESSIBLE PEDESTRIAN SIGNALS	EACH	8		0	0	8
Δ*	X8760250 VIBROTACTILE FEATURE	EACH	8		0	0	8
Δ*	X8850106 INDUCTIVE LOOP DETECTOR, RACK MOUNTED	EACH	16		0	0	16
*	XX000880 SEEDING, CLASS 1, SPECIAL	SQ YD	1,544		1,544	0	0
Δ*	XX002184 PHOTOELECTRIC CONTROL	EACH	1		0	0	1
Δ*	XX002895 SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW FRAME AND LID	EACH	1		1	0	0
*	XX003313 REMOVE AND REINSTALL BRICK PAVER	SQ FT	1,060		1,060	0	0
Δ*	XX003581 ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 1C	FOOT	660		0	0	660
Δ*	81100605 CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	100		0	100	0
*	XX004688 BRICK PAVER SIDEWALK	SQ FT	220		220	0	0

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES			SAFETY CODE		2A	1E	1F
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	I000	Y030	Y031
					ROADWAY	ROADWAY LIGHTING	TRAFFIC SIGNALS
*	XX004735 RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1		1	0	0
Δ*	XX006163 REMOVE ELECTRIC CABLE FROM CONDUIT (SPECIAL)	L SUM	1		0	0	1
*	Z0013798 CONSTRUCTION LAYOUT	L SUM	1		1	0	0
*	Z0026700 FURNISHING AND SETTING STEEL POSTS	EACH	36		36	0	0
*	Z0036700 PARKING METER POSTS TO BE REMOVED	EACH	53		53	0	0
*	Z0038700 PERMANENT BENCH MARKS	EACH	1		1	0	0
*	Z0042300 PORTLAND CEMENT CONCRETE SIDEWALK CURB	FOOT	60		60	0	0
*	Z0051500 REMOVING AND RESETTING STREET SIGNS	EACH	14		14	0	0
*	XX007863 RESTRICTED DEPTH INLET TYPE B, TYPE 11 FRAME AND GRATE	EACH	5		5	0	0
Δ*	XX007864 SANITARY SEWER, DUCTILE IRON, 8"	FOOT	6		6	0	0
*	XX007865 STORM SEWERS, TYPE 3, WATER MAIN QUALITY PIPE, 12"	FOOT	6		6	0	0

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

FILE NAME = P:\U0070052\Plans\Sheets\04-SumQuantities.dgn
 PLOT DATE = 1/23/2009 4:40:47 PM

DESIGNED - JAJ	REVISED -
DRAWN - JAJ	REVISED -
CHECKED - RLH	REVISED -
DATE - 01-2009	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE SHEET NO. 6 OF 75 SHEETS STA. TO STA.

F.A.U. RTE. 7175	SECTION 07-00456-00-RS	COUNTY CHAMPAIGN	TOTAL SHEETS 75	SHEET NO. 6
GOODWIN AVENUE		CONTRACT NO. 91392		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		