

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 102+90 TO STA. 112+00	2064	1548	1387	+161
STA. 112+00 TO STA. 123+50	5268	3951	6661	-2710
STA. 123+50 TO STA. 134+10	2085	1564	1284	+280
CANTRALL ROAD	160	120	22	+98
TOTAL	9577	7183	9354	2171

AGGREGATE SCHEDULE

LOCATION	AGG. BASE COURSE, TYPE A (TON)	AGG. SURF. COURSE, TYPE A (TON)	AGG. SHOULDERS (TON)	AGG. SURFACE COURSE TYPE B (TON)
	STA. 102+90 TO STA. 134+10	6396		
STA. 102+90 TO STA. 134+10 LT. & RT. CANTRALL ROAD		346	111	
F.E. STA. 105+60 LT.			15	
P.E. STA. 106+75 LT.			12	
F.E. @ BERKSHIRE ROAD LT.			26	
F.E. STA. 114+53 RT.			23	
F.E. STA. 116+55 LT.			32	
P.E. STA. 122+69 LT.			85	
STA. 116+45 TO STA. 122+76 (TEMP. ACCESS ROAD)				288
TOTAL	6396	346	2360	288

HOT MIX ASPHALT SCHEDULE

LOCATION	HMA BINDER COURSE IL-19.0 N50 (TON)	HMA SURF. COURSE MIX C N50 (TON)	BIT. MATERIALS (PRIME COAT) (GALLON)
	STA. 102+90 TO STA. 134+10	1412	939
P.E. STA. 106+75 M.B. TURNOUT	13	8	28
BERKSHIRE ROAD	44	29	
P.E. STA. 122+69 M.B. TURNOUT	10	7	23
TICE ROAD	42	28	
CANTRALL ROAD	39	26	42
TOTAL	1561	1037	3213

SCHEDULE PIPE CULVERTS, CLASS D, TYPE 1 & METAL END SECTIONS

LOCATION	PIPE CULVERTS (FOOT)		METAL END SECTIONS (EACH)	
	15"Ø	18"Ø	15"	18"
	STA. 105+35 TO STA. 105+80 LT.	50		
STA. 106+48 TO STA. 106+74 LT.	26		2	
STA. 114+45 TO STA. 115+17 LT.		72		2
STA. 128+50 TO STA. 129+24 RT.	74		2	
STA. 128+53 TO STA. 129+21 LT.		68		2
TOTAL	150	140	6	4

SCHEDULE FURNISHING AND ERECTING RIGHT OF WAY MARKERS

LOCATION	QUANTITY (EACH)
STA. 102+90 35' LT. & 45' LT.	2
STA. 102+90 35' RT. & 40' RT.	2
STA. 106+29 45' LT. & 40' LT.	2
STA. 107+73 40' LT. & 50' LT.	2
STA. 107+73 40' RT.	1
STA. 110+00 60' RT.	1
STA. 112+81.86 50' LT.	1
STA. 114+71.51 60' RT.	1
STA. 120+17.51 60' RT. & 40' RT.	2
STA. 126+15.53 50' LT.	1
STA. 128+15.48 40' RT. & 35' RT.	2
STA. 128+69.53 50' LT.	1
STA. 129+04.53 50' LT.	1
STA. 129+07 63' RT. (STA. 5+63-20' LT. CANTRALL RD.)	1
STA. 129+20 45' RT.	1
STA. 134+10 40' LT. & 50' LT.	2
STA. 134+10 45' RT. & 40' RT.	2
STA. 7+66.66 (CANTRALL RD.) 20' LT.	1
TOTAL	26

SCHEDULE PERIMETER EROSION BARRIER

LOCATION	QUANTITY (FOOT)
STA. 102+90 30' RT. TO STA. 110+00 60' RT.	720
STA. 110+00 60' RT. TO STA. 114+15 75' RT.	430
STA. 114+15 75' RT. TO STA. 121+17 40' RT.	707
STA. 121+17 40' RT. TO STA. 8+50 (CANTRALL RD) 20' RT.	1070
STA. 8+50 (CANTRALL RD.) 20' LT. TO STA. 134+10 30' RT.	810
STA. 102+90 30' LT. TO STA. 105+40 45' LT.	265
STA. 105+40 45' LT. TO STA. 106+45 40' LT.	70
STA. 106+45 40' LT. TO STA. 114+88 130' LT. (BERKSHIRE RD.)	840
STA. 114+88 130' LT. TO STA. 116+40 77' LT.	124
STA. 116+40 77' LT. TO STA. 117+93 86' LT.	128
STA. 117+93 86' LT. TO STA. 122+55 94' LT.	450
STA. 122+55 94' LT. TO STA. 128+70 62' LT. (TICE RD.)	597
STA. 128+70 62' LT. TO STA. 134+10 30' LT.	538
TOTAL	6749

SCHEDULE PAINT PAVEMENT MARKING-LINE 4"

LOCATION	WHITE (FOOT)	YELLOW (FOOT)
	STA. 102+90 TO STA. 134+10 (EDGE)	5890
STA. 102+90 TO STA. 134+10 (NO PASSING)		6240
SUB-TOTAL	5890	6240
TOTAL	12130	

SCHEDULE FENCE REMOVAL

LOCATION	QUANTITY (FOOT)
STA. 102+90 35' LT. TO STA. 114+45 35' LT.	1155
STA. 114+33 75' RT. TO STA. 128+49 35' RT.	1457
STA. 102+90 41' RT. TO STA. 110+45 60' RT.	754
STA. 7+67 (CANTRALL RD.) 20' LT. TO STA. 134+10 40' RT.	754
STA. 126+15 50' LT. TO STA. 128+70 35' LT.	259
STA. 126+15 53' RT. TO STA. 128+70 42' RT.	264
TOTAL	4643

SCHEDULE TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	QUANTITY (UNIT)
STA. 106+92 24' LT.	6
STA. 106+92 36' LT.	6
STA. 107+04 35' LT.	6
TOTAL	18

SCHEDULE SEEDING, CLASS 2 (SPECIAL)

LOCATION	QUANTITY (ACRE)
STA. 102+90 TO STA. 134+10 LT.	2.10
STA. 102+90 TO STA. 134+10 RT.	2.95
CANTRALL ROAD	0.15
TOTAL	5.20

SCHEDULE PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ. YD.)
STA. 102+90 TO STA. 134+10	7627
TOTAL	7627

SCHEDULE RELOCATE EXISTING MAILBOX

LOCATION	QUANTITY (EACH)
STA. 106+84 22' LT.	1
STA. 122+89 22' LT.	1
TOTAL	2

SCHEDULE PIPE CULVERTS, TYPE 1 RCCP 24"

LOCATION	QUANTITY (FOOT)
STA. 123+83 CROSSROAD	56
TOTAL	56

SCHEDULE PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"

LOCATION	QUANTITY (EACH)
STA. 123+83 33' LT. & 23' RT.	2
TOTAL	2

SCHEDULE HOT MIX ASPHALT SURFACE REMOVAL-BUTT JOINT

LOCATION	QUANTITY (SQ. YD.)
BERKSHIRE RD.	25
TICE RD.	11
TOTAL	36

SCHEDULE PIPE CULVERT REMOVAL

LOCATION	QUANTITY (FOOT)
STA. 105+39 TO STA. 105+79 LT. 15"Ø	40
STA. 106+47 TO STA. 106+97 LT. 15"Ø	50
STA. 114+50 TO STA. 115+08 LT. 15"Ø	58
STA. 117+99 CROSS RD. 72"Ø	66
STA. 123+83 CROSS RD. 15"Ø	50
TOTAL	264

SCHEDULE GUARDRAIL REMOVAL

LOCATION	QUANTITY (FOOT)
STA. 122+98 TO STA. 126+90	400
TOTAL	400

SCHEDULE TEMPORARY DITCH CHECKS

LOCATION	QUANTITY (EACH)
STA. 104+50 33' LT. & 32' RT.	2
STA. 106+00 31' LT. & 32.5' RT.	2
STA. 107+50 28' LT. & 31' RT.	2
STA. 109+00 27.5' LT. & 34' RT.	2
STA. 110+50 29' LT. & 36' RT.	2
STA. 112+00 31' LT. & 38' RT.	2
STA. 116+50 42.5' RT.	1
STA. 118+50 47' LT. & 45' RT.	2
STA. 120+00 41' RT.	1
STA. 127+00 36' LT. & 26.5' RT.	2
STA. 128+50 34' LT. & 29' RT.	2
STA. 130+00 32' LT. & 30' RT.	2
STA. 131+50 30' LT. & 29' RT.	2
STA. 133+00 27' LT. & 26' RT.	2
TOTAL	26