

**SCHEDULE  
HOT MIX ASPHALT MATERIALS**

LOCATION	HOT MIX ASPHALT SURFACE REMOVAL (BUTT JOINT) (SQ. YD.)	HOT MIX ASPHALT BASE COURSE (WIDENING) 9" (SQ. YD.)	TEMPORARY RAMP (SQ. YD.)	HOT MIX ASPHALT BINDER COURSE IL-19.0, N70 (TON)	HOT MIX ASPHALT SURFACE COURSE MIX. "D", N70 (TON)
C.E. STA. 209+20 (BOJ)	10		48	-	14
STA. 209+20 TO STA. 217+70				311	261
STA. 217+70 TO STA. 342+20				*4732	2803
E. 1st INT. - STA. 260+63	9		22	10	13
E. 2nd ST INT. - STA. 313+61 RT.	3		14	14	7
VELDA ST. INT. - STA. 319+56.5 RT.	10		22	37	14
HAYES RD. INT. - STA. 326+82 LT.	9		16	18	11
FAYE ST. INT. - STA. 328+27 RT.	13		22	24	14
LUCAS ST. INT. - STA. 337+57.5 RT.	9		16	4	11
EOJ (STA. 342+20)	6		12		
STA. 217+70 TO STA. 342+20 LT.		2045			
STA. 217+70 TO STA. 342+20 RT.		2000			
STA. 214+55.6 LT. - M.B. TURNOUT				10	10
P.E. STA. 240+30 RT.				2	2
STA. 240+30.3 LT. - M.B. TURNOUT				3	3
STA. 277+34.3 RT. - M.B. TURNOUT				3	3
STA. 287+32.7 RT. - M.B. TURNOUT				6	6
ROADWAY GRAND TOTAL	69	4045	172	5174	3150

\* MINIMUM BINDER THICKNESS = 1 1/2", HOWEVER QUANTITY REPRESENTS AVG. DEPTH OF 2 1/2" FOR CROSS SLOPE CORRECTION.

**GUARDRAIL SCHEDULE**

LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT) (EACH)	STEEL PLATE BEAM GUARDRAIL TYPE A (FOOT)	TERMINAL MARKER DIRECT APPLIED (EACH)
STA. 248+05 TO STA. 248+55 RT.	1		1
STA. 248+55 TO STA. 249+80 RT.		125	
STA. 249+80 TO STA. 250+30 RT.	1		1
STA. 279+75 TO STA. 280+25 RT.	1		1
STA. 280+25 TO STA. 282+00 RT.		175	
STA. 282+00 TO STA. 282+50 RT.	1		1
STA. 338+04.5 TO STA. 338+54.5 RT.	1		1
STA. 338+54.5 TO STA. 339+67 RT.		112.5	
STA. 339+67 TO STA. 340+17 RT.	1		1
STA. 247+95 TO STA. 248+45 LT.	1		1
STA. 248+45 TO STA. 251+07.5 LT.		262.5	
STA. 251+07.5 TO STA. 251+57.5 LT.	1		1
STA. 281+06 TO STA. 281+56 LT.	1		1
STA. 281+56 TO STA. 283+31 LT.		175	
STA. 283+31 TO STA. 283+81 LT.	1		1
STA. 338+48 TO STA. 338+98 LT.	1		1
STA. 338+98 TO STA. 340+73 LT.		175	
STA. 340+73 TO STA. 341+23 LT.	1		1
TOTAL	12	1025	12

NOTE: STATIONS ARE APPROXIMATE.

**SCHEDULE  
PAVEMENT MARKING**

LOCATION	LENGTH (FT.)	TEMP. PVMT. MARKING LINE - 4"			SHORT TERM PVMT. MARKING		WORK ZONE PVMT. MARKING REMOVAL		PAINT PVMT. MARKING LINE - 4"			PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	PAINT PAVEMENT MARKING - LINE 24"
		EDGE WHITE (FT.)	SOLID WHITE (FT.)	YELLOW SKIP DASH 30' SPACING (FT.)	WHITE (FT.)	YELLOW (SQ. FT.)	WHITE (SQ. FT.)	YELLOW (SQ. FT.)	EDGE WHITE (FT.)	SOLID YELLOW - @ (FT.)	YELLOW SKIP DASH 30' SPACING (FT.)		
STA. 210+00 TO STA. 217+70	770	1540	1540		*154		51	1540	1540				
STA. 217+70 TO STA. 338+00	12030	24060		3010	*2406		794	24060		3010			
STA. 338+00 TO STA. 342+20	420	840	420	110	*84		28	840	420	110			
STA. 341+60 RAILROAD "X" & "R"											62		
STA. 341+35												24	
STA. 341+85												24	
STA. 342+00												24	
SUB-TOTAL		26440	1960	3120				26440	1960	3120			
TOTAL			31520		*2644		873		31520		62		72

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS.  
\* 10% OF TOTAL LENGTH FOR SHORT-TERM PAVEMENT MARKING

**SCHEDULE  
PRIME COAT**

LOCATION	BITUMINOUS MATERIALS (TON)	AGGREGATE MATERIALS (TON)
STA. 209+20 TO STA. 217+70	1.18	6.20
STA. 217+70 TO STA. 342+20	12.62	66.40
C.E. STA. 209+65.5	0.06	0.32
E. 1ST ST. RD. INT. - STA.	0.06	0.30
E. 2ND ST. RD. INT. - STA. 313+61	0.03	0.16
VELDA ST. INT. - STA. 319+56.50	0.06	0.33
HAYES RD. INT. - STA. 326+82	0.05	0.27
FAYE ST. INT. - STA. 328+27	0.06	0.33
SHARON ST. INT. - STA. 337+37.5	0.05	0.26
TOTAL	14.17	74.57
SAY	15	75

**SCHEDULE  
EARTH EXCAVATION (WIDENING)**

LOCATION	QUANTITY (CU. YD.)
STA. 217+70 TO STA. 342+20 LT.	511
STA. 217+70 TO STA. 342+20 RT.	500
TOTAL	1011

**SCHEDULE  
AGGREGATE SHOULDERS TYPE B**

LOCATION	QUANTITY (TON)
STA. 209+20 TO STA. 217+70	80
STA. 217+70 TO STA. 342+20	2191
FROM PRIVATE AND FIELD ENTRANCE SCHEDULE	413
TOTAL	2684

USER NAME = #USER#  
DRAWN - #SCALE#  
PLOT DATE = #DATE#

DESIGNED - ---  
CHECKED - ---  
DATE - ---

REVISED - ---  
REVISED - ---  
REVISED - ---



**Allen Henderson & Associates, Inc.**  
Civil and Structural Engineers Springfield, IL.  
62703 Phone: (217)544-8033 IL Design Firm  
No. 184-001907

**QUANTITY SCHEDULES**

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_\_ OF \_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
732	07-00125-01-RS	MONTGOMERY	57	8
CONTRACT NO. 93480			FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT	