

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED 20% STATE F.A.P. 781 (IL. RTE. 33)	
				4+920.234 TO 15+545.000	15+545.000 TO 16+016.000
				CONSTRUCTION CODE TYPE	
				I000-2A RURAL	I000-2A URBAN
M5421235	PIPE CULVERTS, TYPE 1 RCCP, 750MM	METER	32.5	32.5	0.0
M5421240	PIPE CULVERTS, TYPE 1 RCCP, 900MM	METER	55.5	55.5	0.0
M542C216	REINFORCED CONCRETE PIPE TEE, 375MM PIPE WITH 300MM RISER	EACH	1	1	0
M542C328	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 375MM RISER	EACH	1	1	0
M542C336	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 375MM RISER	EACH	1	1	0
M542E012	END SECTIONS, 300MM	EACH	1	1	0
M542E016	END SECTIONS, 375MM	EACH	102	100	2
M542E020	END SECTIONS, 450MM	EACH	60	48	12
M542E024	END SECTIONS, 525MM	EACH	14	14	0
M542E028	END SECTIONS, 600MM	EACH	46	46	0
M542E032	END SECTIONS, 675MM	EACH	6	6	0
M542E036	END SECTIONS, 750MM	EACH	12	12	0
M542E044	END SECTIONS, 900MM	EACH	14	14	0
M542E048	END SECTIONS, 1050MM	EACH	4	4	0
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 375MM	EACH	10	10	0
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 450MM	EACH	6	4	2
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 600MM	EACH	14	14	0
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 750MM	EACH	4	4	0
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 900MM	EACH	6	6	0
M542H420	PIPE CULVERTS, CLASS D, TYPE 1, 300MM	METER	2.5	2.5	0.0
M542H425	PIPE CULVERTS, CLASS D, TYPE 1, 375MM	METER	106.0	89.5	16.5
M542H430	PIPE CULVERTS, CLASS D, TYPE 1, 450MM	METER	444.0	363.0	81.0
M542H435	PIPE CULVERTS, CLASS D, TYPE 1, 525MM	METER	93.5	93.5	0.0
M542H440	PIPE CULVERTS, CLASS D, TYPE 1, 600MM	METER	337.5	337.5	0.0
M542H445	PIPE CULVERTS, CLASS D, TYPE 1, 675MM	METER	37.0	37.0	0.0
M542H450	PIPE CULVERTS, CLASS D, TYPE 1, 750MM	METER	90.0	90.0	0.0
M542H455	PIPE CULVERTS, CLASS D, TYPE 1, 900MM	METER	76.0	76.0	0.0
M542H460	PIPE CULVERTS, CLASS D, TYPE 1, 1050MM	METER	24.4	24.4	0.0
M542T220	PIPE CULVERTS, CLASS C, TYPE 1, 375MM (TEMPORARY)	METER	58.0	58.0	0.0
M542T225	PIPE CULVERTS, CLASS C, TYPE 1, 450MM (TEMPORARY)	METER	6.5	6.5	0.0
M542T235	PIPE CULVERTS, CLASS C, TYPE 1 600MM (TEMPORARY)	METER	6.5	6.5	0.0
M5900200	EPOXY CRACK INJECTION	METER	3.6	3.6	0.0
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	438.15	438.15	0.00

* *Specialty Hems*
* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE DECEMBER 22, 2008 CHECKED BY LWJ</p>

PLOT DATE = 1/29/2009
 FILE NAME = H:\1428\Contract 94533\SHT_004_sump_VB.dgn

H. M. & G. NO. 4420