

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED 20% STATE	
				F.A.P. 781 (IL. RTE. 33)	
				4+920.234 TO 15+545.000	15+545.000 TO 16+016.000
				CONSTRUCTION CODE TYPE	
				1000-2A RURAL	1000-2A URBAN
M6320030	GUARDRAIL REMOVAL	METER	5	5	0
M7030100	SHORT-TERM PAVEMENT MARKING	METER	4,360	4,171	189
M7030620	TEMPORARY PAINT PAVEMENT MARKING LINE, 100 MM	METER	29,454	28,479	975
M7040100	TEMPORARY CONCRETE BARRIER	METER	1,230	1,130	100
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	1,130	1,030	100
M7800205	PAINT PAVEMENT MARKING LINE, 100 MM	METER	29,454	28,479	975
MX030199	TEMPORARY PAVEMENT	SQ M	3,451	3,451	0
MX030203	TEMPORARY PAVEMENT REMOVAL	SQ M	3,451	3,451	0
MX032196	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ M	17.9	17.9	0.0
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	2.5	2.5	0.0
MX033731	PRECAST CONCRETE BOX CULVERT 900MM x 450MM	METER	10.0	10.0	0.0
MX033732	PRECAST CONCRETE BOX CULVERT 3.0M x 1.65M	METER	10.9	10.9	0.0
MX033735	PRECAST CONCRETE BOX CULVERT 3.0M x 0.9M	METER	43.2	43.2	0.0
MX033736	PRECAST CONCRETE BOX CULVERT 750MM x 450MM (M273)	METER	51.0	36.6	14.4
MX033748	TEMPORARY EMBANKMENT PLACEMENT AND REMOVAL	CU M	855	855	0
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1	0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12	10	2
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	11	9	2
Z0076600	TRAINEES	HOUR	500	500	0
28000300	TEMPORARY DITCH CHECKS	EACH	408	398	10
28000500	INLET AND PIPE PROTECTION	EACH	158	149	9
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	0
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	0
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	0	1
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	0	1
54001008	BOX CULVERT END SECTION, CULVERT NO. 8	EACH	2	2	0
54001009	BOX CULVERT END SECTION, CULVERT NO. 9	EACH	2	2	0
54001010	BOX CULVERT END SECTION, CULVERT NO. 10	EACH	2	2	0
54001011	BOX CULVERT END SECTION, CULVERT NO. 11	EACH	2	2	0
54001012	BOX CULVERT END SECTION, CULVERT NO. 12	EACH	2	2	0
54001013	BOX CULVERT END SECTION, CULVERT NO. 13	EACH	2	2	0
54001014	BOX CULVERT END SECTION, CULVERT NO. 14	EACH	2	2	0

Ⓞ Y080

\* SEE SPECIAL PROVISIONS

▲ Specialty Items

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p><b>SUMMARY OF QUANTITIES</b></p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE DECEMBER 22, 2008 CHECKED BY LWJ</p>

PLOT DATE = 1/29/2009  
 FILE NAME = H:\1420\Contract 94533\SHT\_084.sumq.vb.dgn

H. M. & G. NO. 4420