

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	LYRS	CRAWFORD	212	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**TREE REMOVAL (6 TO 15 UNITS DIAMETER)  
TREE REMOVAL (OVER 15 UNITS DIAMETER)  
TREE REMOVAL HECTARES**

LOCATION			EXISTING OCTOBER, 1996 TREE SURVEY	COMMON NAME	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL, HECTARES
STATION	OFFSET	RT/LT	MM		UNIT	UNIT	HA
<b>RURAL</b>							
STA 6+732.0	10.8	RT	625	RED MAPLE		25	
STA 6+829.0	13.0	RT		ELM	6		
STA 6+835.4	13.8	RT	675	RED MAPLE		27	
STA 6+845.0	14.0	RT		ELM	6		
STA 6+850.5	12.3	RT	675	RED MAPLE		27	
STA 6+869.8	8.6	RT	150/75 TWIN	SLIPPERY ELM	9		
STA 7+249.5	6.7	LT	425	RED MAPLE		17	
STA 7+257.7	7.2	LT	650	RED MAPLE		26	
STA 7+264.4	7.1	LT	325	SUGAR MAPLE	13		
STA 7+271.9	6.7	LT	550	RED MAPLE		22	
STA 7+294.0 TO 7+328.0	22.0	LT					0.07
STA 7+405.7	8.1	RT	800	AMERICAN ELM		32	
STA 7+613.6	10.9	RT	175	WHITE PINE	7		
STA 7+616.2	10.8	RT	150	WHITE PINE	6		
STA 7+622.2	11.1	RT	175	WHITE PINE	7		
STA 7+627.3	11.4	RT	150	WHITE PINE	6		
STA 7+629.3	11.4	RT	150	WHITE PINE	6		
STA 7+632.2	10.7	RT	175	WHITE PINE	7		
STA 7+636.3	11.1	RT	150	WHITE PINE	6		
STA 7+641.0	11.1	RT		EVERGREEN	7		
STA 7+644.7	11.0	RT		EVERGREEN	6		
STA 8+046.1	11.0	RT	900	SILVER MAPLE		36	
STA 8+054.1	11.4	RT	600	HACKBERRY		24	
STA 8+746.3	9.5	LT	325	RIVER BIRCH	13		
STA 9+675.0 TO 9+904.0	14.0	LT					0.11
STA 10+181.0 TO 10+231.0	14.0	RT					0.03
STA 11+123.0 TO 11+143.0	10.0	LT					0.01
STA 11+465.0 TO 11+555.0	16.0	LT					0.05
STA 11+475.0 TO 11+508.0	16.0	RT					0.02
STA 11+755.0 TO 11+786.0	19.0	RT					0.01
STA 11+767.0 TO 11+792.0	13.0	LT					0.02
STA 12+489.0 TO 12+615.0	15.0	LT					0.11
STA 12+703.0 TO 12+753.0	10.0	RT					0.02
STA 12+773.0 TO 12+846.0	20.0	RT					0.02
STA 12+793.2	11.9	LT	950	WHITE OAK		38	
STA 12+809.6	12.1	LT	450	SHAGBARK HKRY		18	
STA 12+835.3	12.0	LT	800	WHITE OAK		32	
STA 13+033.0 TO 13+050.0	13.0	RT					0.01
STA 13+109.4	10.5	LT	300	WHITE OAK	12		
STA 13+506.2	7.5	RT	425	SUGAR MAPLE		17	
STA 13+523.9	7.5	RT	425	SUGAR MAPLE		17	
STA 13+532.4	7.2	RT	400	RED MAPLE		16	
STA 13+564.2	9.0	RT	500	WHITE PINE		20	
STA 13+569.6	8.9	RT	550	RED MULBERRY		22	
STA 13+575.3	10.4	RT	250	RED PINE	10		
STA 13+585.0	9.7	RT	500	ESTRN WHITE PINE		20	
STA 13+595.0	9.5	RT	325	CHINESE ELM	13		
STA 13+620.9	9.2	RT	750	SHINGLE OAK		30	
STA 13+629.2	12.8	RT	325	ESTRN RED CEDAR	13		
STA 13+642.9	12.6	RT	600	GREEN ASH		24	
TOTALS					153	490	0.48
TOTALS ROUNDED FOR SUMMARY SHEET					153	490	0.5

**PAVED DITCH REMOVAL**

LOCATION			PAVED DITCH REMOVAL
STATION	RT/LT		M4405000 METER
<b>RURAL</b>			
STA. 5+008.0 TO 5+116.0	LT		108.0
STA. 9+063.0 TO 9+184.5	RT		121.5
STA. 9+195.0 TO 9+208.0	RT		14.5
STA. 9+652.0 TO 9+676.5	RT		26.0
STA. 9+687.5 TO 9+712.5	RT		25.0
STA. 9+704.6 TO 9+769.0	LT		64.4
STA. 9+727.5 TO 9+769.0	RT		41.5
STA. 10+066.5 TO 10+115.0	RT		74.0
STA. 10+193.3 TO 10+255.7	LT		62.8
STA. 11+440.3 TO 11+474.0	RT		33.7
STA. 11+441.8 TO 11+471.0	LT		29.2
STA. 11+500.0 TO 11+536.0	LT		37.0
STA. 11+534.0 TO 11+559.0	RT		25.5
STA. 11+760.0 TO 11+775.7	RT		15.7
STA. 11+805.8 TO 11+820.4	LT		14.6
STA. 12+357.5 TO 12+447.5	LT		90.0
STA. 12+358.5 TO 12+445.5	RT		87.0
TOTALS			870.4
TOTALS ROUNDED FOR SUMMARY SHEET			871

**GUARDRAIL REMOVAL**

LOCATION			GUARDRAIL REMOVAL
STATION	RT/LT		M6320030 METER
<b>RURAL</b>			
STA 6+323.800 TO 6+328.600	RT		4.8
TOTAL			4.8
TOTAL ROUNDED FOR SUMMARY SHEET			5

**PAVEMENT REMOVAL**

LOCATION				PAVEMENT REMOVAL
STATION	TO	STATION	LT/RT	M4402000 SQ M
<b>RURAL</b>				
8+910.900			LT	252.52
13+143.500	TO	13+750.733(BK)	LT&RT	4462.34
13+391.700			LT	330.95
15+062.400			RT	216.95
TOTAL				5262.76
TOTALS ROUNDED FOR SUMMARY SHEET				5,263

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  <b>SCHEDULE OF QUANTITIES</b>  SCALE NO SCALE      DRAWN BY KOJ DATE DECEMBER 22, 2008      CHECKED BY LWJ
NAME	DATE	

PLOT DATE = 12/22/2008  
FILE NAME = H:\V\20\Contract\94533\SHI\_014\_sch\_all\_schedules\_V8.dgn

H. M. & G. NO. 4420