

PIPE CULVERT REMOVAL/REMOVE EXISTING CULVERTS (CONTINUED)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	LT/RT	EXISTING MATERIAL	FOR INFORMATION ONLY SIZE (mm)	EXISTING END TREATMENT		REMOVE EXISTING CULVERTS M5010521 METER	PIPE CULVERT REMOVAL M5010522 METER
				UPSTREAM	DOWNSTREAM		
STA 14+234.800	RT	CMP	380				7.2
STA 14+242.400	LT	RCP	380	CONC HDWL	CONC HDWL		15.0
STA 14+265.600	LT	RCP	380				14.5
STA 14+308.900	LT	RCP	380				14.8
STA 14+447.300	LT	CMP	460				12.0
STA 14+447.300	RT	CMP	375				12.0
STA 14+461.300	LT	CMP	740				7.5
STA 14+542.500	LT	CMP	740				7.8
STA 14+553.800	LT	CMP	740				7.3
STA 14+600.800	LT	CMP	910	STEEL HDWL	STEEL HDWL		6.5
STA 14+628.800	RT	RCP	380		CONC HDWL		9.0
STA 14+630.300	LT	CMP	910	STEEL HDWL	CONC HDWL		7.5
STA 14+659.300	LT	CMP/CONC BOX	790/640	RAILROAD TIES	CONC HDWL	9.6	
STA 14+664.800	RT	RCP	380		CONC HDWL		10.0
STA 14+696.800	RT	RCP	380	CONC HDWL	CONC HDWL		8.0
STA 14+711.600	LT	CMP	910				12.3
STA 14+725.800	RT	RCP	380				6.0
STA 14+756.000	LT	ELLIP CMP	860/1270				9.0
STA 17+763.300	RT	CMP	380				22.5
STA 14+770.800	LT	ELLIP CMP	860X1270				9.0
STA 14+784.000	RT	CMP	430				20.3
STA 14+861.000	LT	CMP	380				11.5
STA 14+861.800	RT	CMP	380				9.4
STA 14+886.300	RT	CMP	380				11.5
STA 14+926.300	LT	RCP	380				12.2
STA 14+926.300	RT	VCP	360	CONC HDWL	CONC HDWL		5.6
STA 14+981.300	LT	RCP	380				11.3
STA 15+002.000	LT	RCP	380	CONC HDWL	CONC HDWL		5.2
STA 15+172.500	AR	CONC BOX	460X460	CONC HDWL	CONC HDWL	9.0	
STA 15+232.300	LT	RCP	460				16.4
STA 15+320.300	LT	CMP	430				23.2
STA 15+353.800	LT	CMP	380				9.1
STA 15+450.800	RT	VCP	380		CONC HDWL		10.0
STA 15+454.800	LT	CMP	460				13.6
STA 15+511.800	RT	VCP/CMP	380				9.4
STA 15+544.900	RT	VCP	380	CONC HDWL			5.6
SUBTOTAL						74.6	1840.9
URBAN							
STA 15+595.800	LT	CMP	380/300				13.1
STA 15+660.800	LT	CMP	380				9.2
STA 15+661.300	RT	CMP	330				10.6
STA 15+723.100	RT	CMP	380				13.7
STA 15+870.300	RT	VCP	430	CONC HDWL	CONC HDWL		5.6
STA 15+871.400	LT	RCP	410		CONC HDWL		13.8
STA 15+931.300	RT	RCP	410				21.1
STA 15+933.820		CONC BOX	900X450	CONC HDWL	CONC HDWL	9.1	9.3
STA 15+960.300	LT	RCP	410				28.6
SUBTOTAL						9.1	125.0
TOTALS						83.7	1965.90
TOTALS ROUNDED FOR SUMMARY SHEET						84	1,966

PLOT DATE = 12/22/2008
 FILE NAME = H:\V420\Contract 94533\SHT_014_sch.e11_schedules_VB.dgn

H. M. & G. NO. 4420

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES SCALE NO SCALE DRAWN BY KOJ DATE DECEMBER 22, 2008 CHECKED BY LWJ