F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE CULVERT SCHEDULE - CONTINUED

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS														PRECAST REINFORCED CONCRETE FLARED END SECTIONS					END SECTIONS									PIPE TEES			INLETS
				RCCP					CLASS D																										
				TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1	TYPE 1															375 PIPE WITH 300 RISER	600 PIPE WITH 375 RISER	750 PIPE WITH 375 RISER	TYPE A, TY 8 GRATE
STATION	RT/LT /AR		CUBIC METER	375 METER	450 METER	600 METER	750 METER	900 METER	300 METER	375 METER	450 METER	525 METER	600 METER	675 METER	750 METER	900 METER	1050 METER	375 EACH	450 EACH	600 EACH	750 EACH	900 EACH	300 EACH	375 EACH	450 EACH	525 EACH	600 EACH	675 EACH	750 EACH	900 EACH	1050 EACH	EACH	EACH	EACH	EACH
STA 15+232.300	LT	PIPE CULVERTS												17.07														2							
STA 15+321.000	LT	PIPE CULVERTS	6.72			16.46														2															
STA 15+353.800	LT	PIPE CULVERTS											9.45														2								
STA 15+450.800	RT	PIPE CULVERTS											13.41														2								
STA 15+454.800	LT	PIPE CULVERTS	7.01			16.76														2															
STA 15+509.800	LT	PIPE CULVERTS	8.20			17.98														2															
STA 15+511.800	RT	PIPE CULVERTS											10.67														2								
		SUBTOTAL	138.48	110.04	35.05	118.42	32.30	55.47	2.44	894.92	362.73	93.26	337.45	36.58	89.85	75.60	24.08	10	4	14	4	6	1	100	48	14	46	6	12	14	4	1	1	1	2
URBAN																																			
STA 15+595.800	LT	PIPE CULVERTS									17.07														2										
STA 15+660.800	LT	PIPE CULVERTS									16.76														2										
STA 15+661.300	RT	PIPE CULVERTS	3.06	16.14														2																	
STA 15+723.100	RT	PIPE CULVERTS								16.15														2											
STA 15+870.300	RT	PIPE CULVERTS									9.75														2										
STA 15+871.400	LT	PIPE CULVERTS	1.39		12.19														2																
STA 15+890.000	LT	PIPE CULVERTS									8.84														2										
STA 15+931.300	RT	PIPE CULVERTS									11.28														2										
STA 15+960.300	LT	PIPE CULVERTS									17.37														2										
		SUBTOTAL	4.45	16.14	12.19	0.00	0.00	0.00	0.00	16.15	81.07	0.00	0.00	0.00	0.00	0.00	0.00	2	2	0	0	0	0	2	12	0	0	0	0	0	0	0	0	0	0
TOTALS			142.93	126.18	47.24	118.42	32.30	55.47	2.44	911.1	443.80	93.26	337.45	36.58	89.85	75.60	24.08	12	6	14	4	6	1	102	60	14	46	6	12	14	4	1	1	1	2
TOTALS ROUNDED FOR SUMMARY SHEET			143	126.5	47.5	118.5	32.5	55.5	2.5	911.5	444.0	93.5	337.5	37.0	90.0	76.0	24.5	12	6	14	4	6	1	102	60	14	46	6	12	14	4	1	1	1	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PIPE CULVERT SCHEDULE

SCALE

DRAWN BY KOJ

DATE DECEMBER 22, 2008

CHECKED BY LWJ

H. M. & G. NO. 4420

PLOT DATE = 12/22/2008
FILE NAME = H:\4420\Contract 94533\SHT_024_sch_pipeculverts_V8.dgn