

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STREETSCAPE	CURB AND GUTTER MAINTENANCE AND RESURFACING	CITY OF DECATUR
				80% ITEP	100% STATE	100% CITY
Δ A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	19	19		
Δ A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
Δ C2C00424	SHRUB, ARONIA ARBUIIFOLIA BRILLIANT ISSIMA (BRILLIANT RED CHOKEBERRY), 2' HEIGHT, CONTAINER	EACH	140	140		
Δ 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	921	921		
Δ 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	621	621		
Δ*25200700	SODDING, SPECIAL	SQ YD	450	450		
Δ*25400105	PERENNIAL PLANTS	EACH	1447	1447		
28000400	PERIMETER EROSION BARRIER	FOOT	925	925		
28000500	INLET AND PIPE PROTECTION	EACH	23		23	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	59	59		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3830		3830	
40600300	AGGREGATE (PRIME COAT)	TON	54		54	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1071		1071	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	1048		1048	
40600990	TEMPORARY RAMP	SQ YD	764		764	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2145		2145	
42001300	PROTECTIVE COAT	SQ YD	1364		1364	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	314	314		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	34198	34198		
42400800	DETECTABLE WARNINGS	SQ FT	315	315		
*44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	25067		25067	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	263	263		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5610		5610	
44000600	SIDEWALK REMOVAL	SQ FT	38804	38804		
*44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	960	960		
*56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	21	21		
*60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1			1
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	23		23	
*60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	2			2
60266600	VALVE BOXES TO BE ADJUSTED	EACH	12		12	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16		16	
60600605	CONCRETE CURB, TYPE B	FOOT	1057	1057		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	6140		6140	
63200310	GUARDRAIL REMOVAL	FOOT	153	153		
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	4		4	
66900205	SPECIAL WASTE DISPOSAL	CU YD	4	4		
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70102632	TRAFFIC CONTROL AND PROTECTION STANDARD 701602	L SUM	1	0.5	0.5	
70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L SUM	1	0.5	0.5	
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	15	30	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3329		3329	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	793.2		793.2	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6373		6373	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6101		6101	

Δ SPECIALTY ITEMS
* PAY ITEM REQUIRES A SPECIAL PROVISION

URS	USER NAME =	DESIGNED - BKN	REVISED - March 12, 2009	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	CITY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - BKN/RLS/MEC/CGF	REVISED - March 23, 2009				323	06-00625-00-SW	DECATUR	121	4
	PLOT DATE =	CHECKED - JJM	REVISED -				ELDORADO STREETSCAPE PROJECT		CONTRACT NO. 95574		
		DATE -	REVISED -				ILLINOIS FED. AID PROJECT: TE-00071351				
							SHEET NO. 1 OF 3 SHEETS		STA. TO STA.		