

FBI ROUTE	IDOT SECTION	COUNTY
9177	*	ST. CLAIR
FEDERAL AID PROJECT		ILLINOIS
IDOT JOB NO.	C-98-309-09	
IDOT CONTRACT NO.	97362	
* 05-00007-03-PV; 06-00007-05-PV		

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS ♦ SURVEYORS ♦ PLANNERS



- CORPORATE OFFICE**
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com
- CARBONDALE OFFICE**
206 WEST COLLEGE ST., SUITE 2
CARBONDALE, ILLINOIS 62901
TEL (618) 549-8844
FAX (618) 549-8450
info@twm-inc.com
- EDWARDSVILLE OFFICE**
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
info@twm-inc.com
- ST. CHARLES OFFICE**
400 NORTH 5th ST., SUITE 101
ST. CHARLES, MISSOURI 63301
TEL (636) 724-8300
FAX (636) 724-8304
info@twm-inc.com
- WATERLOO OFFICE**
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
info@twm-inc.com

TREE REMOVAL SCHEDULE - PHASE III			
LOCATION (STATION, OFFSET)	TREE REMOVAL (UNITS)		
	6 TO 15 UNITS	OVER 15 UNITS	
SEIBERT ROAD			
44+05	17.80	LT	6.0
44+26	21.80	LT	6.0
44+36	23.80	LT	12.0
44+46	22.20	LT	6.0
44+49	23.50	LT	6.0
47+17	26.20	LT	8.0
47+20	28.60	LT	6.0
47+35	28.70	LT	15.0
47+70	27.00	LT	6.0
47+80	25.00	LT	12.0
47+88	25.80	LT	12.0
47+95	24.60	LT	12.0
47+96	24.60	LT	8.0
48+12	26.00	LT	10.0
48+20	22.00	LT	15.0
48+22	24.00	LT	10.0
48+34	21.00	LT	10.0
44+55	22.50	LT	20.0
47+02	23.00	LT	24.0
47+76	27.70	LT	18.0
47+78	26.20	LT	18.0
48+28	24.00	LT	18.0
JOHNSON ROAD			
1+11	20.20	LT	24.0
TOTAL:			160

TREE REMOVAL SCHEDULE - PHASE V			
LOCATION (STATION, OFFSET)	TREE REMOVAL (UNITS)		
	6 TO 15 UNITS	OVER 15 UNITS	
SEIBERT ROAD			
SEIBERT ROAD	40	90	
TOTAL:	40 *	90 *	

*NOTE:
TREE REMOVAL FOR PHASE V REPRESENTS AN ESTIMATED QUANTITY.
THE QUANTITY WILL BE FINALIZED IN THE FIELD BY THE ENGINEER.

PIPE CULVERT REMOVAL SCHEDULE - PHASE III			
LOCATION (STATION, DIRECTION)		PIPE CULVERT REMOVAL (FEET)	
SEIBERT ROAD			
45+45.29	LT	12" CMP	25.0
46+10.27	LT	12" CMP	49.0
52+41.00	LT/RT	24" CMP	39.0
JOHNSON ROAD			
0+32.34	LT	18" CMP	37.0
1+10.34	RT	15" CMP	35.0
TOTAL:			185

PIPE CULVERT REMOVAL SCHEDULE - PHASE V			
LOCATION (STATION, DIRECTION)		PIPE CULVERT REMOVAL (FEET)	
SEIBERT ROAD			
25+49.48(AH)	RT	12" CMP	21.0
27+75.00	RT	12" CMP	16.0
TOTAL:			37

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE - PHASE III		
LOCATION (STATION TO STATION)	RAISED REFLECTIVE PAVEMENT MARKERS TWO-WAY AMBER (EACH)	
SEIBERT ROAD		
44+03.40	TO	58+13.25
		19
TOTAL:		19

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE - PHASE V		
LOCATION (STATION TO STATION)	RAISED REFLECTIVE PAVEMENT MARKERS TWO-WAY AMBER (EACH)	
SEIBERT ROAD		
24+53.74(BK)	TO	36+00.00
		16
TOTAL:		16

THERMOPLASTIC PAVEMENT MARKING SCHEDULE - PHASE III						
LOCATION (STATION TO STATION)	PAVEMENT MARKING REMOVAL (SQ. FT.)	4" MARKINGS SOLID YELLOW (FOOT)	12" MARKINGS SOLID WHITE (FOOT)	SHORT-TERM PAVEMENT MK (FOOT)	WORK ZONE PAVT. REM. (SQ. FT.)	
SEIBERT ROAD						
43+00	TO	58+53.25	3107		311	104
43+00	TO	44+03.40	117.0			
JOHNSON ROAD						
0+23.00	TO	2+03.96	362.0		36	12
0+23.00	TO	(STOP BAR)		19.0		
TOTAL:			117	3469	19	347

THERMOPLASTIC PAVEMENT MARKING SCHEDULE - PHASE V					
LOCATION (STATION TO STATION)	PAVEMENT MARKING REMOVAL (SQ. FT.)	4" MARKINGS SOLID YELLOW (FOOT)	SHORT-TERM PAVEMENT MK (FOOT)	WORK ZONE PAVT. REM. (SQ. FT.)	
SEIBERT ROAD					
25+00(BK)	TO	36+00		74	
25+00(BK)	TO	25+53.74(BK)	97.0		
35+00	TO	36+00	177.0		
TOTAL:			275	2,200	74

CURB AND GUTTER SCHEDULE - PHASE III		
LOCATION (STATION TO STATION)	COMBINATION CURB & GUTTER, TYPE B 6.24 (FOOT)	
SEIBERT ROAD		
44+03.40	LT	TO 57+76.25
44+03.40	RT	TO 55+82.65
56+60.45	RT	TO 57+76.25
JOHNSON ROAD		
0+38.18	LT	TO 1+73.96
1+26.31	RT	TO 1+73.96
		RADIUS RETURN LT
		RADIUS RETURN RT
TOTAL:		3004

CURB AND GUTTER SCHEDULE - PHASE V		
LOCATION (STATION TO STATION)	COMBINATION CURB & GUTTER, TYPE B 6.24 (FOOT)	
SEIBERT ROAD		
25+15.53(AH)	TO	35+00.00
25+15.53(AH)	TO	35+00.00
TOTAL:		1,969

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

SCHEDULE OF QUANTITIES
SEIBERT ROAD
RECONSTRUCTION - PH. III + V
VILLAGE OF SHILOH
ST. CLAIR COUNTY, ILLINOIS

REV.	DATE	DESCRIPTION

DRAWN BY: JWS	SHEET
DESIGNED BY: JWS	5
CHECKED BY: AJE	OF 79 SHEETS
APPROVED BY: SJK	PROJECT DESCRIPTION
PROJECT NUMBER: 120-010479	SEIBERT ROAD RECONSTRUCTION
<input checked="" type="checkbox"/> ISSUED FOR REVIEW	<input type="checkbox"/> ISSUED FOR BIDDING
<input type="checkbox"/> ISSUED FOR CONSTR.	<input type="checkbox"/> RECORD DRAWING

PLOT DATE = 2/19/2009
 FILE NAME = P:\004799\004799\DOT PHASE III - TWM PHASE V\phase v\0184799-SCHD-PH5.dgn
 PLOT SCALE = 28.0000 / IN.
 USER NAME = jstein