ENTRANCE CULVERTS

LOCATION STATION TO STATION	EXISTING ENTRANCE INFORMATION		PIPE CULVERTS, CLASS D,		END SECTIONS 375MM	REMARKS
			TYPE 1 375 MM	TYPE 2 375 MM		
	TYPE	SURFACE	METER	METER	EACH	
IL 146						
RT STA 13+086.	FER	EARTH	7.9		2.0	
LT STA 3+086.	FEL	EARTH	8.5		2.0	
RT STA 13+220.	FER	EARTH				RELOCATE TO STA 13+086
LT STA 3+220.	FEL	EARTH				RELOCATE TO STA 3+086
LT STA 3+445.	PEL	AGGREGATE	12.2		2.0	
RT STA 13+445.	FER	EARTH		20.4	2.0	
RT STA 3+459.	FER	EARTH				RELOCATE TO STA 13+445
LT STA 3+575.	FEL	EARTH				
RT STA 13+575.	FER	EARTH				REMOVE
RT STA 13+787.	FER	EARTH		20.1	2.0	
RT STA 14+079. REIMAN RD	SRR	OIL & CHIP				
LT STA 4+079. GERARD RD	SRL	AGGREGATE				
LT STA 4+297.	PEL	AGGREGATE		11.6	2.0	
RT STA 14+301.	FER	AGGREGATE		16.2	2.0	
RT STA 14+725.	FER	EARTH				
LT STA 4+717.	FEL	EARTH				
RT STA 14+900.	FER	EARTH		17.7	2.0	
LT STA 4+890.	FEL	EARTH				
RT STA 15+174.	FER	EARTH	8.8		2.0	
LT STA 5+175.	FEL	EARTH	8.8		2.0	
RT STA 15+270.	FER	EARTH				RELOCATE TO STA 15+174
LT STA 5+270.	FEL	EARTH				RELOCATE TO STA 5+175
RT STA 15+550.	FER	EARTH				
RT STA 15+570.	FER	EARTH				RELOCATE TO STA 15+550
LT STA 5+570.	FEL	EARTH				
LT STA 5+680.	FEL	EARTH				RELOCATE TO STA 5+570
RT STA 15+784.	FER	EARTH	13.1		2.0	
RT STA 15+804.	CER	AGGREGATE				RELOCATE TO STA 15+784
RT STA 15+944.1 CONIFER LN	CER	OIL & CHIP				REMOVE
IL 146 PROJECT TOTAL			59.3	86.0	22.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 10/24/2008
FILE NAME = c:\pw_work\PWIDOT\KRANZJC\dms43642\d825949sch.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc