

SUMMARY OF QUANTITIES

FAP 885 (IL 146)
100% FED.
JOHNSON COUNTY
CONSTRUCTION TYPE CODE 1000

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	10,820.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,592.0
40600300	AGGREGATE (PRIME COAT)	TON	193.2
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	115.2
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90	TON	10,820.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	128,810.0
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	8.1
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	862.3
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	23.3
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	642.0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	89,352.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,099.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12.0
63200310	GUARDRAIL REMOVAL	FOOT	300.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	5,361.0
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	145,035.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	49,631.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	145,035.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	563
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	563

**Specialty Items*