

## EROSION CONTROL SCHEDULE

SN 035-0015 LOCATION STATION TO STATION	EROSION CONTROL BLANKET	STONE RIPRAP CLASS A3	PERIMETER EROSION BARRIER	TEMPORARY DITCH CHECKS	INLET PIPE PROTECTION	FILTER FABRIC
	SQ YD	SQ YD	FOOT	EACH	EACH	SQ YD
FAP 889 (IL 34/146)						
PRE- STAGE 1						
STA. 70+78 60' LT TO STA. 76+00 77' LT			560			
STA. 73+93 60' LT TO STA. 76+45 45' LT		787				787
STA. 76+23 58' LT				1		
STAGE 1						
STA. 70+78 17' RT TO STA. 74+12 22' RT	505					
STA. 73+46 28' RT					1	
STA. 74+08 70' RT TO STA. 76+62 58' RT			250			
STA. 74+24 26' RT TO STA. 76+50 37' RT	825					
STA. 74+94 53' RT				1		
STA. 77+18 25' RT TO STA. 82+82 25' RT	562					
STA. 77+18 40' RT TO STA. 82+82 31' RT			514			
STA. 78+23 29' RT				1		
STA. 79+59 26' RT					1	
STA. 82+54 26' RT					1	
STAGE 2						
STA. 70+78 13' LT TO STA. 73+50 16' LT	114					
STA. 73+50 13' LT TO STA. 76+38 38' LT	804					
STA. 77+21 19' LT TO STA. 82+82 13' LT	642					
STA. 77+21 37' LT TO STA. 82+82 38' LT			564			
STA. 80+00 31' LT				1		
<b>TOTAL</b>	<b>3444</b>	<b>787</b>	<b>1888</b>	<b>4</b>	<b>3</b>	<b>787</b>

## TREE REMOVAL

SN 035-0015 LOCATION STATION	OFFSET FROM E.P.	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
	FEET	UNIT	UNIT
76+50	30' RT.	12	
77+40	24' RT.	12	18
<b>TOTAL</b>		<b>24</b>	<b>18</b>

## SIDEROAD SCHEDULE

SN 035-0015 LOCATION STATION TO STATION	PIPE CULVERTS CLASS D TY. 2 15"	PIPE CULVERTS REMOVAL	END SECTIONS 15"	RELOCATE EXISTING MAILBOX	AGGREGATE SHOULDERS TYPE A, 6'	AGGREGATE SURF. CSE TYPE A, 6'
	FEET	FEET	EACH	EACH	TON	SQ YD
STA. LT 73+22				2	9	
STA. RT 73+71.9	57	57	2			58
STA. LT 80+18				1	9	
<b>TOTALS</b>	<b>57</b>	<b>57</b>	<b>2</b>	<b>3</b>	<b>18</b>	<b>58</b>

## PAVING SCHEDULE

SN 035-0015 LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE COURSE MIX C, N90	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N90	HOT-MIX ASPHALT BASE COURSE WIDENING 10"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SHOULDERS, 8"	HOT-MIX ASPHALT SHOULDERS, 10"	AGGREGATE SHOULDERS, TYPE A 8"	BRIDGE APPROACH PAVEMENT
	TON	TON	GALLON	TON	TON	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.
PRE STAGE 1									
STA. 74+88.00 TO STA. 75+47.99 LT			20						
STA. 77+61.60 TO STA. 78+82.00 LT			40						
STAGE 1									
STA. 70+78.00 TO STA. 73+99.41 RT						167		108	
STA. 70+78.00 TO STA. 76+07.00 RT	54	101		138	2.5				
STA. 75+55.00 TO STA. 76+48.85 RT						43			
STA. 76+15.92 TO STA. 76+48.68 RT									56
STA. 76+46.04 TO STA. 77+47.04 RT									56
STA. 77+17.22 TO STA. 78+05.00 RT							41		
STA. 77+53.00 TO STA. 82+82.00 RT	54	86		138	2.5			133	
STA. 78+84.50 TO STA. 82+82.00 RT						97			
STA. 78+05.00 TO STA. 82+82.00 RT									
STAGE 2									
STA. 70+78.00 TO STA. 73+52.16 LT								92	
STA. 70+78.00 TO STA. 75+15.00 LT						137			
STA. 70+78.00 TO STA. 76+07.00 LT	54	65		138	2.5				
STA. 75+15.00 TO STA. 76+43.29 LT						67			
STA. 76+13.19 TO STA. 76+16.00 LT									56
STA. 77+10.59 TO STA. 78+50.00 LT						72			
STA. 77+10.99 TO STA. 77+52.96 LT									56
STA. 77+53.00 TO STA. 82+82.00 LT	54	93		138	2.5				
STA. 78+50.00 TO STA. 82+82.00 LT						125			
STA. 79+91.29 TO STA. 82+82.00 LT								96	
<b>TOTALS</b>	<b>216</b>	<b>345</b>	<b>60</b>	<b>552</b>	<b>10</b>	<b>526</b>	<b>223</b>	<b>429</b>	<b>224</b>

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES IL 34 /146 OVER THREE MILE CREEK</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			885	5B-1	HARDIN	48	7	
		CHECKED -	REVISED -			CONTRACT NO. 98949					
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
				SCALE: _____		SHEET NO. _____ OF _____ SHEETS		STA. _____ TO STA. _____			