ROADWAY SCHEDULE

LOCATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE BASE COURSE TYPE A	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	LEVELING BINDER (MACHINE METHOD) N50	HOT MIX ASPHALT SURFACE REMOVAL BUTT-JOINT	TEMPORARY RAMP	HOT MIX ASPHALT SURFACE COURSE MIX C, N50	INCIDENTAL HOT MIX ASPHALT SURFACING	AREA REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	AGGREGATE SHOULDERS TYPE B
		8"	0.1 GAL/SY	0.4 GAL/SY		1.5" MIN			1.5" MIN			6"
	21001000	35100100	40600100	40600100	40600300	40600625	40600982	40600990	40603310	40800050	44300300	48101200
	SQ YD	TON	GAL	GAL	TON	TON	SQ YD	SQ YD	TONS	TONS	SQ YD	TONS
FAS 824 (CH42)												
STA. 7+10 TO STA. 9+55	446	129	18	169	0.4	33	156	11	46		367	114
STA. 10+35 TO STA. 12+90	554	239	1	210	0.2	41	78	11	48		456	127
CR 150 N							39	28		7		
SUB TOTAL	1000	368	19	379	0.6	74	273	50	94	7	823	241
GRAND TOTAL	1000	368	398		0.6	74	273	50	94	7	823	241
USE	1000	370	400		1	75	275	50	95	7	823	245

SEEDING SCHEDULE

LOCATION	CLASS 2 SPECIAL
	25001000
	ACRE
FAS 824 /CH42	
STA 7+10 TO STA 9+55	0.30
STA 10+35 TO STA 12+90	0.30
TOTAL PROJECT	0.60

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	CHANNEL EXCAVATION	SHRINKAGE FACTOR	PERCENT USED	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT REQUIRED	EARTHWORK BALANCE
	20200100	20300100					
	CU.YD.	CU.YD.			CU.YD.	CU.YD.	CU.YD.
FAS 824 /CH42							
STA 7+10 TO STA 9+55	20		25.00%	100.00%	15	289	-274
STA 10+35 TO STA 12+90	10		25.00%	100.00%	8	891	-883
							0
CHANNEL EXCAVATION		165	25.00%	70.00%	87		87
							0
TOTAL	30	165			110	1180	-1070
TOTAL USE	30	165					-1070

20400800 FURNISHED EXCAVATION = 1070 CU YDS

CULVERT SCHEDULE

LOCATION	TYPE	EXIST SIZE	PIPE CULVERTS TYPE 1 RCCP 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"
			54200439	54213669
			FOOT	EACH
FAS 824 (CH42)				
CL STA. 11+24.41	AR	24" RCCP	5	2
CL STA. 11+73.78	AR	24" RCCP		2
TOTAL			5	4

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING PERMAMENT 4" SINGLE WHITE EDGE LINE	4" SOLID YELLOW CENTERLINE	PAVEMENT MARKING REMOVAL
	78000200		78300100
	FOOT	FOOT	SQ FT
FAS 824 (CH42) SPRING GARDEN ROAD			
LT. STA. 7+10 TO LT. STA. 12+90	580		47
LCL. STA. 7+10 TO LCL. STA. 12+90		580	47
RCL. STA. 7+10 TO RCL. STA. 12+90		580	47
RT. STA. 8+00 TO RT. STA. 12+90	490		17
SUBTOTAL	1070	1160	158
TOTAL	2230		158

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A 9 FOOT POSTS	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 5A	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS
	63000003	63100167	63100075	78201000	78200405
	FOOT	EACH	EACH	EACH	EACH
FAS 842 (CH42)					
RT. STA. 7+97.72 TO RT. STA. 9+51.61	87.5	1	1	1	
LT. STA. 8+773.28 TO LT. STA. 9+64.67	25	1	1	1	
RT. STA. 10+25.33 TO RT. STA. 11+16.72	25	1	1	1	
LT. STA. 10+38.39 TO LT. STA. 11+79.78	75	1	1	1	
RT. STA. 7+97.72 TO RT. STA. 11+16.72					5
LT. STA. 8+773.28 TO LT. STA. 11+79.78					5
TOTAL	212.5	4	4	4	10