


SUMMARY OF QUANTITIES

PHASE II CONSTRUCTION - SUMMARY OF QUANTITIES

Item Number	Item Description	Unit of Measure	Quantity
AR150510	ENGINEER'S FIELD OFFICE	LUMP SUM	1.0
AR152410	UNCLASSIFIED EXCAVATION	CUBIC YARD	25,350.0
AR152460	TOPSOIL STRIPPING	CUBIC YARD	8,600.0
AR156510	SILT FENCE	LINEAR FOOT	3,772.4
AR156511	DITCH CHECK	EACH	9.0
AR156544	RIPRAP - GRADATION NO. 4	SQUARE YARD	98.7
AR208606	6" AGGREGATE BASE COURSE	SQUARE YARD	2,556.0
AR208608	8" AGGREGATE BASE COURSE	SQUARE YARD	3,339.3
AR401650	BITUMINOUS PAVEMENT MILLING	SQUARE YARD	546.0
AR401665	BITUMINOUS PAVEMENT SAWING	LINEAR FOOT	1,322.0
AR401900	REMOVE BITUMINOUS PAVEMENT	SQUARE YARD	11,538.0
AR602510	BITUMINOUS PRIME COAT	GALLON	10,200.0
AR603510	BITUMINOUS TACK COAT	GALLON	12,948.0
AR620530	PAVEMENT MARKING - EPOXY	SQUARE FOOT	850.0
AR701512	12" RCP, CLASS IV	LINEAR FOOT	96.0
AR701515	15" RCP, CLASS IV	LINEAR FOOT	47.0
AR701900	REMOVE PIPE	LINEAR FOOT	284.6
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	6.0
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH	4.0
AR752512	GRATING FOR CONC. FES 12"	EACH	6.0
AR752515	GRATING FOR CONC. FES 15"	EACH	4.0
AR803002	SEEDING- MIXTURE 2A	ACRE	2.9
AR803003	SEEDING, NATIVE MIX	ACRE	0.4
AR803004	CLEARING TREE 0-6" DBH	EACH	4.0
AR803005	CLEARING TREE 6"-15" DBH	EACH	5.0
AR803006	CLEARING TREE OVER 15" DBH	EACH	5.0
AR803007	STUMP REMOVAL 0-6" DBH	EACH	4.0
AR803008	STUMP REMOVAL 6"-15" DBH	EACH	5.0
AR803009	STUMP REMOVAL OVER 15" DBH	EACH	5.0
AR803013	EROSION MAT - DITCH BOTTOM	SQUARE YARD	57.7
AR803018	CONSERVATION COVER	ACRE	4.0
AR803019	HMA SURFACE MIX "D", N70, PG 64-22	TON	1,567.0
AR803021	HMA BINDER IL-19, N70, PG 64-22	TON	2,605.0
AR803022	HMA BASE COURSE, PG 58-22, 8"	SQUARE YARD	19,686.0
AR803023	HMA SURFACE MIX "C", N50, PG 58-22	TON	611.9
AR803024	HOT-MIX ASPHALT SHOULDERS, 8"	SQUARE YARD	3,474.0
AR803025	SUBBASE GRANULAR MAT., TYPE B, 4"	SQUARE YARD	18,694.0
AR803026	SUBBASE GRANULAR MAT., TYPE B, 7.75"	SQUARE YARD	4,429.0
AR803027	AGGREGATE SHOULDERS, TYPE B, 8"	SQUARE YARD	3,648.0
AR803028	CONSTRUCTING TEST STRIP	EACH	4.0
AR803031	GROOVED 4" LINE HP PAVEMENT TAPE	LINEAR FOOT	19,810.0
AR803032	GROOVED 6" LINE HP PAVEMENT TAPE	LINEAR FOOT	1,623.0
AR803033	HOT INLAID 24" LINE HP PVT TAPE	LINEAR FOOT	40.0
AR803034	HOT INLAID 12" LINE HP PVT TAPE	LINEAR FOOT	370.0
AR803035	HOT INLAID LETTERS & SYMBOLS, HP TAPE	SQUARE FOOT	440.0
AR803036	CHANGEABLE MESSAGE SIGN	CAL MO	16.0
AR803037	SIGN PANEL	SQUARE FOOT	246.0
AR803038	METAL POST - TYPE B	LINEAR FOOT	708.0
AR803039	REMOVE FENCE	LINEAR FOOT	2,816.0
AR803040	IDOT SPEC X0322256 - TEMP INFO SIGNING	SQUARE FOOT	51.0
AR803041	IDOT SPEC X7012620 - TR CONT & PROT 701501	LUMP SUM	1.0
AR803042	IDOT SPEC 70300825 TEMP PT PVT MK 4 YEL	LINEAR FOOT	3,600.0
AR803043	IDOT SPEC 70300725 TEMP PT PAVT MK 4 WH	LINEAR FOOT	3,500.0
AR803044	IDOT SPEC 70300320 PAVT MARK TAPE T1 4	LINEAR FOOT	300.0
AR803045	IDOT SPEC X7012622 TR CONT & PROT 701502	LUMP SUM	1.0
AR803046	IDOT SPEC X7010530 TC-PROT 701306 SPL	LUMP SUM	1.0
AR904510	SODDING	SQUARE YARD	2,246.0
AR905510	TOPSOILING (FROM ON SITE)	CUBIC YARD	4,000.0
AR908510	MULCHING	ACRE	7.3
AR910915	REMOVE ROADWAY SIGN	EACH	11.0

Hanson Professional Services Inc.
 Suite 200, 815 Commerce Drive
 Oak Brook, Illinois 60523
 © Copyright Hanson Professional Services Inc. 2009



FILE NAME = I:\05\Jobs\00841\058802\Civil Part B\Sheets\VC-SUM-QUANT.SHT
 PLOT SCALE = 2.0000' / IN.
 PLOT DATE = 03/21/09, 10:47 AM

USER NAME = Blair01219
 DESIGNED -
 DRAWN -
 CHECKED - BLB
 DATE - 05/21/08

REVISED -
 REVISED -
 REVISED -
 REVISED -

**VILLAGE OF
LAKE IN THE HILLS, ILLINOIS**

SUMMARY OF QUANTITIES

SCALE:

COUNTY	TOTAL SHEETS	SHEET NO.
MCHENRY	143	3

AIP NO. 3-17-0112-B10 ILLINOIS IDA NO. 3CR-3807