	Proposal Submitted By
LETTING DATE April 24, 2009	Name
ITEM NUMBER 15A	
	Address
	City/State
	9 Digit Zip Code Telephone Number
	FEIN Number FAX Number
	E-Mail Address
those companies that read of the companies that	
는 글   AIRPORT Quad City II	
MUNICIPAL DESIGNATION	
COUNTY DESIGNATION ILLINOIS PROJECT NO	
ILLINOIS PROJECT NO	D. <u>MLI-3854</u>
FEDERAL PROJECT N	IO. <u>3-17-0068-XX</u>
FEDERAL PROJECT N  For engineering informat  Stanley & Associates at (	tion, contact Denny Martin of Missman, (309) 788-7644.
FAA rules prohibit the use of escalation clauses for materials. Therefore, the Division of Aeronautics cannot offer a bituminous material cost adjustment	PLEASE MARK THE APPROPRIATE BOX BELOW:  A Bid Bond is included.

A Cashier's Check or a Certified Check is included.

provision for projects utilizing federal

funds.

#### **INSTRUCTIONS**

**ABOUT IDOT PROPOSALS**: All proposals issued by IDOT are potential bidding proposals. Each proposal contains all Certifications and Affidavits, a Proposal Signature Sheet and a Proposal Bid Bond required for Prime Contractors to submit a bid after written **Authorization to Bid** has been issued by IDOT's Central Bureau of Construction.

**HOW MANY PROPOSALS SHOULD PROSPECTIVE BIDDERS REQUEST**?: Prospective bidders should, prior to submitting their initial request for plans and proposals, determine their needs and request the total number of plans and proposals needed for each item requested. There will be a nonrefundable charge of \$15 for each set of plans and specifications issued.

WHO CAN BID?: Bids will be accepted from only those companies that request and receive written Authorization to Bid from IDOT's Central Bureau of Construction.

WHAT CONSTITUTES WRITTEN AUTHORIZATION TO BID?: When a prospective prime bidder submits a "Request for Proposal Forms and Plans" he/she must indicate at that time which items are being requested For Bidding purposes. Only those items requested For Bidding will be analyzed. After the request has been analyzed, the bidder will be issued a **Proposal Denial and/or Authorization Form**, approved by the Central Bureau of Construction, that indicates which items have been approved For Bidding. If **Authorization to Bid** cannot be approved, the **Proposal Denial and/or Authorization Form** will indicate the reason for denial. If a contractor has requested to bid but has not received a **Proposal Denial and/or Authorization Form**, they should contact the Central Bureau of Construction in advance of the letting date.

**WHAT MUST BE INCLUDED WHEN BIDS ARE SUBMITTED**?: Bidders need not return the entire proposal when bids are submitted. That portion of the proposal that must be returned includes the following:

- 1. All documents from the Proposal Cover Sheet through the Proposal Bid Bond
- 2. Other special documentation and/or information that may be required by the contract special provisions

All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed by IDOT personnel.

**ABOUT SUBMITTING BIDS**: It is recommended that bidders deliver bids in person to insure they arrive at the proper location prior to the time specified for the receipt of bids. Any bid received at the place of letting after the time specified will not be accepted.

#### WHO SHOULD BE CALLED IF ASSISTANCE IS NEEDED?

Questions Regarding	Call
Prequalification and/or Authorization to Bid	217/782-3413
Preparation and submittal of bids	217/782-7806
Mailing of plans and proposals	217/782-7806



**PROPOSAL** 

1.	Proposal of	I KOI OSAI
	•	

for the improvement officially known as:

- (a) Quad City International Airport
- (b) The proposed improvement shown in detail on the plans issued by the Department schedule and detail sheets included herein, includes, in general, the following described work:

#### Taxiway P, Phase II - Middle Paving

#### TO THE DEPARTMENT OF TRANSPORTATION

The plans for the proposed work are those issued by the Department of Transportation to cover the work described above.

The specifications are those prepared by the Department of Transportation, Division of Aeronautics and designated as "Standard Specifications for Construction of Airports," adopted January, 1985, the "Supplemental Specifications and Recurring Special Provisions," adopted July 1, 2004 and the "Special Provisions" thereto, adopted and in effect on the date of invitation for bids.

3. **COMPLETION TIME/LIQUIDATED DAMAGES**. It being understood and agreed that the completion within the time limit is an essential part of the contract, the bidder agrees to complete the Base Bid work within 181 calendar days, unless additional time is granted by the Engineer in accordance with the provisions of the specifications. If Additive Alternate No. 1 is awarded, an additional 14 calendar days will be granted. If Additive Alternate No. 2 is awarded, an additional 22 calendar days will be granted. In case of failure to complete the work on or before the time named herein, or within such extra time as may have been allowed by extensions, the bidder agrees that the Department of Transportation shall withhold from such sum as may be due him/her under the terms of this contract, the costs, as set forth below, which costs shall be considered and treated not as a penalty but as damages due to the State from the bidder by reason of the failure of the bidder to complete the work within the time specified in the contract. The following Schedule of Deductions supersedes the table given in Section 60-09 of the Division's Standard Specifications for Construction of Airports.

# Schedule of Deductions for Each Day of Overrun in Contract Time

Original Cont	ract Amount	Daily Charge
From More Than	To and Including	Calendar <u>Day</u>
\$ 0	\$ 25,000	\$ 300
25,000	100,000	375
100,000	500,000	550
500,000	1,000,000	725
1,000,000	2,000,000	900
2,000,000	3,000,000	1,100
3,000,000	5,000,000	1,300
5,000,000	7,500,000	1,450
7,500,000	10,000,000	1,650

A daily charge shall be made for every day shown on the calendar beyond the specified contract time in calendar days.

- 4. ASSURANCE OF EXAMINATION AND INSPECTION/WAIVER. The undersigned further declares that he/she has carefully examined the proposal, plans, specifications, supplemental and applicable recurring special provisions, form of contract and contract bonds, and special provisions, and that he/she has inspected in detail the site of the proposed work, and that he/she has familiarized themselves with all of the local conditions affecting the contract and the detailed requirements of construction, and understands that in making this proposal he/she waives all right to plead any misunderstanding regarding the same.
- 5. **EXECUTION OF CONTRACT AND CONTRACT BONDS.** The undersigned further agrees to execute a contract for this work and present the same to the department within fifteen (15) days after the contract has been mailed to him/her. The undersigned further agrees that he/she and his/her surety will execute and present within fifteen (15) days after the contract has been mailed to him/her contract bonds satisfactory to and in the form prescribed by the Department of Transportation, in the penal sum of the full amount of the contract, guaranteeing the faithful performance of the work in accordance with the terms of the contract and guaranteeing payment in full all bills and accounts for materials and labor used in the construction of the work.
- **6. PROPOSAL GUARANTY.** Accompanying this proposal is either a bid bond on the department form, executed by a corporate surety company satisfactory to the department, or a proposal guaranty check consisting of a bank cashier's check or a properly certified check for not less than 5 per cent of the amount bid or for the amount specified in the following schedule:

	Amount	Proposal of Bid Guaranty	<u>.</u>	amount o	Propo of Bid Guara	
Up to		\$5,000\$150	\$2,000,000	to	\$3,000,000\$100,	000
\$5,000	to	\$10,000\$300	\$3,000,000	to	\$5,000,000\$150,	000
\$10,000	to	\$50,000\$1,000	\$5,000,000	to	\$7,500,000\$250,	000
\$50,000	to	\$100,000\$3,000	\$7,500,000	to	\$10,000,000\$400,	000
\$100,000	to	\$150,000\$5,000	\$10,000,000	to	\$15,000,000\$500,	000
\$150,000	to	\$250,000\$7,500	\$15,000,000	to	\$20,000,000\$600,	000
\$250,000	to	\$500,000\$12,500	\$20,000,000	to	\$25,000,000\$700,	000
\$500,000	to	\$1,000,000\$25,000	\$25,000,000	to	\$30,000,000\$800,	000
\$1,000,000	to	\$1,500,000\$50,000	\$30,000,000	to	\$35,000,000\$900,	000
\$1,500,000	to	\$2,000,000\$75,000	over		\$35,000,000\$1,000,	000

Bank cashier's checks or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois, when the state is awarding authority; the county treasurer, when a county is the awarding authority; or the city, village, or town treasurer, when a city, village, or town is the awarding authority.

If a combination bid is submitted, the proposal guaranties which accompany the individual proposals making up the combination will be considered as also covering the combination bid.

Attach Cashier's Check or C	ertified Check Here
In the event that one proposal guaranty check is intended to cover sum of the proposal guaranties which would be required for each indiviproposal, state below where it may be found.	• •
The proposal guaranty check will be found in the proposal for:	Item

#### Mark the proposal cover sheet as to the type of proposal guaranty submitted.

7. COMBINATION BIDS. The undersigned further agrees that if awarded the contract for the sections contained in the following combination, he/she will perform the work in accordance with the requirements of each individual proposal comprising the combination bid specified in the schedule below, and that the combination bid shall be prorated against each section in proportion to the bid submitted for the same. If an error is found to exist in the gross sum bid for one or more of the individual sections included in a combination, the combination bid shall be corrected as provided below.

A combination bid is a total bid received on 2 or more proposals. No combination bids other than those specifically set up by the Department will be considered. Separate proposal forms will be issued for each project in the combination so bids may be submitted on the combination as well as on separate units of the combination. The Department reserves the right to make awards on combination bids or separate bids to the best advantage of the Department.

If a combination bid is submitted on 2 or more proposals, separate proposals on each individual contract shall also be submitted, and unless separate proposals are so submitted, the combination bid will not be considered. If the bidder desires to submit a combination bid, the bidder shall state, in the place provided in the proposal form, the amount of the combination bid for the entire combination.

If a combination bid is submitted on any stipulated combination, and errors are found to exist in computing the gross sum bid on any one or more of the individual proposals, corrections shall be made, by the Department and the amount of the combination bid shall be corrected so that it will be in the same proportion to the sum of the corrected gross sum bid as the combination bid submitted was to the sum of the gross sum bid submitted.

The following provisions shall govern combination bidding:

- (a) A combination bid which is submitted for 2 or more proposals and awarded on that basis shall have the bid prorated against each proposal in proportion to the bid submitted for each proposal.
- (b) Separate contracts shall be executed for each individual proposal included in the combination.
- (c) The contract time for all contracts awarded on a combination bid shall be the sum of all calendar days contained within each contract included in the combination, unless otherwise provided in the contracts.
- (d) In the event the Contractor fails to complete any or all of the contracts on the combination bid within the contract time, including any authorized extension, the liquidated damages shall be determined from the schedule of deductions shown above in paragraph 3 for each day of overrun in contract time, based on the combination bid total, and shall be computed on the combination and prorated against the 2 or more individual contracts based on the dollar value of each contract.

(e) The plans and Special Provisions for each separate contract shall be construed separately for all requirements, except as described in paragraphs (a) through (d) listed above.

When a combination bid is submitted, the schedule below must be completed in each proposal comprising the combination.

If alternate bids are submitted for one or more of the sections comprising the combination, a combination bid must be submitted for each alternate.

#### **Schedule of Combination Bids**

Combination		Combination E	Bid
No.	Sections Included in Combination	Dollars	Cents

8. **SCHEDULE OF PRICES.** The undersigned submits herewith his/her schedule of prices covering the work to be performed under this contract; he/she understands that he/she must show in the schedule the unit prices (with no more than two decimal places, i.e. \$25.35, not \$25.348) for which he/she proposes to perform each item of work, that the extensions must be made by him/her, and that if not so done his/her proposal may be rejected as irregular.

The undersigned further agrees that the unit prices submitted herewith are for the purpose of obtaining a gross sum, and for use in computing the value of additions and deductions; that if there is a discrepancy between the gross sum bid and that resulting from the summation of the quantities multiplied by their respective unit prices, the latter shall govern.

STATE JOB #-

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

RUN DATE - 04/02/09 RUN TIME - 183321

1	COUNTY NAME CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
	ROCK ISLAND 161	02	QUAD-CITY INTERNATIONAL	3-17-0068-XX	ML-I -3854

\*\*\*\*\* BASE \*\*\*\*\*

ITEM		UNIT OF		UNIT PRIC		TOTAL PRICE	
NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS	CENTS	DOLLARS	CTS
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	8,540.000	(	=		
AR108258	2/C #8 5 KV UG CABLE IN UD	L.F.	3,580.000	(	=		
AR108962	REPLACE CABLE	L.F.	950.000	(	=		
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	670.000	(	=		
AR110901	CONCRETE DUCT REMOVAL	L.F.	260.000	(			
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2.000	(	=		
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2.000	(	=		
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2.000	(	=		
AR125510	MIRL, BASE MOUNTED	EACH	2.000	(	=		
AR125520	HIRLQ, BASE MOUNTED	EACH	1.000	(	=======================================		
AR125565	SPLICE CAN	EACH	2.000	(	=		
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	7.000	( 			
AR125903	REMOVE INPAVEMENT LIGHT	EACH	1.000 >	(	=		
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	8.000	(			
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	7.000	( 	=		

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE DOLLARS CTS
AR125944	ADJUST TAXI GUIDANCE SIGN	EACH	2.000 X	:	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	68.000 X	( :	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000 X	ζ :	
AR150530	TRAFFIC MAINTENANCE	L.S.	1.000 X	(	
AR151450	CLEARING AND GRUBBING	ACRE	2.500 X	(	=
AR152410	UNCLASSIFIED EXCAVATION	С.Ү.	15,825.000 X	ζ :	-   -
AR152441	ON-SITE BORROW	С.Ү.	34,800.000 X	ζ :	-     -
AR152442	OFFSITE BORROW EXCAVATION	С.Ү.	46,600.000 X	(	
AR156500	TEMPORARY EROSION CONTROL	L.S.	1.000 X	(	
AR156540	RIPRAP	S.Y.	410.000 X	(	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	16,795.000 X	(	
AR209600	GEOTEXTILE FABRIC	S.Y.	20,641.000	<	
AR401610	BITUMINOUS SURFACE COURSE	TON	6,140.000 X	:	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1.000 X	:	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	1,175.000 X	ζ :	=

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE DOLLARS CTS
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	14,900.000	=	
AR501512	12" PCC PAVEMENT	S.Y.	20,124.000	\ \ 	=
AR501530	PCC TEST BATCH	EACH	1.000 >	\ \ !	
AR501540	PCC PAVEMENT GROOVING	S.Y.	9,345.000	\ \ 	
AR501900	REMOVE PCC PAVEMENT	S.Y.	10,800.000	X =	
AR602510	BITUMINOUS PRIME COAT	GAL.	3,735.000	( = = = = = = = = = = = = = = = = = = =	
AR603510	BITUMINOUS TACK COAT	GAL.	123.000	X =	
AR620510	PAVEMENT MARKING	S.F.	9,700.000	X =	
AR701442	42" RCP, CLASS III	L.F.	535.000	X :	
AR701512	12" RCP, CLASS IV	L.F.	126.000	X =	
AR701524	24" RCP, CLASS IV	L.F.	895.000	X =	
AR701713	RCEP SPAN 30 RISE 19	L.F.	302.000	X =	
AR701900	REMOVE PIPE	L.F.	160.000	X =	
AR705506	6" PERFORATED UNDERDRAIN	L.F.	3,108.000	X =	
AR751410	INLET	EACH	1.000	X =	
					THE RESERVE THE PROPERTY OF THE PERSON NAMED IN COLUMN 1

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMS002 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

ITEM		UNIT OF		UNIT PRICE		TOTAL PRICE	Married Control of the Control of th
NUMBER_	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS C	ENTS	DOLLARS	CTS
AR751415	INLET-SPECIAL	EACH	4.000	(	=		
AR751540	MANHOLE 4'	EACH	2.000	(	=		
AR751550	MANHOLE 5'	EACH	5.000	(	=		
AR751560	MANHOLE 6'	EACH	1.000 >	(	=		
AR751570	MANHOLE-SPECIAL	EACH	4.000	(	=		
AR751903	REMOVE MANHOLE	EACH	2.000 >	(	=		
AR751906	REMOVE CATCH BASIN	EACH	1.000 >	(,	<u> </u> 		
AR751945	ADJUST MANHOLE - NON PAVEMENT	EACH	2.000	(	=		
AR751963	RELOCATE MANHOLE	EACH	1.000	(	=		
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	1.000	<	=		
AR752442	PRECAST REINFORCED CONC. FES 42"	EACH	1.000	<	=		
AR752724	P R CONC. FES EQ. ROUND SIZE 24"	EACH	1.000	(	=		
AR752900	REMOVE END SECTION	EACH	1.000	(	=		
AR801605	REPLACE TAXI GUIDANCE SIGN PANEL	EACH	60.000	(	=		
AR801628	RELOCATE TAXI GUIDANCE SIGN	EACH	8.000 >	(	=		

### ILLINOIS DEPARTMENT OF TRANSPORTATION ECMSO02 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

ITEM		UNIT OF		UNIT PRI	CE	TOTAL PRIC	CE
NUMBER	PAY ITEM DESCRIPTION	<u>MEASURE</u>	QUANTITY	DOLLARS	CENTS	DOLLARS	CTS
AR901510	SEEDING	ACRE	35.000	(			
AR908513	MULCHING-METHOD 3	ACRE	35.000	( 	=		
AR908520	EXCELSIOR BLANKET	S.Y.	1,500.000	( 			
				SUBTOTAL	BASE 9		_!

<sup>\*\*\*</sup>THE DEPARTMENT RESERVES THE RIGHT TO AWARD THIS CONTRACT ON THE \*\*\*BASIS OF ANY OF THE ALTERNATES OR COMBINATION THEREOF.

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMSO02 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

RUN DATE - 04/02/09 RUN TIME - 183321

\*\*\*\*\* ALT 1 \*\*\*\*\*

ITEM		UNIT OF		UNIT PRICE	TOTAL PRICE
NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS CENT	S DOLLARS CTS
AS108158	1/C #8 5 KV UG CABLE IN UD	L.F.	725.000		_
AS108258	2/C #8 5 KV UG CABLE IN UD	L.F.	595.000 >	( 	=
AS110502	2-WAY CONCRETE ENCASED DUCT	L.F.	115.000	( (	=
AS125448	TAXI GUIDANCE SIGN, 8 CHARACTER	EACH	1.000 >	\ \ 	=
AS125510	MIRL, BASE MOUNTED	EACH	6.000	( (	=
AS152410	UNCLASSIFIED EXCAVATION	С.Ү.	175.000	X 	=
AS209510	CRUSHED AGGREGATE BASE COURSE	TON	3,410.000	X 	=
AS209600	GEOTEXTILE FABRIC	S.Y.	5,847.000	X X	=
AS501512	12" PCC PAVEMENT	S.Y.	5,748.000	X	=
AS620510	PAVEMENT MARKING	S.F.	900.000	X	=
AS705506	6" PERFORATED UNDERDRAIN	L.F.	1,175.000	X	=
AS751570	MANHOLE - SPECIAL	EACH	2.000	X   	=

SUBTOTAL ALT 1 \$

# ILLINOIS DEPARTMENT OF TRANSPORTATION ECMSO02 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

RUN DATE - 04/02/09 RUN TIME - 183321

\*\*\*\*\* ALT 2 \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE DOLLARS CENTS	TOTAL PRICE DOLLARS CTS
AT108158	1/C #8 5 KV UG CABLE IN UD	L.F.	575.000	(	=
AT108258	2/C #8 5 KV UG CABLE IN UD	L.F.	475.000	<	=
AT110501	1-WAY CONC. ENCASED DUCT	L.F.	425.000	<	=
AT110502	2-WAY CONCRETE ENCASED DUCT	L.F.	115.000	<	=
AT110710	ELECTRICAL MANHOLE	EACH	2.000	<	=
AT110907	REMOVE ELECTRICAL MANHOLE	EACH	1.000 >	ζ	=
AT125510	MIRL, BASE MOUNTED	EACH	4.000	<	=
AT 152410	UNCLASSIFIED EXCAVATION	С.Ү.	1,050.000	(	=
AT 152441	ON-SITE BORROW	С.Ү.	1,200.000	(	=
AT152442	OFFSITE BORROW EXCAVATION	С.Ү.	2,750.000	(	  - 
AT209510	CRUSHED AGGREGATE BASE COURSE	TON	2,195.000	<	=
AT209600	GEOTEXTILE FABRIC	S.Y.	3,762.000	(	=
AT501512	12" PCC PAVEMENT	S.Y.	3,678.000	(	=
AT501540	PCC PAVEMENT GROOVING	S.Y.	13,155.000	ζ	
AT705506	6" PERFORATED UNDERDRAIN	L.F.	469.000 >	( 	=

#### ILLINOIS DEPARTMENT OF TRANSPORTATION ECMSO02 DTGECM03 ECMR003 PAGE SCHEDULE OF PRICES CONTRACT NUMBER - QUOO8

RUN DATE - 04/02/09 RUN TIME - 183321

ITEM		UNIT OF		UNIT PRI	CE	TOTAL PRIC	CE
NUMBER	PAY ITEM DESCRIPTION	MEASURE	QUANTITY	DOLLARS	CENTS	DOLLARS	CTS
AT751570	MANHOLE - SPECIAL	EACH	2.000 X		=		
AT801614	SUPPLY TAXI GUIDANCE SIGN PANEL	EACH	20.000 X		=		
AT901510	SEEDING	ACRE	2.000 X		=		
AT908513	MULCHING - METHOD 3	ACRE	2.000 X		=		

SUBTOTAL ALT 2 \$ CONTRACT - QUOO8

SUMMAR	RY OF		OTAL	ALTERNATES	
TOTAL	BASE	=	\$	DOLLARS	CTS
TOTAL	ALT	1	\$		
TOTAL	ALT	2	\$ -		
			<u> </u>		

#### NOTE:

- 1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
- 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
- 3. IF A UNIT PRICE IS OMITTED. THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
- 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

# THE PRECEDING SCHEDULE OF PRICES MUST BE

# COMPLETED AND RETURNED.

# STATE REQUIRED ETHICAL STANDARDS GOVERNING CONTRACT PROCUREMENT: ASSURANCES, CERTIFICATIONS AND DISCLOSURES

#### I. GENERAL

- **A.** Article 50 of the Illinois Procurement Code establishes the duty of all State chief procurement officers, State purchasing officers, and their designees to maximize the value of the expenditure of public moneys in procuring goods, services, and contracts for the State of Illinois and to act in a manner that maintains the integrity and public trust of State government. In discharging this duty, they are charged by law to use all available information, reasonable efforts, and reasonable actions to protect, safeguard, and maintain the procurement process of the State of Illinois.
- **B.** In order to comply with the provisions of Article 50 and to carry out the duty established therein, all bidders are to adhere to ethical standards established for the procurement process, and to make such assurances, disclosures and certifications required by law. By execution of the Proposal Signature Sheet, the bidder indicates that each of the mandated assurances has been read and understood, that each certification is made and understood, and that each disclosure requirement has been understood and completed.
- **C.** In addition to all other remedies provided by law, failure to comply with any assurance, failure to make any disclosure or the making of a false certification shall be grounds for termination of the contract and the suspension or debarment of the bidder.

#### II. ASSURANCES

**A.** The assurances hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous assurance, and the surety providing the performance bond shall be responsible for the completion of the contract.

#### B. Felons

1. The Illinois Procurement Code provides:

Section 50-10. Felons. Unless otherwise provided, no person or business convicted of a felony shall do business with the State of Illinois or any state agency from the date of conviction until 5 years after the date of completion of the sentence for that felony, unless no person held responsible by a prosecutorial office for the facts upon which the conviction was based continues to have any involvement with the business.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-10.

#### C. Conflicts of Interest

1. The Illinois Procurement Code provides in pertinent part:

Section 50-13. Conflicts of Interest.

- (a) Prohibition. It is unlawful for any person holding an elective office in this State, holding a seat in the General Assembly, or appointed to or employed in any of the offices or agencies of state government and who receives compensation for such employment in excess of 60% of the salary of the Governor of the State of Illinois, or who is an officer or employee of the Capital Development Board or the Illinois Toll Highway Authority, or who is the spouse or minor child of any such person to have or acquire any contract, or any direct pecuniary interest in any contract therein, whether for stationery, printing, paper, or any services, materials, or supplies, that will be wholly or partially satisfied by the payment of funds appropriated by the General Assembly of the State of Illinois or in any contract of the Capital Development Board or the Illinois Toll Highway authority.
- (b) Interests. It is unlawful for any firm, partnership, association or corporation, in which any person listed in subsection (a) is entitled to receive (i) more than 7 1/2% of the total distributable income or (ii) an amount in excess of the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (c) Combined interests. It is unlawful for any firm, partnership, association, or corporation, in which any person listed in subsection (a) together with his or her spouse or minor children is entitled to receive (i) more than 15%, in the aggregate, of the total distributable income or (ii) an amount in excess of 2 times the salary of the Governor, to have or acquire any such contract or direct pecuniary interest therein.
- (d) Securities. Nothing in this Section invalidates the provisions of any bond or other security previously offered or to be offered for sale or sold by or for the State of Illinois.
- (e) Prior interests. This Section does not affect the validity of any contract made between the State and an officer or employee of the State or member of the General Assembly, his or her spouse, minor child or any combination of those persons if that contract was in existence before his or her election or employment as an officer, member, or employee. The contract is voidable, however, if it cannot be completed within 365 days after the officer, member, or employee takes office or is employed.

The current salary of the Governor is \$150,700.00. Sixty percent of the salary is \$90,420.00.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-13, or that an effective exemption has been issued by the Board of Ethics to any individual subject to the Section 50-13 prohibitions pursuant to the provisions of Section 50-20 of the Code and Executive Order Number 3 (1998). Information concerning the exemption process is available from the Department upon request.

#### D. Negotiations

1. The Illinois Procurement Code provides in pertinent part:

Section 50-15. Negotiations.

- (a) It is unlawful for any person employed in or on a continual contractual relationship with any of the offices or agencies of State government to participate in contract negotiations on behalf of that office or agency with any firm, partnership, association, or corporation with whom that person has a contract for future employment or is negotiating concerning possible future employment.
- 2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-15, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### E. Inducements

1. The Illinois Procurement Code provides:

Section 50-25. Inducement. Any person who offers or pays any money or other valuable thing to any person to induce him or her not to bid for a State contract or as recompense for not having bid on a State contract is guilty of a Class 4 felony. Any person who accepts any money or other valuable thing for not bidding for a State contract or who withholds a bid in consideration of the promise for the payment of money or other valuable thing is guilty of a Class 4 felony.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-25, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### F. Revolving Door Prohibition

1. The Illinois Procurement Code provides:

Section 50-30. Revolving door prohibition. Chief procurement officers, associate procurement officers, State purchasing officers, their designees whose principal duties are directly related to State procurement, and executive officers confirmed by the Senate are expressly prohibited for a period of 2 years after terminating an affected position from engaging in any procurement activity relating to the State agency most recently employing them in an affected position for a period of at least 6 months. The prohibition includes, but is not limited to: lobbying the procurement process; specifying; bidding; proposing bid, proposal, or contract documents; on their own behalf or on behalf of any firm, partnership, association, or corporation. This Section applies only to persons who terminate an affected position on or after January 15, 1999.

2. The bidder assures the Department that the award and execution of the contract would not cause a violation of Section 50-30, and that the bidder has no knowledge of any facts relevant to the kinds of acts prohibited therein.

#### **G.** Reporting Anticompetitive Practices

1. The Illinois Procurement Code provides:

Section 50-40. Reporting anticompetitive practices. When, for any reason, any vendor, bidder, contractor, chief procurement officer, State purchasing officer, designee, elected official, or State employee suspects collusion or other anticompetitive practice among any bidders, offers, contractors, proposers, or employees of the State, a notice of the relevant facts shall be transmitted to the Attorney General and the chief procurement officer.

2. The bidder assures the Department that it has not failed to report any relevant facts concerning the practices addressed in Section 50-40 which may involve the contract for which the bid is submitted.

#### H. Confidentiality

1. The Illinois Procurement Code provides:

Section 50-45. Confidentiality. Any chief procurement officer, State purchasing officer, designee, or executive officer who willfully uses or allows the use of specifications, competitive bid documents, proprietary competitive information, proposals, contracts, or selection information to compromise the fairness or integrity of the procurement, bidding, or contract process shall be subject to immediate dismissal, regardless of the Personnel code, any contract, or any collective bargaining agreement, and may in addition be subject to criminal prosecution.

2. The bidder assures the Department that it has no knowledge of any fact relevant to the practices addressed in Section 50-45 which may involve the contract for which the bid is submitted.

#### I. Insider Information

1. The Illinois Procurement Act provides:

Section 50-50. Insider information. It is unlawful for any current or former elected or appointed State official or State employee to knowingly use confidential information available only by virtue of that office or employment for actual or anticipated gain for themselves or another person.

2. The bidder assures the Department that it has no knowledge of any facts relevant to the practices addressed in Section 50-50 which may involve the contract for which the bid is submitted.

#### III. CERTIFICATIONS

**A.** The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous certification, and the surety providing the performance bond shall be responsible for completion of the contract.

#### B. Bribery

1. The Illinois Procurement Code provides:

Section 50-5. Bribery.

- (a) Prohibition. No person or business shall be awarded a contract or subcontract under this Code who:
  - (1) has been convicted under the laws of Illinois or any other state of bribery or attempting to bribe an officer or employee of the State of Illinois or any other state in that officer's or employee's official capacity; or
  - (2) has made an admission of guilt of that conduct that is a matter of record but has not been prosecuted for that conduct.
- (b) Businesses. No business shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of the business if the employee or agent is no longer employed by the business and:
  - (1) the business has been finally adjudicated not guilty; or
  - (2) the business demonstrates to the governmental entity with which it seeks to contract, and that entity finds that the commission of the offense was not authorized, requested, commanded, or performed by a director, officer, or high managerial agent on behalf of the business as provided in paragraph (2) of subsection (a) of Section 5-4 of the Criminal Code of 1961.
- (c) Conduct on behalf of business. For purposes of this Section, when an official, agent, or employee of a business committed the bribery or attempted bribery on behalf of the business and in accordance with the direction or authorization of a responsible official of the business, the business shall be chargeable with the conduct.
- (d) Certification. Every bid submitted to and contract executed by the State shall contain a certification by the contractor that the contractor is not barred from being awarded a contract or subcontract under this Section. A contractor who makes a false statement, material to the certification, commits a Class 3 felony.
- 2. The bidder certifies that it is not barred from being awarded a contract under Section 50.5.

#### C. Educational Loan

- 1. Section 3 of the Educational Loan Default Act provides:
- § 3. No State agency shall contract with an individual for goods or services if that individual is in default, as defined in Section 2 of this Act, on an educational loan. Any contract used by any State agency shall include a statement certifying that the individual is not in default on an educational loan as provided in this Section.
- 2. The bidder, if an individual as opposed to a corporation, partnership or other form of business organization, certifies that the bidder is not in default on an educational loan as provided in Section 3 of the Act.

#### D. Bid-Rigging/Bid Rotating

- 1. Section 33E-11 of the Criminal Code of 1961 provides:
- § 33E-11. (a) Every bid submitted to and public contract executed pursuant to such bid by the State or a unit of local government shall contain a certification by the prime contractor that the prime contractor is not barred from contracting with any unit of State or local government as a result of a violation of either Section 33E-3 or 33E-4 of this Article. The State and units of local government shall provide the appropriate forms for such certification.
- (b) A contractor who makes a false statement, material to the certification, commits a Class 3 felony.

A violation of Section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent in behalf of the corporation.

2. The bidder certifies that it is not barred from contracting with the Department by reason of a violation of either Section 33E-3 or Section 33E-4.

#### E. International Anti-Boycott

- 1. Section 5 of the International Anti-Boycott Certification Act provides:
- § 5. State contracts. Every contract entered into by the State of Illinois for the manufacture, furnishing, or purchasing of supplies, material, or equipment or for the furnishing of work, labor, or services, in an amount exceeding the threshold for small purchases according to the purchasing laws of this State or \$10,000.00, whichever is less, shall contain certification, as a material condition of the contract, by which the contractor agrees that neither the contractor nor any substantially-owned affiliated company is participating or shall participate in an international boycott in violation of the provisions of the U.S. Export Administration Act of 1979 or the regulations of the U.S. Department of Commerce promulgated under that Act.
- 2. The bidder makes the certification set forth in Section 5 of the Act.

#### F. Drug Free Workplace

- 1. The Illinois "Drug Free Workplace Act" applies to this contract and it is necessary to comply with the provisions of the "Act" if the contractor is a corporation, partnership, or other entity (including a sole proprietorship) which has 25 or more employees.
- 2. The bidder certifies that if awarded a contract in excess of \$5,000 it will provide a drug free workplace by:
- (a) Publishing a statement notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the contractor's workplace; specifying the actions that will be taken against employees for violations of such prohibition; and notifying the employee that, as a condition of employment on such contract, the employee shall abide by the terms of the statement, and notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.
- (b) Establishing a drug free awareness program to inform employees about the dangers of drug abuse in the workplace; the contractor's policy of maintaining a drug free workplace; any available drug counseling, rehabilitation, and employee assistance programs; and the penalties that may be imposed upon employees for drug violations.
- (c) Providing a copy of the statement required by subparagraph (1) to each employee engaged in the performance of the contract and to post the statement in a prominent place in the workplace.
- (d) Notifying the Department within ten (10) days after receiving notice from an employee or otherwise receiving actual notice of the conviction of an employee for a violation of any criminal drug statute occurring in the workplace.
- (e) Imposing or requiring, within 30 days after receiving notice from an employee of a conviction or actual notice of such a conviction, an appropriate personnel action, up to and including termination, or the satisfactory participation in a drug abuse assistance or rehabilitation program approved by a federal, state or local health, law enforcement or other appropriate agency.
- (f) Assisting employees in selecting a course of action in the event drug counseling, treatment, and rehabilitation is required and indicating that a trained referral team is in place.
- (g) Making a good faith effort to continue to maintain a drug free workplace through implementation of the actions and efforts stated in this certification.

#### **G.** Debt Delinquency

1. The Illinois Procurement Code provides:

Section 50-11 and 50-12. Debt Delinquency.

The contractor or bidder certifies that it, or any affiliate, is not barred from being awarded a contract under 30 ILCS 500. Section 50-11 prohibits a person from entering into a contract with a State agency if it knows or should know that it, or any affiliate, is delinquent in the payment of any debt to the State as defined by the Debt Collection Board. Section 50-12 prohibits a person from entering into a contract with a State agency if it, or any affiliate, has failed to collect and remit Illinois Use Tax on all sales of tangible personal property into the State of Illinois in accordance with the provisions of the Illinois Use Tax Act. The contractor further acknowledges that the contracting State agency may declare the contract void if this certification is false or if the contractor, or any affiliate, is determined to be delinquent in the payment of any debt to the State during the term of the contract.

#### H. Sarbanes-Oxley Act of 2002

1. The Illinois Procurement Code provides:

Section 50-60(c).

The contractor certifies in accordance with 30 ILCS 500/50-10.5 that no officer, director, partner or other managerial agent of the contracting business has been convicted of a felony under the Sarbanes-Oxley Act of 2002 or a Class 3 or Class 2 felony under the Illinois Securities Law of 1953 for a period of five years prior to the date of the bid or contract. The contractor acknowledges that the contracting agency shall declare the contract void if this certification is false.

#### I. Addenda

The contractor or bidder certifies that all relevant addenda have been incorporated in to this contract. Failure to do so may cause the bid to be declared unacceptable.

#### J. Section 42 of the Environmental Protection Act

The contractor certifies in accordance with 30 ILCS 500/50-12 that the bidder or contractor is not barred from being awarded a contract under this Section which prohibits the bidding on or entering into contracts with the State of Illinois or a State agency by a person or business found by a court or the Pollution Control Board to have committed a willful or knowing violation of Section 42 of the Environmental Protection Act for a period of five years from the date of the order. The contractor acknowledges that the contracting agency may declare the contract void if this certification is false.

#### K. Apprenticeship and Training Certification (Does not apply to federal aid projects)

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Department, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontracted work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project as reported on the Construction Employee Workforce Projection (Form BC-1256) and returned with the bid is accounted for and listed.

N/A	(Federal)			

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

#### L. Executive Order Number 1 (2007) Regarding Lobbying on Government Procurements

The bidder hereby warrants and certifies that they have complied and will comply with the requirements set forth in this Order. The requirements of this warrant and certification are a material part of the contract, and the contractor shall require this warrant and certification provision to be included in all approved subcontracts.

#### M. Disclosure of Business Operations in Iran

Public Act 95-0616 provides that each bid, offer, or proposal submitted for a State contract shall include a disclosure of whether or not the Company acting as the bidder, offeror, or proposing entity, or any of its corporate parents or subsidiaries, within the 24 months before submission of the bid, offer, or proposal had business operations that involved contracts with or provision of supplies or services to the Government of Iran, companies in which the Government of Iran has any direct or indirect equity share, consortiums or projects commissioned by the Government of Iran, or companies involved in consortiums or projects commissioned by the Government of Iran and either of the following conditions apply:

- (1) More than 10% of the Company's revenues produced in or assets located in Iran involve oil-related activities or mineral-extraction activities; less than 75% of the Company's revenues produced in or assets located in Iran involve contracts with or provision of oil-related or mineral-extraction products or services to the Government of Iran or a project or consortium created exclusively by that government; and the Company has failed to take substantial action.
- (2) The Company has, on or after August 5, 1996, made an investment of \$20 million or more, or any combination of investments of at least \$10 million each that in the aggregate equals or exceeds \$20 million in any 12-month period, which directly or significantly contributes to the enhancement of Iran's ability to develop petroleum resources of Iran.

The terms "Business operations", "Company", "Mineral-extraction activities", "Oil-related activities", "Petroleum resources", and "Substantial action" are all defined in the Act.

Failure to make the disclosure required by the Act shall cause the bid, offer or proposal to be considered not responsive. The disclosure will be considered when evaluating the bid, offer, or proposal or awarding the contract. The name of each Company disclosed as doing business or having done business in Iran will be provided to the State Comptroller.

Check the appropriate statement:
// Company has no business operations in Iran to disclose.
// Company has business operations in Iran as disclosed in the attached document.

#### N. PA 95-0635 SUBSTANCE ABUSE PREVENTION PROGRAM (SAPP)

Effective January 1, 2008

This Public Act requires that all contractors and subcontractors have an SAPP, meeting certain requirements, in place **before** starting work.

The contractor must submit their correctly completed SAPP Certification (Form BC 261) prior to issuance of the Notice-to-Proceed.

The requirements of this Public Act are a material part of the contract, and the contractor shall require this provision to be included in all approved subcontracts. The contractor shall submit the correctly completed SAPP Certification Form BC 261 for each subcontractor with the Request for Approval of Subcontractor (Form AER 260-A) prior to issuance of the Notice-to-Proceed.

All SAPPs and Requests for Approval of Subcontractor are to be submitted to:

Department of Transportation Division of Aeronautics Attn: Chief Engineer 1 Langhorne Bond Drive Capital Airport Springfield, IL 62707-8415.

Telephone number (217) 785-8514 Telefax number (217) 785-4533

#### O. Registration with the State Board of Elections.

Public Act 95-0971, amending the Illinois Procurement Code, 30 ILCS 500, adding new sections 20-160 and 50-37, and Executive Order 3 (2008) establish new requirements affecting contributions that contractors, consultants, vendors and bidders, including affiliated persons and entities, may make to state officeholders, declared candidates for state offices and political organizations established to benefit such officeholders and candidates. These provisions do not apply to federal-aid contracts.

By submission of a bid, the bidder acknowledges and agrees that it has read and understands the requirements of PA 95-0971 and Executive Order 3 (2008), including but not limited to, all reporting requirements and all restrictions on soliciting and making contributions to state officeholders, declared candidates for state offices and covered political organizations that promote the candidacy of an officeholder or declared candidate for office. In addition, the bidder makes the following certifications:

- (1) As to Executive Order 3 (2008), the bidder certifies that no contribution will be made that would violate the order, and that the bidder will report all contributions as required by the order.
- (2) As to PA 95-0971, the bidder shall check either of the following certifications that apply:

/\_\_\_/ The bidder is not required to register as a business entity with the State Board of Elections.

/\_\_/ The bidder has registered as a business entity with the State Board of Elections, and acknowledges a continuing duty to update the registration as required the Act. A copy of the time-stamped certificate of registration is enclosed with the bid. The Department will not award this contract without the submission of a certificate of registration.

In accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, this certification shall be part of the contract. Compliance with PA 95-0971 and Executive Order 3 (2008) is a material part of the contract and any breach shall be cause to void the contract under Section 50-60 of the Illinois Procurement Code.

#### IV. DISCLOSURES

**A.** The disclosures hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder. The Department may terminate the contract if it is later determined that the bidder rendered a false or erroneous disclosure, and the surety providing the performance bond shall be responsible for completion of the contract.

#### B. Financial Interests and Conflicts of Interest

1. Section 50-35 of the Illinois Procurement Code provides that all bids of more than \$10,000 shall be accompanied by disclosure of the financial interests of the bidder. This disclosed information for the successful bidder, will be maintained as public information subject to release by request pursuant to the Freedom of Information Act.

The financial interests to be disclosed shall include ownership or distributive income share that is in excess of 5%, or an amount greater than 60% of the annual salary of the Governor, of the bidding entity or its parent entity, whichever is less, unless the contractor or bidder is a publicly traded entity subject to Federal 10K reporting, in which case it may submit its 10K disclosure in place of the prescribed disclosure. The disclosure shall include the names, addresses, and dollar or proportionate share of ownership of each person making the disclosure, their instrument of ownership or beneficial relationship, and notice of any potential conflict of interest resulting from the current ownership or beneficial interest of each person making the disclosure having any of the relationships identified in Section 50-35 and on the disclosure form.

In addition, all disclosures shall indicate any other current or pending contracts, proposals, leases, or other ongoing procurement relationships the bidding entity has with any other unit of state government and shall clearly identify the unit and the contract, proposal, lease, or other relationship.

2. <u>Disclosure Forms</u>. Disclosure Form A is attached for use concerning the individuals meeting the above ownership or distributive share requirements. Subject individuals should be covered each by one form. In addition, a second form (Disclosure Form B) provides for the disclosure of current or pending procurement relationships with other (non-IDOT) state agencies. **The forms must be included with each bid or incorporated by reference.** 

#### C. <u>Disclosure Form Instructions</u>

#### Form A: For bidders that have previously submitted the information requested in Form A

The Department has retained the Form A disclosures submitted by all bidders responding to these requirements for the April 24, 1998 or any subsequent letting conducted by the Department. The bidder has the option of submitting the information again or the bidder may sign the following certification statement indicating that the information previously submitted by the bidder is, as of the date of signature, current and accurate. The Certification must be signed and dated by a person who is authorized to execute contracts for the bidding company. Before signing this certification, the bidder should carefully review its prior submissions to ensure the Certification is correct. If the Bidder signs the Certification, the Bidder should proceed to Form B instructions.

#### CERTIFICATION STATEMENT

I have determined that the Form A disclosure information previously subm incorporated by reference in this bid. Any necessary additional forms or arbid.					
(Bidding Compa	(Bidding Company)				
Name of Authorized Representative (type or print)	Title of Authorized Representative (type or print)				
Signature of Authorized Represe	entative Date				

#### Form A: For bidders who have NOT previously submitted the information requested in Form A

If the bidder is a publicly traded entity subject to Federal 10K reporting, the 10K Report may be submitted to meet the requirements of Form A. If a bidder is not subject to Federal 10K reporting, the bidder must determine if any individuals are required by law to complete a financial disclosure form. To do this, the bidder should answer each of the following questions. A "YES" answer indicates Form A must be completed. If the answer to each of the following questions is "NO", then the NOT APPLICABLE STATEMENT on the second page of Form A must be signed and dated by a person that is authorized to execute contracts for the bidding company. Note These questions are for assistance only and are not required to be completed.

	1.	Does anyone in your organization have a direct or beneficial ownership share of greater than 5% of the bidding entity or parent entity? YES NO
	2.	Does anyone in your organization have a direct or beneficial ownership share of less than 5%, but which has a value greater than \$87,526.20? YES NO
	3.	Does anyone in your organization receive more than \$87,526.20 of the bidding entity's or parent entity's distributive income? (Note: Distributive income is, for these purposes, any type of distribution of profits. An annual salary is not distributive income.) YES NO
	4.	Does anyone in your organization receive greater than 5% of the bidding entity's or parent entity's total distributive income, but which is less than \$87,526.20? YES NO
		(Note: Only one set of forms needs to be completed <u>per person per bid</u> even if a specific individual would require a yes answer to more than one question.)
	bidding e authorize	answer to any of these questions requires the completion of Form A. The bidder must determine each individual in the bidding entity or the ntity's parent company that would cause the questions to be answered "Yes". Each form must be signed and dated by a person that is d to execute contracts for your organization. <b>Photocopied or stamped signatures are not acceptable</b> . The person signing can be, but does to be, the person for which the form is being completed. The bidder is responsible for the accuracy of any information provided.
		wer to each of the above questions is "NO", then the <u>NOT APPLICABLE STATEMENT</u> on page 2 of Form A must be signed and dated by a at is authorized to execute contracts for your company.
	bidding e	Identifying Other Contracts & Procurement Related Information Disclosure Form B must be completed for each bid submitted by the ntity. It must be signed by an individual who is authorized to execute contracts for the bidding entity. Note: Signing the NOT APPLICABLE on Form A does not allow the bidder to ignore Form B. Form B must be completed, signed and dated or the bidder may be considered nasive and the bid will not be accepted.
	procurem	er shall identify, by checking Yes or No on Form B, whether it has any pending contracts (including leases), bids, proposals, or other ongoing ent relationship with any other (non-IDOT) State of Illinois agency. If "No" is checked, the bidder only needs to complete the signature box ttom of Form B. If "Yes" is checked, the bidder must do one of the following:
	agency pe attached s	If the bidder did not submit an Affidavit of Availability to obtain authorization to bid, the bidder must list all non-IDOT State of Illinois ending contracts, leases, bids, proposals, and other ongoing procurement relationships. These items may be listed on Form B or on an sheet(s). Do not include IDOT contracts. Contracts with cities, counties, villages, etc. are not considered State of Illinois agency contracts of to be included. Contracts with other State of Illinois agencies such as the Department of Natural Resources or the Capital Development ist be included. Bidders who submit Affidavits of Availability are suggested to use Option II.
	"See Affi Illinois ag	If the bidder is required and has submitted an Affidavit of Availability in order to obtain authorization to bid, the bidder may write or type davit of Availability" which indicates that the Affidavit of Availability is incorporated by reference and includes all non-IDOT State of gency pending contracts, leases, bids, proposals, and other ongoing procurement relationships. For any contracts that are not covered by the of Availability, the bidder must identify them on Form B or on an attached sheet(s). These might be such things as leases.
D.	Bidders S	Submitting More Than One Bid
		ubmitting multiple bids may submit one set of forms consisting of all required Form A disclosures and one Form B for use with all bids. licate in the space provided below the bid item that contains the original disclosure forms and the bid items which incorporate the forms by
		the bid submitted for letting item contains the Form A disclosures or Certification Statement and the Form B sclosures. The following letting items incorporate the said forms by reference:

# **RETURN WITH BID/OFFER**

# ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form A Financial Information & Potential Conflicts of Interest Disclosure

Contractor Name					
Legal Address					
City, State, Zip					
Telephone Number				Fax Number (if avail	able)
enter into a contract wit Disclosure Form. This in		lose the financia he publicly availa npany may subn	l information and pote able contract file. This	ntial conflict of interest info Form A must be completed to a satisfaction of the require	formation as specified in thi for bids in excess of \$10,000
of ownership or dist the Governor's salar <b>for each individual</b>	nancial Information. The tributive income share in extry as of 10/1/2000). (Make I meeting these requiremental (type or print information)	e individual naccess of 5%, ce copies of thients)	amed below has an or an interest which	interest in the BIDDER has a value of more th	nan \$87,526.20 (60% o
NAME:					
ADDRESS					
Type of own	nership/distributable inco	ome share:			
stock	sole proprietorship	)	partnership	other: (explai	in on separate sheet):
% or \$ value	e of ownership/distributable	e income shar	e:		
conflict of interest re	otential Conflicts of Intercellationships apply. If the amployment, currently or in	inswer to any	question is "Yes",	please attach additiona	al pages and describe.  It of services.
(b) State er the previou	mployment of spouse, fathers 2 years.	er, mother, son	n, or daughter, incl		
				Yes	No
any unit of	e status; the holding of electrocal government authorize currently or in the previous	ed by the Cor			
	1	Ž		Yes	No
(d) Relation	nship to anyone holding elegater	ective office of	currently or in the p	previous 2 years; spouse	e, father, mother,
- , - <del></del>				Yes	No

# **RETURN WITH BID/OFFER**

States of Americ	office; the holding of any appointive government office of ca, or any unit of local government authorized by the Co	onstitution of the State	of Illinois or the
	tate of Illinois, which office entitles the holder to compete that office currently or in the previous 3 years.	ensation in excess of th	ne expenses incurred in
the disentage of	that office currently of in the previous 5 years.	Yes	No
(f) Relationship mother, son, or	to anyone holding appointive office currently or in the p	previous 2 years; spou	se, father,
, , .		Yes	No
(g) Employment	t, currently or in the previous 3 years, as or by any regist		tate government.
(h) Relationship son, or daughter	to anyone who is or was a registered lobbyist in the pre		
		Yes	No
committee regis	d employment, currently or in the previous 3 years, by an tered with the Secretary of State or any county clerk of t tered with either the Secretary of State or the Federal Bo	the State of Illinois, or pard of Elections.	any political action
		Yes	No
2 years by any r	to anyone; spouse, father, mother, son, or daughter; who egistered election or re-election committee registered willinois, or any political action committee registered with f Elections.	ith the Secretary of Sta	
		Yes	No
This Disclosure Form	APPLICABLE STATEME A is submitted on behalf of the INDIVIDUAL named		
Completed by:			
-	Name of Authorized Representative (type or	print)	
Completed by:	Title of Authorized Representative (type or	print)	
Completed by:	The of Admonized Representative (type of	print)	
_	Signature of Individual or Authorized Repres	entative	Date
	NOT APPLICABLE STATEN	MENT	
I have determined tha completion of this For	t no individuals associated with this organization me		ould require the
This Disclosure Form	A is submitted on behalf of the CONTRACTOR liste	ed on the previous pa	ge.
_	Name of Authorized Representative (type or	print)	
_	Title of Authorized Representative (type or	print)	
_	Signature of Authorized Representative	e	Date

19

# **RETURN WITH BID/OFFER**

# ILLINOIS DEPARTMENT OF TRANSPORTATION

# Form B Other Contracts & Procurement Related Information Disclosure

Contractor Name						
Legal Address						
City, State, Zip						
Telephone Number		Fax Number (if available)				
Disclosure of the information contained in the ILCS 500). This information shall become p bids in excess of \$10,000, and for all open-end	art of the publicly available contract					
DISCLOSURE OF OTHER COM	NTRACTS AND PROCUREMENT	RELATED INFORMATION				
1. Identifying Other Contracts & Procurer pending contracts (including leases), bids, pro Illinois agency: Yes No If "No" is checked, the bidder only needs to contract the pending contracts of the pending contr	posals, or other ongoing procurement	relationship with any other State of				
<b>2. If "Yes" is checked.</b> Identify each such relinformation such as bid or project number (att INSTRUCTIONS:						
2.01.10 0.1201.131						
THE FOLLOWING STATEMENT MUST BE SIGNED						
Name of A	Authorized Representative (type or pr	int)				
Title of A	authorized Representative (type or pri	nt)				
Sign	ature of Authorized Representative	Date				

#### SPECIAL NOTICE TO CONTRACTORS

The following requirements of the Illinois Department of Human Rights' Rules and Regulations are applicable to bidders on all construction contracts advertised by the Illinois Department of Transportation:

#### **CONSTRUCTION EMPLOYEE UTILIZATION PROJECTION**

- (a) All bidders on construction contracts shall complete and submit, along with and as part of their bids, a Bidder's Employee Utilization Form (Form BC-1256) setting forth a projection and breakdown of the total workforce intended to be hired and/or allocated to such contract work by the bidder including a projection of minority and female employee utilization in all job classifications on the contract project.
- (b) The Department of Transportation shall review the Employee Utilization Form, and workforce projections contained therein, of the contract awardee to determine if such projections reflect an underutilization of minority persons and/or women in any job classification in accordance with the Equal Employment Opportunity Clause and Section 7.2 of the Illinois Department of Human Rights' Rules and Regulations for Public Contracts adopted as amended on September 17, 1980. If it is determined that the contract awardee's projections reflect an underutilization of minority persons and/or women in any job classification, it shall be advised in writing of the manner in which it is underutilizing and such awardee shall be considered to be in breach of the contract unless, prior to commencement of work on the contract project, it submits revised satisfactory projections or an acceptable written affirmative action plan to correct such underutilization including a specific timetable geared to the completion stages of the contract.
- (c) The Department of Transportation shall provide to the Department of Human Rights a copy of the contract awardee's Employee Utilization Form, a copy of any required written affirmative action plan, and any written correspondence related thereto. The Department of Human Rights may review and revise any action taken by the Department of Transportation with respect to these requirements.



#### PART I. IDENTIFICATION

Human Rights	
Bid Number:	Duration of Project:
Name of Bidder:	

#### PART II. WORKFORCE PROJECTION

A. The undersigned bidder has analyzed minority group and female populations, unemployment rates and availability of workers for the location in which this contract work is to be performed, and for the locations from which the bidder recruits employees, and hereby submits the following workforce projection including a projection for minority and female employee utilization in all job categories in the workforce to be allocated to this contract:

		TOT	AI W	rkfora	TABLI e Project		Contro	at					1 -	C	TABLE		/PLOYE	EC
		101	AL W	JIKIUIC	e rroject	1011 1101	Contra	ici						C			APLOYE. SIGNED	دىد
			MINORITY EMPLOYEES TRAINEES									TO CONTRACT						
JOB	_	ΓAL				*OTHER		APPF		ON THE JOB		TOTAL					ORITY	
CATEGORIES	EMPLO			ACK	HISPA		MINOR.		TICES		TRAINEES			EMPLOYEES			EMPLOYEES	
	M	F	M	F	M	F	M	F	M	F	M	F	<u> </u>	M	F		M	F
OFFICIALS (MANAGERS)																		
SUPERVISORS																		
FOREMEN																		
CLERICAL																		
EQUIPMENT OPERATORS																		
MECHANICS																		
TRUCK DRIVERS																		
IRONWORKERS																		
CARPENTERS																		
CEMENT MASONS																		
ELECTRICIANS																		
PIPEFITTERS, PLUMBERS																		
PAINTERS																		
LABORERS, SEMI-SKILLED																		
LABORERS, UNSKILLED																		
TOTAL		_								-								

TABLE C									
TOTAL Training Projection for Contract									
EMPLOYEES	TO	ΓAL			*OTHER				
IN	EMPLO	OYEES	BLA	ACK	HISP.	ANIC	MINOR.		
TRAINING	M	F	M	F	M	F	M	F	
APPRENTICES									
ON THE JOB									
TRAINEES									

<sup>\*</sup>Other minorities are defined as Asians (A) or Native Americans (N).

Please specify race of each employee shown in Other Minorities column.

Note: See instructions on page 2

FOR DEPARTMENT USE ONLY

BC 1256 - Pg 1 (Rev. 3/98) IL 494-0454

# PART II. WORKFORCE PROJECTION - continued

The	e Bidder's signature on the Proposal Signature Sheeck needs to be completed only if revisions are require nature:	GARDING SIGNATURE  et will constitute the signing ed.  Title:  onnel in addition to prime contact the signing ed.	Date: ntractor personnel.  orm the contract work and the total
The	NOTICE RECEIVED BID STATE OF THE PROPOSAL SIGNATURE Sheet Control of Sheet Control of Sheet Control of Sheet Control of Sheet	GARDING SIGNATURE et will constitute the signing ed.	of this form. The following signature
Addres	NOTICE REC	GARDING SIGNATURE et will constitute the signing	of this form. The following signature
·	eany	_	er
·	any	_	er
Compa		Telephone Numb	er
	be part of the contract specifications.		
В.	submitted herein, and the goals and timetable inclu		
A.	The undersigned bidder understands and agrees utilization projection included under <b>PART II</b> is d in any job category, and in the event that the ur commencement of work, develop and submit a (geared to the completion stages of the contraction are corrected. Such Affirmative Action	letermined to be an underutil indersigned bidder is awarde written Affirmative Action ct) whereby deficiencies in	ization of minority persons or women ed this contract, he/she will, prior to Plan including a specific timetable in minority and/or female employee
PART 1	III. AFFIRMATIVE ACTION PLAN		
	The undersigned bidder estimates that (number) _ directly employed by the prime contractor and employed by subcontractors.	that (number)	persons will be persons will be
C.		projection of numbers of po	ersons to be employed directly by the
	recruited from the area in which new hires was office or base of operation is located.	would be recruited from the	area in which the bidder's principal
	The undersigned bidder projects that: (number) recruited from the area in which		

<u>CERTIFICATIONS REQUIRED BY STATE AND/OR FEDERAL LAW</u>. The bidder is required by State and/or Federal law to make the below certifications and assurances as a part of the proposal and contract upon award. It is understood by the bidder that the certifications and assurances made herein are a part of the contract.

By signing the Proposal Signature Sheet, the bidder certifies that he/she has read and completed each of the following certifications and assurances, that required responses are true and correct and that the certified signature of the Proposal Signature Sheet constitutes an endorsement and execution of each certification and assurance as though each was individually signed:

A. By the execution of this proposal, the signing bidder certifies that the bidding entity has not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action, in restraint of free competitive bidding in connection with the submitted bid. This statement made by the undersigned bidder is true and correct under penalty of perjury under the laws of the United States.

#### B. CERTIFICATION, EQUAL EMPLOYMENT OPPORTUNITY:

1.	Have you participated in any previous contracts or subcontracts subject to the equal opportunity clause. YES NO
2.	If answer to #1 is yes, have you filed with the Joint Reporting Committee, the Director of OFCC, any Federal agency, or the former President's Committee on Equal Employment Opportunity, all reports due under the applicable filing requirements of those organizations? YES NO

- C. BUY AMERICAN STEEL AND MANUFACTURED PRODUCTS FOR CONSTRUCTION CONTRACTS (JAN 1991)
  - (a) The Aviation Safety and Capacity Expansion Act of 1990 provides that preference be given to steel and manufactured products produced in the United States when funds are expended pursuant to a grant issued under the Airport Improvement Program. The following terms apply:
    - 1. <u>Steel and manufactured products</u>. As used in this clause, steel and manufactured products include (1) steel produced in the United States or (2) a manufactured product produced in the United States, if the cost of its components mined, produced or manufactured in the United States exceeds 60 percent of the cost of all its components and final assembly has taken place in the United States. Components of foreign origin of the same class or kind as the products referred to in subparagraphs (b)(1) or (2) shall be treated as domestic.
    - 2. <u>Components</u>. As used in this clause, components means those articles, materials, and supplies incorporated directly into steel and manufactured products.
    - 3. <u>Cost of Components</u>. This means the costs for production of the components, exclusive of final assembly labor costs.
  - (b) The successful bidder will be required to assure that only domestic steel and manufactured products will be used by the Contractor, subcontractors, materialmen, and suppliers in the performance of this contract, except those-
    - (1) that the U.S. Department of Transportation has determined, under the Aviation Safety and Capacity Expansion Act of 1990, are not produced in the United States in sufficient and reasonably available quantities of a satisfactory quality;
    - (2) that the U.S. Department of Transportation has determined, under the Aviation Safety and Capacity Expansion Act of 1990, that domestic preference would be inconsistent with the public interest; or
    - (3) that inclusion of domestic material will increase the cost of the overall project contract by more than 25 percent.

(End of Clause)

#### D. BUY AMERICAN CERTIFICATE (JAN 1991)

By submitting a bid/proposal under this solicitation, except for those items listed by the offeror below or on a separate and clearly identified attachment to this bid/proposal, the offeror certifies that steel and each manufactured product, is produced in the United States (as defined in the clause Buy American - Steel and Manufactured Products or Buy American - Steel and Manufactured Products For Construction Contracts) and that components of unknown origin are considered to have been produced or manufactured outside the United States.

Offerors may obtain from (IDOT, Division of Aeronautics) lists of articles, materials, and supplies excepted from this provision.

PRODUCT	COUNTRY OF ORIGIN

#### E. NPDES CERTIFICATION

In accordance with the provisions of the Illinois Environmental Protection Act, the Illinois Pollution Control Board Rules and Regulations (35 Ill. Adm. Code, Subtitle C, Chapter I), and the Clean Water Act, and the regulations thereunder, this certification is required for all construction contracts that will result in the disturbance of one or more acres total land area.

The undersigned bidder certifies under penalty of law that he/she understands the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit (ILR100000) that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

The Airport Owner or its Agent will:

- 1) prepare, sign and submit the Notice of Intent (NOI)
- 2) conduct site inspections and complete and file the inspection reports
- 3) submit Incidence of Non-Compliance (ION) forms
- 4) submit Notice of Termination (NOT) form

Prior to the issuance of the Notice-to-Proceed, for <u>each</u> erosion control measure identified in the Storm Water Pollution Prevention Plan, the contractor or subcontractor responsible for the control measure(s) must sign the above certification (forms to be provided by the Department).

#### F. NON-APPROPRIATION CLAUSE

By submitting a bid/proposal under this solicitation the offeror certifies that he/she understands that obligations of the State will cease immediately without penalty or further payment being required in any fiscal year the Illinois General Assembly fails to appropriate or otherwise make available sufficient funds for this contract.

G. Contractor is not delinquent in the payment of any debt to the State (or if delinquent has entered into a deferred payment plan to pay the debt), and Contractor acknowledges the contracting state agency may declare the contract void if this certification is false (30 ILCS 500/50-11, effective July 1, 2002).

#### NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS. Sealed proposals for the improvement described herein will be received by the Department of Transportation at the Harry R. Hanley Building, 2300 South Dirksen Parkway in Springfield, Illinois until 10:00 o'clock a.m., <u>April 24, 2009</u>. All bids will be gathered, sorted, publicly opened and read in the auditorium at the Department of Transportation's Harry R. Hanley Building shortly after the 10:00 a.m. cut off time.
- **2. DESCRIPTION OF WORK**. The proposed improvement, shown in detail on the plans issued by the Department includes, in general, the following described work:

Taxiway P, Phase II – Middle Paving

- **3. INSTRUCTIONS TO BIDDERS**. (a) This Notice, the invitation for bids, proposal and award shall, together with all other documents in accordance with Article 10-15 of the Illinois Standard Specifications for Construction of Airports, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.
  - (b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS. This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the proposal and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.
- **5. PRE-BID CONFERENCE.** There will be a pre-bid conference held at N/A at the Quad City International Airport administration building. For engineering information, contact Denny Martin of Missman, Stanley & Associates at ((309) 788-7644.
- **6. DISADVANTAGED BUSINESS POLICY.** The DBE goal for this contract is 10.0%.
- 7. SPECIFICATIONS AND DRAWINGS. The work shall be done in accordance with the Illinois Standard Specifications for Construction of Airports, the Illinois Division of Aeronautics Supplemental Specifications and Recurring Special Provisions, the Special Provisions dated <u>March 20, 2009</u> and the Construction Plans dated <u>March 20, 2009</u> as approved by the Department of Transportation, Division of Aeronautics.

- **8. INSPECTION OF RECORDS.** The Contractor shall maintain an acceptable cost accounting system. The Sponsor, the FAA, and the Comptroller General of the United States shall have access to any books, documents, paper, and records of the Contractor which are directly pertinent to the specific contract for the purposes of making an audit, examination, excerpts, and transcriptions. The Contractor shall maintain all required records for <u>three years</u> after the Sponsor makes final payment and all other pending matters are closed.
- **9. RIGHTS TO INVENTIONS.** All rights to inventions and materials generated under this contract are subject to Illinois law and to regulations issued by the FAA and the Sponsor of the Federal grant under which this contract is executed. Information regarding these rights is available from the FAA and the Sponsor.

#### 10. TERMINATION OF CONTRACT.

- 1. The Sponsor may, be written notice, terminate this contract in whole or in part at any time, either for the Sponsor's convenience or because of failure to fulfill the contract obligations. Upon receipt of such notice services shall be immediately discontinued (unless the notice directs otherwise) and all materials as may have been accumulated in performing this contract, whether completed or in progress, delivered to the Sponsor.
- If the termination is for the convenience of the Sponsor, an equitable adjustment in the contract price shall be made, but no amount shall be allowed for anticipated profit on unperformed services.
- 3. If the termination is due to failure to fulfill the Contractor's obligations, the Sponsor may take over the work and prosecute the same to completion by contract or otherwise. In such case, the Contractor shall be liable to the Sponsor for any additional cost occasioned to the Sponsor thereby.
- 4. If, after notice of termination for failure to fulfill contract obligations, it is determined that the Contractor had not so failed, the termination shall be deemed to have been effected for the convenience of the Sponsor. In such event, adjustment in the contract price shall be made as provided in paragraph 2 of this clause.
- 5. The rights and remedies of the sponsor provided in this clause are in addition to any other rights and remedies provided by law or under this contract.

#### **RETURN WITH BID**

- 11. BIDDING REQUIREMENTS AND BASIS OF AWARD. When alternates are included in the proposal, the following shall apply:
  - a. Additive Alternates
    - (1) Bidders must submit a bid for the Base Bid and for all Additive Alternates.
    - (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lowest aggregate amount of (i) the Base Bid plus (ii) any Additive Alternate(s) which the Department elects to award.

The Department may elect not to award any Additive Alternates. In that case, award will be to the lowest responsible qualified bidder of the Base Bid.

- b. Optional Alternates
  - (1) Bidders must submit a bid for the Base Bid and for either Alternate A or Alternate B or for both Alternate A and Alternate B.
  - (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lower of the aggregate of either (i) the Base Bid plus Alternate A or (ii) the Base Bid plus Alternate B.

**12. CONTRACT TIME.** The Contractor shall complete all work within the specified contract time. Any calendar day extension beyond the specified contract time must be fully justified, requested by the Contractor in writing, and approved by the Engineer, or be subject to liquidated damages.

The contract time for this contract is <u>181</u> calendar days for the base bid. If Additive Alternate No. 1 is awarded, an additional 14 calendar days will be granted. If Additive Alternate No. 2 is awarded, an additional 22 calendar days will be granted.

- 13. INDEPENDENT WEIGHT CHECKS. The Department reserves the right to conduct random unannounced independent weight checks on any delivery for bituminous, aggregate or other pay item for which the method of measurement for payment is based on weight. The weight checks will be accomplished by selecting, at random, a loaded truck and obtaining a loaded and empty weight on an independent scale. In addition, the department may perform random weight checks by obtaining loaded and empty truck weights on portable scales operated by department personnel.
- 14. GOOD FAITH COMPLIANCE. The Illinois Department of Transportation has made a good faith effort to include all statements, requirements, and other language required by federal and state law and by various offices within federal and state governments whether that language is required by law or not. If anything of this nature has been left out or if additional language etc. is later required, the bidder/contractor shall cooperate fully with the Department to modify the contract or bid documents to correct the deficiency. If the change results in increased operational costs, the Department shall reimburse the contractor for such costs as it may find to be reasonable.

#### RETURN WITH BID

#### PROPOSAL SIGNATURE SHEET

The undersigned bidder hereby makes and submits this bid on the subject Proposal, thereby assuring the Department that all requirements of the Invitation for Bids and rules of the Department have been met, that there is no misunderstanding of the requirements of paragraph 4 of this Proposal, and that the contract will be executed in accordance with the rules of the Department if an award is made on this bid.

	Firm Name		
(IF AN INDIVIDUAL)	Signature of Owner		
	Business Address		
	Firm Name		
	Ву		
(IF A CO-PARTNERSHIP)	Business Address		
	Name and Address of All	Members of the Firm:	
	Corporate Name		
	Ву		Corporate Seal
(IF A CORPORATION)	Attest		
	Business Address		Corporate Secretary
	Name of Corporate Office	ers:	
	President	Corporate Secretary	Treasurer
	NOTARY CERTIFIC	ATION	
STATE OF ILLINOIS,	ALL SIGNATURES MUST BI	F NOTADIZED	
COUNTY OF	ALL SIGNATURES MUST BI	INOTARIZED	
I,	, a Notary Public in and for said cou	nty, do hereby certify that	
	AND		
	(Insert names of individual(s) signing	g on behalf of bidder)	
bidder, appeared before me this day	ne to be the same persons whose names are in person and acknowledged that they sign		
voluntary act for the uses and purposes therein	ı set forth.		
Given under my hand and notarial s	eal this day	of	, A.D
My commission expires			(Seal)
-		Notary F	

# **Return with Bid**



# **Division of Aeronautics** Proposal Bid Bond (Effective January 1, 2002)

			Item No. Letting Date:	15A April 24, 2009	
		International Airport			
	III. Proj. No. <u>MLI-</u> Fed. Proj. No. <u>3-17</u> -		_		
KNOW ALL MEN BY THESE PRESE	NTS that we				, as
PRINCIPAL, and					
bound unto the, hereinafter called the PROPOSAL GUARANTEE of the Propayment of which we bind ourselves, or	posal Document, whichever	is the lesser sum, wel	otal bid price or I and truly to be	, as SURETY are of the amount sp paid unto the sai	ecified in Section 6,
THE CONDITION OF THIS OBLIGAT AGENT, the State of Illinois, Department Bulletin Item Number and Letting Date	ent of Transportation, Division				
NOW, THEREFORE, if the SPONSOF time and as specified in the Bidding ar and if after the award, the PRINCIPAL including evidence of insurance covers such contract and for prompt payment PRINCIPAL to make the required DBE SPONSOR the difference not to exceed SPONSOR may contract with another otherwise to remain in full force and effort in the SURETY does not make full paym SURETY is liable to the SPONSOR ar SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the SURETY is liable to the SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF, the said PRINCIPAL in the BID SPONSOR or AGENT prevail either in IN WITNESS WHEREOF.	nd Contract Documents, sub- shall enter into a contract in age's and providing such both of labor and material furnists. Submission or to enter into ed the penalty hereof between party to perform the work offect.  through its AGENT determand the penal sent within such period of time and to the AGENT for all its enternal whole or in part.	omit the DBE Utilization accordance with the ond as specified with go hed in the prosecution of such contract and to generate the amount in the Bovered by said Propositions the PRINCIPAL hours to the SPONSOR when, the AGENT may broxpenses, including atternal contracts and the proposition of the pr	n Plan that is acterms of the Bicood and sufficie thereof; or if, in give the specifie id Proposal and al Document, the as failed to comvithin fifteen (15 ing an action to orney's fees, incompared to the proposal and the propos	ceptable and applding and Contraint surety for the fifthe event of the id bond, the PRIM such larger amoren, this obligation ply with any required by days of written collect the amountaints.	proved by the AGENT, ct Documents raithful performance of failure of the NCIPAL pays to the punt for which the n to be void;  direment as set forth in demand therefor. If nt owed. The
their respective officers this	day of		A.D., 20		
PRINCIPAL		SURETY			
		<del>-</del>			
(Company Name)		(Company Name	<del>)</del> )		
By:(Signature & Title)		By:	(Signature o	of Attorney-in-Fac	<u></u>
(Orginataro a Titio)		ion for Dringing and		or rationally in ratio	<del></del>
	Notary Certificat	ion for Principal and	Surety		
State of Illinois ) ) ss:					
County of)					
l,		, a Notary Public i	n and for said C	ounty, do hereby	certify that
	and				
(Insert names of individuals	signing on behalf of PRINC	IPAL & SURETY)			
who are each personally known to me PRINCIPAL and SURETY, appeared I instrument as their free and voluntary	before me this day in persor	n and acknowledged re			
Given under my hand and notary se	eal thisd	ay of			A.D., 20
My commission expires					
			(Notary Pub	olic)	
In lieu of completing the above section PRINCIPAL is ensuring the identified of SPONSOR through its AGENT under	electronic bid bond has bee	n executed and the PR			
Electronic Bid Bond ID#	Company/Bidder	Name	Si	gnature and Title Forr	n D.E. (Rev. 12-2001)



# **PROPOSALS**

for construction work advertised for bids by the Illinois Department of Transportation

Item No.	Item No.	Item No.

#### Submitted By:

Name:		
Address:		
Phone No.		

Bidders should affix this form to the front of a 10" x 13" envelope and use that envelope for the submittal of bids. If proposals are mailed, they should be enclosed in a second or outer envelope addressed to:

Engineer of Design and Environment - Room 323 Illinois Department of Transportation 2300 South Dirksen Parkway Springfield, Illinois 62764

# CONTRACTOR OFFICE COPY OF CONTRACT SPECIFICATIONS

# **NOTICE**

None of the following material needs to be returned with the bid package unless the special provisions require documentation and/or other information to be submitted.



#### CONTRACT REQUIREMENTS

- (1) <u>Airport Improvement Program projects</u>. The work in this contract is included in the federal Airport Improvement Program and is being undertaken and accomplished by the Illinois Department of Transportation, Division of Aeronautics and the Municipality, hereinafter called the Co-Sponsors, in accordance with the terms and conditions of a Grant Agreement between the Co-Sponsors and the United States, under the Airport and Airway Improvement Act of 1982 (Public Law 97-248; Title V, Section 501 et seq., September 3, 1982; 96 Stat. 671; codified at 49 U.S.C Section 2201 et seq.) and Part 152 of the Federal Aviation Regulations (14 CFR Part 152), pursuant to which the United States has agreed to pay a certain percentage of the costs of the Project that are determined to be allowable Project costs under the Act. The United States is not a party to this contract and no reference in this contract to FAA or representative thereof, or to any rights granted to the FAA or any representative thereof, or the United States, by the contract, makes the United States a party to this contract.
- (2) <u>Consent of Assignment</u>. The Contractor shall obtain the prior written consent of the Co-Sponsors to any proposed assignment of any interest in or part of this contract.
  - (3) <u>Convict Labor</u>. No convict labor may be employed under this contract.
- (4) <u>Veterans Preference</u>. In the employment of labor, except in executive, administrative, and supervisory positions, preference shall be given to veterans of the Vietnam era and disabled veterans as defined in Section 515(c) of the Airport and Airway Improvement Act of 1982. However, this preference shall apply only where the individuals are available and qualified to perform the work to which the employment relates.
- (5) <u>Withholding: Sponsor from Contractor</u>. Whether or not payments or advances to the Co-Sponsors are withheld or suspended by the FAA, the Co-Sponsors may withhold or cause to be withheld from the Contractor so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics employed by the Contractor or any subcontractor on the work the full amount of wages required by this contract.
- (6) Nonpayment of Wages. If the Contractor or subcontractor fails to pay any laborer or mechanic employed or working on the site of the work any of the wages required by this contract the Co-Sponsors may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment or advance of funds until the violations cease.
- (7) <u>FAA Inspection and Review</u>. The Contractor shall allow any authorized representative of the FAA to inspect and review any work or materials used in the performance of this contract.
- (8) <u>Subcontracts</u>. The Contractor shall insert in each of his subcontracts the provisions contained in Paragraphs (1), (3), (4), (5), (6), and (7) above and also a clause requiring the subcontractors to include these provisions in any lower tier subcontracts which they may enter into, together with a clause requiring this insertion in any further subcontracts that may in turn be made.
- (9) <u>Contract Termination</u>. A breach of Paragraph (6), (7), and (8) above may be grounds for termination of the contract.

#### PROVISIONS REQUIRED BY THE REGULATIONS OF THE SECRETARY OF LABOR 29 CFR 5.5

- (a) Contract Provisions and Related Matters.
  - (1) Minimum Wages.

Revised 1/92

- (i) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provision of paragraph (a)(1)(iv) of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in paragraph 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: provided, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph (a)(1)(ii) of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.
- (ii)(A) The contracting officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefor only when the following criteria have been met:
  - (1) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
    - (2) The classification is utilized in the area by the construction industry; and
  - (3) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (ii)(B) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, D.C. 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary. (Approved by the Office of Management and Budget under OMB control number 1215-0140).
- (ii)(C) In the event the Contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary. (Approved by the Office of Management and Budget under OMB control number 1215-0140).

- (ii)(D) The wage rate (including fringe benefits where appropriate) determined pursuant to subparagraphs (1)(B) or (C) of this paragraph, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- (iii) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- (iv) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, provided, that the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program. (Approved by the Office of Management and Budget under OMB control number 1215-0140).
- (2) Withholding. The Federal Aviation Administration shall upon its own action or written request of an authorized representative of the Department of Labor withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same prime Contractor, or any other Federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the (Agency) may, after written notice to the Contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

#### (3) Payrolls and basic records.

- (i) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such work, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs. (Approved by the Office Management and Budget under OMB control numbers 1215-0140 and 1215-0017).
- (ii)(A) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Federal Aviation Administration if the agency is a party to the contract, but if the agency is not such a party, the Contractor will submit the payrolls to the applicant, sponsor, or owner, as the case may be, for transmission to the Federal Aviation Administration. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph 5.5(a)(3)(i) of Regulations, 29 CFR Part 5. This information may be submitted in any form desired.

Optional Form WH-347 is available for this purpose and may be purchased from the Superintendent of Documents (Federal Stock Number 029-005-00014-1), U.S. Government Printing Office, Washington, D.C. 20402. The prime Contractor is responsible for the submission of copies of payrolls by all subcontractors. (Approved by the Office of Management and Budget under OMB control number 1215-0149).

- (ii)(B) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor, or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
  - (1) That the payroll for the payroll period contains the information required to be maintained under paragraph 5.5(a)(3)(i) of Regulations, 29 CFR Part 5 and that such information is correct and complete;
  - (2) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR Part 3;
  - (3) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed as specified in the applicable wage determination incorporated into the contract.
- (ii)(C) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph (a)(3)(ii)(B) of this section.
- (ii)(D) The falsification of any of the above certifications may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 231 of Title 31 of the United States Code.
- (iii) The Contractor or subcontractor shall make the records required under paragraph (a)(3)(i) of this section available for inspection, copying, or transcription by authorized representatives of the (write the name of the agency) or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit the required records or to make them available, the Federal agency may, after written notice to the Contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

# (4) Apprentices and Trainees

(i) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as a apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a Contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or

subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

- (ii) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ration permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the contract will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (iii) Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.
- (5) Compliance with Copeland Act requirements. The Contractor shall comply with the requirements of 29 CFR Part 3, which are incorporated by reference in this contract.
- (6) Subcontracts. The Contractor or subcontractor shall insert in any subcontracts the clauses contained in paragraph (a)(1) through (10) of this contract and such other clauses as the Federal Aviation Administration may by appropriate instructions require, and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime Contractor shall be responsible for the compliance by an subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.
- (7) Contract determination: debarment. A breach of these contract clauses paragraphs (a)(1) through (10) and the 2nd clause (b)(1) through (5) below may be grounds for termination of the contract and for debarment as a Contractor and a subcontractor as provided in 29 CFR 5.12.
- (8) Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are herein incorporated by referenced in this contract.
- (9) Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR Parts 5, 6, and 7. Disputes within the meaning

of this clause include disputes between the Contractor (or any of its subcontractors ) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

#### (10) Certification of Eligibility.

- (i) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- (ii) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- (iii) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.
- (b) Contract Work Hours and Safety Standards Act. The Agency Head shall cause or require the contracting officer to insert the following clauses set forth in paragraphs (b)(1), (2), (3), (4) and (5) of this section in full in AIP construction contracts in excess of \$2,000. These clauses shall be inserted in addition to the clauses required by paragraph 5.5(a) or paragraph 4.6 of Part 4 of this title. As used in this paragraph, the terms "laborers" and "mechanics" include watchmen and guards.
  - (1) Overtime requirements: No Contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers, mechanics, watchmen or guards (including apprentices and trainees described in paragraphs 5 and 6 above) shall require or permit any laborer, mechanic, watchman or guard in any workweek in which he/she is employed on such work, to work in excess of 40 hours in such workweek unless such laborer, mechanic, watchman or guard receives compensation at a rate not less than one and one-half times his/her basic rate of pay for all hours worked in excess of 40 hours in such workweek.
  - (2) Violations: Liability for Unpaid Wages; Liquidated Damages: In the event of any violation of the clause set forth in subparagraph (1) of this paragraph, the Contractor and any subcontractor responsible therefore shall be liable to any affected employee for his/her unpaid wages. In addition, such Contractor and subcontractor shall be liable to the United States (in case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer, mechanic, watchman or guard employed in violation of the clause set forth in subparagraph (1) of this paragraph, in the sum of \$10.00 for each calendar day on which such employee was required or permitted to work in excess of the standard workweek of 40 hours without payment of the overtime wages required by the clause set forth in subparagraph (1) of this paragraph.
  - (3) Withholding for unpaid wages and liquidated damages. The (write in the name of the Federal agency or the loan or grant recipient) shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the Contractor or subcontractor under any such contract or any other Federal contract with the same prime Contractor, or any other Federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime Contractor, such sums as may be determined to be necessary to satisfy any liabilities of such Contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in subparagraph (2) of this paragraph.
  - (4) Subcontracts. The Contractor or subcontractor shall insert in any subcontracts the clauses set forth in subparagraph (1) through (4) of this paragraph and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in subparagraphs (1) through (4) of this paragraph.

- (5) Working Conditions. No Contractor or subcontractor may require any laborer or mechanic employed in the performance of any contract to work in surroundings or under working conditions that are unsanitary, hazardous, or dangerous to his health or safety as determined under construction safety and health standards (29 CFR 1926) issued by Department of Labor.
- (c) In addition to the clauses contained in paragraph (b), in any contract subject only to the Contract Work Hours and Safety Standards Act and not to any of the other statutes cited in paragraph 5.1, the Agency Head shall cause or require the contracting officer to insert a clause requiring that the Contractor or subcontractor shall maintain payrolls and basic payroll records during the course of the work and shall preserve them for a period of three years from the completion of the contract for all laborers and mechanics, including guards and watchmen, working on the contract. Such records shall contain the name and address of each such employee, social security number, correct classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. Further, the Agency Head shall cause or require the contracting officer to insert in any such contract a clause providing that the records to be maintained under this paragraph shall be made available by the Contractor or subcontractor for inspection, copying, or transcription by authorized representatives of the (write the name of agency) and the Department of Labor, and the Contractor or subcontractor will permit such representatives to interview employees during working hours on the job. (Approved by the Office of Management and Budget under OMB control numbers 1215-0140 and 1215-0017).

# FEDERAL REGULATIONS VOL. 40, #74, WEDNESDAY, APRIL 16, 1975, PAGE 17124, ADMINISTRATION OF THE CLEAR AIR ACT & WATER POLLUTION CONTROL ACT (with respect to Federal Grants)

In connection with the administration of the Clean Air Act and the Water Pollution Control Act with respect to Federal Grants, specific requirements have been imposed of any contract which is not exempt under the provisions of 40 CFR 15.5.

- (1) Any facility listed on the EPA List of Violating Facilities pursuant to Paragraph 15.20 of 40 CFR as of the date of the contract award will not be utilized in the performance of any non-exempt contract or subcontract.
- (2) The Contractor shall comply with all the requirements of Section 114 of the Clean Air Act, as amended, 42 USC 1857 et seq. and Section 308 of the Federal Water Pollution Control Act, as amended, 33 USC 1251 et seq. relating to inspection, monitoring, entry, reports and information, as well as all other requirements specified in Section 114 and Section 308 of the Air Act and Water Act, respectively, and all regulations and guidelines issued thereunder after the award of the contract.
- (3) Prompt notification shall be required prior to contract award to the awarding official by the Contractor who will receive the award of the receipt of any communication from the Director, Office of Federal Activities, U.S. Environmental Protection Agency, indicating that a facility to be utilized for the contract is under consideration to be listed on the EPA List of Violating Facilities.
- (4) The Contractor shall include or cause to be included the criteria and requirements in paragraphs 1 through 4 in any non-exempt subcontract and will take such action as the Government may direct as a means of enforcing such provisions.

#### Attachment No. 1

During the performance of the contract, the Contractor agrees as follows:

- (1) The Contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex or national origin. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex or national origin. Such action shall include, but not be limited to the following: Employment, upgrading, demotion or transfer, recruitment or recruitment advertising, layoff or termination, rates of pay or other forms of compensation, and selection for training including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- (2) The Contractor will, in all solicitations or advertisements for employees placed by or on the behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex or national origin.
- (3) The Contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or worker's representatives of the Contractor's commitments under this section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (4) The Contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (5) The Contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- (6) In the event of the Contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further government contracts or federally assisted construction contracts in accordance with procedures authorized in Executive Order 11246 of 24 September 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of 24 September 1965, or by rule, regulation or order of the Secretary of Labor, or as otherwise provided by law.
- (7) The Contractor will include the portion of the sentence immediately preceding paragraph (1) and the provisions of paragraphs (1) through (7) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to Section 204 of Executive Order 11246 of 24 September 1965, so that such provisions will be binding upon each subcontractor or vendor. The Contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as means of enforcing such provisions, including sanctions for noncompliance; provided, however, that in the event a Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction by the administering agency, the Contractor may request the United States to enter into such litigation to protect the interests of the United States.

#### ATTACHMENT NO. 2

EACH PRIME CONTRACTOR SHALL INSERT IN EACH SUBCONTRACT THE CERTIFICATION IN APPENDIX B, AND FURTHER, SHALL REQUIRE ITS INCLUSION IN ANY LOWER TIER SUBCONTRACT, PURCHASE ORDER, OR TRANSACTION THAT MAY IN TURN BE MADE.
- Appendix B of 49 CFR Part 29 -

This certification applies to subcontractors, material suppliers, vendors and other lower tier participants. Appendix B--Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions

#### Instructions for Certification

- 1. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below
- 2. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.
- 3. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 4. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction, "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause sections of rules implementing Executive Order 12549. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations.
- 5. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.
- 6. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- 7. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to, check the Nonprocurement List.
- 8. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 9. Except for transactions authorized under paragraph 5 of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Covered Transactions

(1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

(2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification such prospective participant shall attach an explanation to this proposal.				

#### STATE REQUIRED CONTRACT PROVISIONS

#### ALL FEDERAL-AID CONSTRUCTION CONTRACTS

Effective February 1, 1969 Revised January 2, 1973

The following provisions are State of Illinois requirements and are in addition to the Federal requirements.

#### "EQUAL EMPLOYMENT OPPORTUNITY"

In the event of the Contractor's noncompliance with any provisions of this Equal Employment Opportunity Clause, the Illinois Fair Employment Practices Act or the Fair Employment Practices Commission's Rules and Regulations for Public Contracts, the Contractor may be declared nonresponsible and therefore ineligible for future contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations, and the contract may be canceled or avoided in whole or in part, and such other sanctions or penalties may be imposed or remedies invoked as provided by statute or regulation.

During the performance of this contract, the Contractor agrees as follows:

- (1) That it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, national origin or ancestry; and further that it will examine all job classifications to determine if minority persons or women are underutilized and will take appropriate affirmative action to rectify any such underutilization.
- (2) That, if it hires additional employees in order to perform this contract or any portion hereof, it will determine the availability (in accordance with the Commission's Rules and Regulations for Public Contracts) of minorities and women in the area(s) from which it may reasonably recruit and it will hire for each job classification for which employees are hired in such a way that minorities and women are not underutilized.
- (3) That, in all solicitations or advertisements for employees placed by it or on its behalf, it will state that all applicants will be afforded equal opportunity without discrimination because of race, color, religion, sex, national origin or ancestry.
- (4) That it will send to each labor organization or representative of workers with which it has or is bound by a collective bargaining or other agreement or understanding, a notice advising such labor organization or representative of the Contractors obligations under the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts. If any such labor organization or representative fails or refuses to cooperate with the Contractor in its efforts to comply with such Act and Rules and Regulations, the Contractor will promptly so notify the Illinois Fair Employment Practices Commission and the contracting agency and will recruit employees from other sources when necessary to fulfill its obligations thereunder.
- (5) That it will submit reports as required by the Illinois Fair Employment Practices Commission's Rules and Regulations for Public Contracts, furnish all relevant information as may from time to time be requested by the Commission or the contracting agency, and in all respects comply with the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts.
- (6) That it will permit access to all relevant books, records, accounts and work sites by personnel of the contracting agency and the Illinois Fair Employment Practices Commission for purposes of investigation to ascertain compliance with the Illinois Fair Employment Practices Act and the Commission's Rules and Regulations for Public Contracts.
- (7) That it will include verbatim or by reference the provisions of paragraphs 1 through 7 of this clause in every performance subcontract as defined in Section 2.10(b) of the Commission's Rules and Regulations for Public Contracts so that such provisions will be binding upon every subcontractor; and that it will also so include the provisions or paragraphs 1, 5, 6 and 7 in every supply subcontract as defined in Section 2.10(a) of the Commission's Rules and Regulations for Public Contracts so that such provisions will be binding upon every such subcontractor. In the same manner as with other provisions of this contract, the Contractor will be liable for compliance with applicable provisions of this clause by all its subcontractors; and further it will promptly notify the contracting agency and the Illinois Fair Employment Practices Commission in the event any subcontractor fails or refuses to comply therewith. In addition, no Contractor will utilize any subcontractor declared by the Commission to be nonresponsible and therefore ineligible for contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations.

# CONSTRUCTION CONTRACT PROCUREMENT POLICIES

#### TABLE OF CONTENTS

<b>SECTION</b>	]

Proposal Requirements and Conditions

# **SUB-SECTION**

	ADVERTISEMENT (Notice to Bidders)	
1-02	PREQUALIFICATION OF BIDDERS	46
1-03	CONTENTS OF PROPOSAL FORMS	47
	ISSUANCE OF PROPOSAL FORMS	
1-05	INTERPRETATION OF QUANTITIES IN BID SCHEDULE	47
1-06	EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE	47
1-07	PREPARATION OF THE PROPOSAL	48
	REJECTION OF PROPOSALS	
	PROPOSAL GUARANTY	
	DELIVERY OF PROPOSALS	
1-11	WITHDRAWAL OF PROPOSALS	49
	PUBLIC OPENING OF PROPOSALS	
1-13	DISQUALIFICATION OF BIDDERS	49
1-14	WORKER'S COMPENSATION INSURANCE	49

## **SECTION 2**

Award and Execution of Contract

# **SUB-SECTION**

2-01	CONSIDERATION OF PROPOSALS	50
2-02	AWARD OF CONTRACT	50
	CANCELLATION OF AWARD	
2-04	RETURN OF PROPOSAL GUARANTY	50
	REQUIREMENT OF PERFORMANCE AND PAYMENT BONDS	
2-06	EXECUTION OF CONTRACT	50
2-07	APPROVAL OF CONTRACT	51
	FAILURE TO EXECUTE CONTRACT	

#### SECTION 1

#### PROPOSAL REQUIREMENTS AND CONDITIONS

1-01 ADVERTISEMENT (Notice to Bidders). The State of Illinois shall publish the advertisement at such places and at such times as are required by local law or ordinances. The published advertisement shall state the time and place for submitting sealed proposals; a description of the proposed work; instructions to bidders as to obtaining proposal forms, plans, and specifications; proposal guaranty required; and the Owner's right to reject any and all bids.

For Federally assisted contracts the advertisement shall conform to the requirements of local laws and ordinances pertaining to letting of contracts and, in addition, shall conform to the requirements of the appropriate parts of the Federal Aviation Regulations applicable to the particular contract being advertised.

#### 1-02 PREQUALIFICATION OF BIDDERS.

(a) When the awarding authority is the State of Illinois, each prospective bidder, prior to being considered for issuance of any proposal forms will be required to file, on forms furnished by the Department, an experience questionnaire and a confidential financial statement in accordance with the Department's Instructions for Prequalification of Contractors. The Statement shall include a complete report of the prospective bidder's financial resources and liabilities, equipment, past record and personnel, and must be submitted at least thirty (30) days prior to the scheduled opening of bids in which the Contractor is interested.

After the Department has analyzed the submitted "Contractor's Statement of Experience and Financial Condition" and related information and has determined appropriate ratings, the Department will issue to the Contractor a "Certificate of Eligibility". The Certificate will permit the Contractor to obtain proposal forms and plans for any Department of Transportation letting on work which is within the limits of the Contractor's potential as indicated on his "Certificate of Eligibility", subject to any limitations due to present work under contract or pending award as determined from the Contractor's submitted "Affidavit of Availability". Bidders intending to consistently submit proposals shall submit a "Contractor's Statement of Experience and Financial Condition" at least once a year. However, prequalification may be changed during that period upon the submission of additional favorable reports or upon reports of unsatisfactory performance.

Before a proposal is issued, the prospective bidder will be required to furnish an "Affidavit of Availability" indicating the location and amount of all uncompleted work under contract, or pending award, either as principal or subcontractor, as well as a listing of all subcontractors and value of work sublet to others. The prospective bidder may be requested to file a statement showing the amount and condition of equipment which will be available.

Before an award is made, the bidder may be required to furnish an outline of his plans for conducting the work.

(b) When the awarding authority for contract construction work is the County Board of a county; the Council, the City Council, or the President and Board of Trustees of a city, village or town, each prospective bidder, in evidence of his competence, shall furnish the awarding authority as a prerequisite to the release of proposal forms by the awarding authority, a certified or photostatic copy of a "Certificate of Eligibility" issued by the Department of Transportation, in accordance with Section 1-02(a).

The two low bidders must file within 24 hours after the letting a sworn affidavit, in triplicate, showing all uncompleted contracts awarded to them and all low bids pending award for Federal, State, County, Municipal and private work, using the blank form made available for this affidavit. One copy shall be filed with the awarding authority and two copies with the District Highway Office.

1-03 CONTENTS OF PROPOSAL FORMS. Upon request, the Department will furnish the prequalified bidders a proposal form. This form will state the location and description of the contemplated construction and will show the estimate of the various quantities and kinds of work to be performed or materials to be furnished, and will have a schedule of items for which unit bid prices are invited. The proposal form will state the time in which work must be completed, the amount of the proposal guaranty, labor requirements, and date, time and place of the opening of proposals. The form will also include any special provisions or requirements which vary from or are not contained in these specifications.

All papers bound with or attached to the proposal form are considered a part thereof and must not be detached or altered when the proposal is submitted. Any addenda officially issued by the Department, will be considered a part of the proposal whether attached or not.

For Federally assisted contracts, the proposal shall conform to the requirements of local laws and ordinances pertaining to letting of contracts and, in addition, shall conform to the requirements of the appropriate parts of the Federal Aviation Regulations pertaining to the particular contract being let.

1-04 ISSUANCE OF PROPOSAL FORMS. The Department shall refuse to issue a proposal form for any of the following reasons:

- (a) Lack of competency and adequate machinery, plant and other equipment, as revealed by the financial statement and experience questionnaires required under Section 1-02(a).
- (b) Uncompleted work which, in the judgment of the Department, might hinder or prevent the prompt completion of additional work if awarded.
- (c) False information provided on a bidder's "Affidavit of Availability".
- (d) Failure to pay, or satisfactorily settle, all bills due for labor and material on former contracts in force at the time of issuance of proposal forms.
- (e) Failure to comply with any prequalification regulations of the Department.
- (f) Default under previous contracts.
- (g) Unsatisfactory performance record as shown by past work for the Department, judged from the standpoint of workmanship and progress.
- (h) When the Contractor is suspended from eligibility to bid at a public letting where the contract is awarded by, or require approval of, the Department.
- (i) When any agent, servant, or employee of the prospective bidder currently serves as a member, employee, or agent of a governmental body that is financially involved in the proposed work.
- (j) When any agent, servant, or employee of the prospective bidder has participated in the preparation of plans or specifications for the proposed work.

1-05 INTERPRETATION OF QUANTITIES IN BID SCHEDULE. An estimate of quantities of work to be done and materials to be furnished under these specifications is given in the proposal. It is the result of careful calculations and is believed to be correct. It is given only as a basis for comparison of proposals and the award of the contract. The Owner does not expressly or by implication agree that the actual quantities involved will correspond exactly therewith; nor shall the bidder plead misunderstanding or deception because of such estimates of quantities, or of the character, location, or other conditions pertaining to the work. Payment to the Contractor will be made only for the actual quantities of work performed or materials furnished in accordance with the plans and specifications. It is understood that the quantities may be increased or decreased as provided in the subsection titled ALTERATION OF WORK AND QUANTITIES of Section 20 of the Illinois Standard Specifications for Construction of Airports without in any way invalidating the unit bid prices.

1-06 EXAMINATION OF PLANS, SPECIFICATIONS, AND SITE. The bidder is expected to carefully examine the site of the proposed work, the proposal, plans, specifications, and contract forms. He shall satisfy himself as to the character, quality, and quantities of work to be performed, materials to be furnished, and as to the requirements of the proposed contract. The submission of a proposal shall be prima facie evidence that the bidder has made such examination and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the proposed contract, plans, and specifications.

Boring logs, underground utilities and other records of subsurface investigations and tests are available for inspection of bidders. It is understood and agreed that such subsurface information, whether included in the plans, specifications, or otherwise made available to the bidder, was obtained and is intended for the Owner's design and estimating purposes only. Such information has been made available for the convenience of all bidders. It is further understood and agreed that each bidder is solely responsible for all assumptions, deductions, or conclusions which he may make or obtain from his examination of the boring logs and other records of subsurface investigations and tests that are furnished by the Owner.

1-07 PREPARATION OF THE PROPOSAL. The bidder shall submit his proposal on the form furnished by the Department. The proposal shall be executed property, and bids shall be made for all items indicated in the proposal form, except that when alternate bids are asked, a bid on more than one alternate for each item is not required, unless otherwise provided. The bidder shall indicate, in figures, a unit price for each of the separate items called for in the proposal; he shall show the products of the respective quantities and unit prices in the column provided for that purpose, and the gross sum shown in the place indicated in the proposal shall be the summation of said products. All writing shall be with ink or typewriter, except the signature of the bidder which shall be written with ink.

If the proposal is made by an individual, his name and business address shall be shown. If made by a firm or partnership, the name and business address of each member of the firm or partnership shall be shown. If made by a corporation, the proposal shall show the names, titles, and business address of the president, secretary, and treasurer, and the seal of the corporation shall be affixed and attested by the secretary.

The proposal shall be issued to a prequalified bidder in the same name and style as the financial statement used for prequalification and shall be submitted in like manner.

1-08 REJECTION OF PROPOSALS. The Department reserves the right to reject proposals for any of the conditions in Article 1-04 or for any of the following reasons:

- (a) More than one proposal for the same work from an individual, firm, partnership, or corporation under the same or different names.
- (b) Evidence of collusion among bidders.
- (c) Unbalanced proposals in which the prices for some items are obviously out of proportion to the prices for other items.
- (d) If the proposal does not contain a unit price for each pay item listed except in the case of authorized alternate pay items or lump sum pay items.
- (e) If the proposal is other than that furnished by the Department; or if the form is altered or any part thereof is detached.
- (f) If there are omissions, erasures, alterations, unauthorized additions, conditional or alternate bids, or irregularities of any kind which may tend to make the proposal incomplete, indefinite, or ambiguous as to its meaning.
- (g) If the bidder adds any provisions reserving the right to accept or reject an award, or to enter into a contract pursuant to an award.
- (h) If the proposal is not accompanied by the proper proposal guaranty.
- (i) If the proposal is prepared with other than ink or typewriter.
- (j) If the proposal is submitted in any other name other than that to whom it was issued by the Department.

1-09 PROPOSAL GUARANTY. Each Proposal shall be accompanied by either a bid bond on the Department of Transportation, Division of Aeronautics form contained in the proposal, executed by a corporate surety company satisfactory to the Department or by a bank cashier's check or a properly certified check for not less than 5 percent of the amount bid.

Bank cashier's checks, or properly certified checks accompanying proposals shall be made payable to the Treasurer, State of Illinois.

- 1-10 DELIVERY OF PROPOSALS. Each proposal should be submitted in a special envelope furnished by the Department. The blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Department is used, it shall be of the same general size and shape and be similarly marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Department at the address and in care of the official in whose office the bids are to be received. All proposals shall be filed prior to the time and place specified in the Notice to Bidders. Proposals received after the time for opening of bids will be returned to the bidder unopened.
- 1-11 WITHDRAWAL OF PROPOSALS. Permission will be given a bidder to withdraw a proposal if he makes his request in writing or by telegram before the time for opening proposals. If a proposal is withdrawn, the bidder will not be permitted to resubmit this proposal at the same letting. With the approval of the Engineer, a bidder may withdraw a proposal and substitute a new proposal prior to the time of opening bids.
- 1-12 PUBLIC OPENING OF PROPOSALS. Proposals will be opened and read publicly at the time and place specified in the Notice to Bidders. Bidders, their authorized agents, and other interested parties are invited to be present.
- 1-13 DISQUALIFICATION OF BIDDERS. A bidder shall be considered disqualified for any of the following reasons:
  - (a) Submitting more than one proposal from the same partnership, firm, or corporation under the same or different name.
  - (b) Evidence of collusion among bidders. Bidders participating in such collusion shall be disqualified as bidders for any future work of the Owner.
  - (c) If the bidder is considered to be in "default" for any reason specified in the Subsection 1-04 titled ISSUANCE OF PROPOSAL FORMS of this section.
- 1-14 WORKER'S COMPENSATION INSURANCE. Prior to the approval of his contract by the Division, the Contractor shall furnish to the Division certificates of insurance covering Worker's Compensation, or satisfactory evidence that this liability is otherwise taken care of in accordance with Section 4.(a) of the "Worker's Compensation Act of the State of Illinois" as amended.

#### **SECTION 2**

#### AWARD AND EXECUTION OF CONTRACT

2-01 CONSIDERATION OF PROPOSALS. After the proposals are publicly opened and read, they will be compared on the basis of the summation of the products obtained by multiplying the estimated quantities shown in the proposal by the unit bid prices. In the event of a discrepancy between unit bid prices and extensions, the unit bid price shall govern.

Until the award of a contract is made, the Owner reserves the right to reject a bidder's proposal for any of the following reasons:

- (a) If the proposal is irregular as specified in the subsection titled REJECTION OF PROPOSALS of Section 1.
- (b) If the bidder is disqualified for any of the reasons specified in the subsection titled DISQUALIFICATION OF BIDDERS of Section 1.

In addition, until the award of a contract is made, the Owner reserves the right to reject any or all proposals; waive technicalities, if such waiver is in the best interest of the Owner and is in conformance with applicable State and Local laws or regulations pertaining to the letting of construction contracts; advertise for new proposals; or proceed with the work otherwise.

2-02 AWARD OF CONTRACT. The award of contract will be made within 60 calendar days after the opening of proposals to the lowest responsible and qualified bidder whose proposal complies with all the requirements prescribed. The successful bidder will be notified by letter, that his bid has been accepted, and that he has been awarded the contract.

If a contract is not awarded within 60 days after the opening of proposals, a bidder may file a written request with the Division for the withdrawal of his bid and the Division will permit such withdrawal.

For Federally assisted contracts, unless otherwise specified in this subsection, no award shall be made until the FAA has concurred in the Owner's recommendation to make such award and has approved the Owner's proposal contract to the extent that such concurrence and approval are required by Federal Regulations.

- 2-03 CANCELLATION OF AWARD. The Division reserves the right to cancel the award without liability to the bidder at any time before a contract has been fully executed by all parties and is approved by the Owner in accordance with the subsection titled APPROVAL OF CONTRACT of this section. The Division at the time of cancellation will return the proposal guaranty.
- 2-04 RETURN OF PROPOSAL GUARANTY. The proposal guaranties of all except the two lowest bidders will be returned promptly after the proposals have been checked, tabulated, and the relation of the proposals established. Proposal guaranties of the two lowest bidders will be returned as soon as the Construction Contract, Performance Bonds, and Payment Bonds of the successful bidder have been properly executed and approved.

If any other form of proposal guaranty is used, other than a bid bond, a bid bond may be substituted at the Contractor's option.

2-05 REQUIREMENT OF PERFORMANCE AND PAYMENT BONDS. The successful bidder for a contract, at the time of the execution of the contract, shall deposit with the Division separate performance and payment bonds each for the full amount of the contract. The form of the bonds shall be that furnished by the Division, and the sureties shall be acceptable to the Division.

2-06 EXECUTION OF CONTRACT. The successful bidder shall sign (execute) the Contract and shall return the signed Contract to the Owner (Sponsor) for signature (execution) and subsequently return all copies to the Division. The fully executed surety bonds specified in the subsection title REQUIREMENTS OF PERFORMANCE AND

PAYMENT BONDS of this section will be forwarded to the Division within 15 days of the date mailed or otherwise delivered to the successful bidder. If the Contract and Bonds are mailed, special handling is recommended.

If the bidder to whom award is to be made is a corporation organized under the laws of a State other than Illinois, the bidder shall furnish the Division a copy of the corporation's certificate of authority to do business in the State of Illinois with the return of the executed contract and bond. Failure to furnish such evidence of a certificate of authority within the time required will be considered as just cause for the annulment of the award and the forfeiture of the proposal guaranty to the State, not as a penalty, but in payment of liquidated damages sustained as a result of such failure.

2-07 APPROVAL OF CONTRACT. Upon receipt of the contract and bonds that have been executed by the successful bidder, the Owner shall complete the execution of the contract in accordance with local laws or ordinances, and return the contract to the Division for approval and execution by the Division. Delivery of the fully executed contract to the Contractor shall constitute the Department's approval to be bound by the successful bidder's proposal and the terms of the contract.

2-08 FAILURE TO EXECUTE CONTRACT. If the contract is not executed by the Division within 15 days following receipt from the bidder of the properly executed contracts and bonds, the bidder shall have the right to withdraw his bid without penalty.

Failure of the successful bidder to execute the contract and file acceptable bonds within 15 days after the contract has been mailed to him shall be just cause for the cancellation of the award and the forfeiture of the proposal guaranty which shall become the property of the State, not as a penalty, but as liquidation of damages sustained.

#### ILLINOIS DEPARTMENT OF TRANSPORTATION

#### **DIVISION OF AERONAUTICS**

The requirements of the following provisions written for Federally-assisted construction contracts, including all goals and timetables and affirmative action steps, shall also apply to all State-funded construction contracts awarded by the Illinois Department of Transportation.

#### NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)

- 1. The Offeror's or Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.
- 2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

#### APPENDIX A

The following goal for female utilization in each construction craft and trade shall apply to all Contractors holding Federal and federally assisted construction contracts and subcontracts in excess of \$10,000. The goal is applicable to the Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a Federal, federally assisted or nonfederally related construction contact or subcontract.

#### AREA COVERED (STATEWIDE)

Goals for Women apply nationwide.

GOAL

	Goal (percent)	
Female Utilization.		6.9

#### APPENDIX B

Until further notice, the following goals for minority utilization in each construction craft and trade shall apply to all Contractors holding Federal and federally-assisted construction contracts and subcontracts in excess of \$10,000. to be performed in the respective geographical areas. The goals are applicable to the Contractor's total onsite construction workforce, regardless of whether or not part of that workforce is performing work on a Federal, federally-assisted or nonfederally related construction contract or subcontract.

Economic Area	Goal
Economic Area	(percent)
056 Paducah, KY:	
Non-SMSA Counties -	5.2
IL - Hardin, Massac, Pope	
KY - Ballard, Caldwell, Calloway, Carlisle, Crittenden,	
Fulton, Graves, Hickman, Livingston, Lyon, McCracken, Marshall	

Economic Area	Goal (percent)
080 Evansville, IN: Non-SMSA Counties - IL - Edwards, Gallatin, Hamilton, Lawrence, Saline, Wabash, White IN - Dubois, Knox, Perry, Pike, Spencer KY - Hancock, Hopkins, McLean, Mublenberg, Ohio, Union, Webster	3.5
081 Terre Haute, IN: Non-SMSA Counties - IL - Clark, Crawford IN - Parke	2.5
083 Chicago, IL: SMSA Counties: 1600 Chicago, IL - IL - Cook, DuPage, Kane, Lake, McHenry, Will	19.6
3740 Kankakee, IL - IL - Kankakee	9.1
Non-SMSA Counties IL - Bureau, DeKalb, Grundy, Iroquois, Kendall, LaSalle, Livingston, Putnam IN - Jasper, Laporte, Newton, Pulaski, Starke	18.4
084 Champaign - Urbana, IL: SMSA Counties: 1400 Champaign - Urbana - Rantoul, IL - IL - Champaign	7.8
Non-SMSA Counties - IL - Coles, Cumberland, Douglas, Edgar, Ford, Piatt, Vermilion	4.8
085 Springfield - Decatur, IL: SMSA Counties: 2040 Decatur, IL - IL - Macon	7.6
7880 Springfield, IL - IL - Mendard, Sangamon	4.5
Non-SMSA Counties IL - Cass, Christian, Dewitt, Logan, Morgan, Moultrie, Scott, Shelby	4.0
086 Quincy, IL: Non-SMSA Counties	3.1
IL - Adams, Brown, Pike MO - Lewis, Marion, Pike, Ralls	

## APPENDIX B (CONTINUED)

Economic Area	Goal (percent)
087 Peoria, IL: SMSA Counties: 1040 Bloomington - Normal, IL - IL - McLean	2.5
6120 Peoria, IL - IL - Peoria, Tazewell, Woodford	4.4
Non-SMSA Counties - IL - Fulton, Knox, McDonough, Marshall, Mason, Schuyler, Stark, Warren	3.3
088 Rockford, IL: SMSA Counties: 6880 Rockford, IL - IL - Boone, Winnebago	6.3
Non-SMSA Counties - IL - Lee, Ogle, Stephenson	4.6
098 Dubuque, IA: Non-SMSA Counties - IL - JoDaviess IA - Atlamakee, Clayton, Delaware, Jackson, Winnesheik WI - Crawford, Grant, Lafayette	0.5
099 Davenport, Rock Island, Moline, IA - IL: SMSA Counties: 1960 Davenport, Rock Island, Moline, IA - IL - IL - Henry, Rock Island IA - Scott	4.6
Non-SMSA Counties - IL - Carroll, Hancock, Henderson, Mercer, Whiteside IA - Clinton, DesMoines, Henry, Lee, Louisa, Muscatine MO - Clark	3.4
107 St. Louis, MO: SMSA Counties: 7040 St. Louis, MO - IL - IL - Clinton, Madison, Monroe, St. Clair MO - Franklin, Jefferson, St. Charles, St. Louis, St. Louis City	14.7
<ul> <li>Non-SMSA Counties -</li> <li>IL - Alexander, Bond, Calhoun, Clay, Effingham, Fayette, Franklin, Greene, Jackson, Jasper, Jefferson, Jersey, Johnson, Macoupin, Marion, Montgomery, Perry, Pulaski, Randolph, Richland, Union, Washington, Wayne, Williamson</li> <li>MO - Bollinger, Butler, Cape Girardeau, Carter, Crawford, Dent, Gasconade, Iron, Lincoln, Madison, Maries, Mississippi, Montgomery, Perry, Phelps, Reynolds, Ripley, St. Francois, St. Genevieve, Scott, Stoddard, Warren, Washington, Wayne</li> </ul>	11.4

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the Contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The Contractor's compliance with Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the provisions and specifications set forth in its federally assisted contracts, and its efforts to meet the goals established for the geographical area where the contract resulting from this solicitation is to be performed. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

- 3. The Illinois Division of Aeronautics will provide written notification to the Director of the Office of Federal Contract Compliance Programs within 10 working days of award of any construction contract and/or subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. This notification will list the name, address and telephone number of the subcontractor; employer identification number; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the contract is to be performed.
- 4. As used in this Notice, and in the contract resulting from this solicitation, the "covered area" is the entire State of Illinois for the goal set forth in APPENDIX A and the county or counties in which the work is located for the goals set forth in APPENDIX B.

#### STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY CONSTRUCTION CONTRACT SPECIFICATIONS (EXECUTIVE ORDER 11246)

- 1. As used in these specifications:
  - a) "Covered area" means the geographical area described in the solicitation from which this contract resulted;
  - b) "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;
  - c) "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941;
  - d) "Minority" includes:
    - (i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);
    - (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American or other Spanish Culture or origin, regardless of race);
    - (iii) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
    - (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
- 2. Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000. the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.
- 3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.
- 4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered Construction Contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. Goals are published periodically in the Federal Register in notice form, and such notices may be obtained from any Office of Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress toward its goals in each craft during the period specified.
- 5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.

- 6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
- 7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
  - a) Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working as such sites or in such facilities.
  - b) Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.
  - Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractors may have taken.
  - d) Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
  - e) Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
  - f) Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreements; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.

- g) Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with onsite supervisory personnel such as Superintendents, General Foreman, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- h) Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i) Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship of other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
- j) Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's workforce.
- k) Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.
- Conduct, at least annually, an inventory and evaluation at least of all minority and female
  personnel for promotional opportunities and encourage these employees to seek or to prepare for,
  through appropriate training, etc., such opportunities.
- m) Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- n) Ensure that all facilities and company activities are nonsegregated except that separate or singleuser toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
- Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction Contractors and suppliers, including circulation of solicitations to minority and female Contractor associations and other business associations.
- p) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.

- 8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through p). The efforts of a Contractor association, joint Contractor-union, Contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through p of these Specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.
- 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specified minority group of women is underutilized).
- 10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.
- 11. The Contractor shall not enter into any Subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
- 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
- 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy his requirement, Contractors shall not be required to maintain separate records.
- 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

#### ANNUAL EEO-1 REPORT TO JOINT REPORTING COMMITTEE AS REQUIRED AT

#### 41 CFR 60-1.7(a)

Any Contractor having a Federal contract of \$50,000 or more and 50 or more employees is required to file annual compliance reports on Standard Form 100 (EEO-1) with the Joint Reporting Committee in accordance with the instructions provided with the form. The Contractor will provide a copy of such a report to the contracting agency within 30 days after the award of a contract.

The Contractor shall require its subcontractors to file an SF 100 within 30 days after award of the subcontract if (1) it is not exempt from the provisions of these regulations in accordance with 60-1.5, (2) has 50 or more employees, (3) first tier subcontractor, and (4) has a subcontract amounting to \$50,000 or more.

Subcontractors below the first tier which perform construction work at the site of construction shall be required to file such a report if (1) it is not exempt from the provisions of these regulations in accordance with 60-1.5, (2) has 50 or more employees and has a subcontract amounting to \$50,000 or more.

The SF 100 is available at the following address:

Joint Reports Committee EEOC - Survey Division 1801 "L" Street N.W. Washington, D.C. 20750

Phone (202) 663-4968

#### DISADVANTAGED BUSINESS POLICY

#### I. NOTICE

This proposal contains the special provision entitled "Required Disadvantaged Business Participation." Inclusion of this Special Provision in this contract satisfies the obligations of the Department of Transportation under federal law as implemented by 49 CFR 23 and under the Illinois "Minority and Female Business Enterprise Act."

#### II. POLICY

It is public policy that the businesses defined in 49 CFR Part 23 shall have the maximum opportunity to participate in the performance of contracts financed in whole or in part with State or Federal funds. Consequently, the requirements of 49 CFR Part 23 apply to this contract.

#### III. OBLIGATION

The Contractor agrees to ensure that the businesses defined in 49 CFR Part 23 have the maximum opportunity to participate in the performance of this contract. In this regard, the Contractor shall take all necessary and reasonable steps, in accordance with 49 CFR Part 23, to ensure that the said businesses have the maximum opportunity to compete for and perform portions of this contract. The Contractor shall not discriminate on the basis of race, color, national origin, or sex in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

The Contractor shall include the above Policy and Obligation statements of this Special Provision in every subcontract, including procurement of materials and leases of equipment.

## IV. DBE/WBE CONTRACTOR FINANCE PROGRAM

On contracts where a loan has been obtained through the DBE/WBE Contractor Finance Program, the Contractor shall cooperate with the Department by making all payments due to the DBE/WBE Contractor by means of a two-payee check payable to the Lender (Bank) and the Borrower (DBE/WBE Contractor).

#### V. BREACH OF CONTRACT

Failure to carry out the requirements set forth above and in the Special Provision shall constitute a breach of contract and may result in termination of the contract or liquidated damages as provided in the special provision.

(Rev. 9/21/92)

# State of Illinois Department of Transportation

# SPECIAL PROVISION FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION

- I. <u>FEDERAL OBLIGATION</u>: The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR part 26 and listed in the DBE Directory or most recent addendum.
- II. <u>CONTRACTOR ASSURANCE</u>: The Contractor makes the following assurance and agrees to include the assurance in each subcontract that the Contractor signs with a subcontractor:

The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of federally-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate.

- III. OVERALL GOAL SET FOR THE DEPARTMENT: As a requirement of compliance with 49 CFR part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal is 22.7% of all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve this goal. The dollar amount paid to all approved DBE firms performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.
- IV. CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR: This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined that the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. This determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates that, in the absence of unlawful discrimination, and in an arena of fair and open competition, DBE companies can be expected to perform 10.0% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set forth in this Special Provision:
  - A. The bidder documents that firmly committed DBE participation has been obtained to meet the goal; or
  - B. The bidder documents that a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

- V. <u>DBE LOCATOR REFERENCES:</u> Bidders may consult the DBE Directory as a reference source for DBE companies certified by the Department. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217)785-4611, or by visiting the Department's web site at www.dot.state.il.us.
- VI. <u>BIDDING PROCEDURES:</u> Compliance with the bidding procedures of this Special Provision is required prior to the award of the contract and the failure of the as-read low bidder to comply will render the bid nonresponsive.
  - A. In order to assure the timely award of the contract, the as-read low bidder must submit a Disadvantaged Business Utilization Plan on Department form SBE 2026 within seven (7) working days after the date of letting. To meet the seven (7) day requirement, the bidder may send the Plan by certified mail or delivery service within the seven (7) working day period. If a question arises concerning the mailing date of a Plan, the mailing date will be established by the U.S. Postal Service postmark on the original certified mail receipt from the U.S. Postal Service or the receipt issued by a delivery service. It is the responsibility of the as-read low bidder to ensure that the postmark or receipt date is affixed within the seven (7) working days if the bidder intends to rely upon mailing or delivery to satisfy the submission day requirement. The Plan is to be submitted to the Department of Transportation, Bureau of Small Business Enterprises, Contract Compliance Section, 2300 South Dirksen Parkway, Room 319, Springfield, Illinois 62764 (Telefax: (217) 785-1524). It is the responsibility of the bidder to obtain confirmation of telefax delivery. The Department will not accept a Utilization Plan if it does not meet the seven (7) day submittal requirement, and the bid will be declared nonresponsive. In the event the bid is declared nonresponsive due to a failure to submit a Plan or failure to comply with the bidding procedures set forth herein, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty, and may deny authorization to bid the project if re-advertised for bids. The Department reserves the right to invite any other bidder to submit a Utilization Plan at any time for award consideration or to extend the time for award.
  - B. The Utilization Plan shall indicate that the bidder either has obtained sufficient DBE participation commitments to meet the contract goal or has not obtained enough DBE participation commitments in spite of a good faith effort to meet the goal. The Utilization Plan shall further provide the name, telephone number and telefax number of a responsible official of the bidder designated for purposes of notification of plan approval or disapproval under the procedures of this Special Provision.
  - C. The Utilization Plan shall include a DBE Participation Commitment Statement, Department form SBE 2025, for each DBE proposed for the performance of work to achieve the contract goal. The signatures on these forms must be original signatures. All elements of information indicated on the said form shall be provided, including but not limited to the following:
    - 1. The name and address of each DBE to be used;
    - 2. A description, including pay item numbers, of the commercially useful work to be done by each DBE;
    - 3. The price to be paid to each DBE for the identified work specifically stating the quantity, unit price and total subcontract price for the work to be completed by the DBE. If partial pay items are to be performed by the DBE, indicate the portion of each item, a unit price where appropriate and the subcontract price amount;
    - 4. A commitment statement signed by the bidder and each DBE evidencing availability and intent to perform commercially useful work on the project; and
    - 5. If the bidder is a joint venture comprised of DBE firms and non-DBE firms, the plan must also include a clear identification of the portion of the work to be performed by the DBE partner(s).

- D. The contract will not be awarded until the Utilization Plan submitted by the bidder is approved. The Utilization Plan will be approved by the Department if the Plan commits sufficient commercially useful DBE work performance to meet the contract goal. The Utilization Plan will not be approved by the Department if the Plan does not commit sufficient DBE performance to meet the contract goal unless the bidder documents that it made a good faith effort to meet the goal. The good faith procedures of Section VIII of this special provision apply. If the Utilization Plan is not approved because it is deficient in a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no less than a five (5) working day period in order to cure the deficiency.
- VII. <u>CALCULATING DBE PARTICIPATION</u>: The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR part 26.55, the provisions of which govern over the summary contained herein.
  - A. DBE as the Contractor: 100% goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE firm does not count toward the DBE goals.
  - B. DBE as a joint venture Contractor: 100% goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
  - C. DBE as a subcontractor: 100% goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontractor in turn subcontracts to a non-DBE firm does not count toward the DBE goal.
  - D. DBE as a trucker: 100% goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed and insured by the DBE must be used on the contact. Credit will be given for the full value of all such DBE trucks operated using DBE employed drivers. Goal credit will be limited to the value of the reasonable fee or commission received by the DBE if trucks are leased from a non-DBE company.
  - E. DBE as a material supplier:
    - 1. 60% goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
    - 2. 100% goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
    - 3. 100% credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a regular dealer or manufacturer.
- VIII. GOOD FAITH EFFORT PROCEDURES: If the bidder cannot obtain sufficient DBE commitments to meet the contract goal, the bidder must document in the Utilization Plan the good faith efforts made in the attempt to meet the goal. This means that the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which could reasonably be expected to obtain sufficient DBE participation. The Department will consider the quality, quantity and intensity of the kinds of efforts that the bidder has made. Mere *pro forma* efforts are not good faith efforts; rather, the bidder is expected to have taken those efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- A. The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases, and will be considered by the Department.
  - 1. Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
  - 2. Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces.
  - 3. Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
  - 4. (a) Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.
    - (b) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable.
  - 5. Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the contractor's efforts to meet the project goal.
  - 6. Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
  - 7. Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
  - 8. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- B. If the Department determines that the Contractor has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided that it is otherwise eligible for award. If the Department determines that a good faith effort has

not been made, the Department will notify the bidder of that preliminary determination by contacting the responsible company official designated in the Utilization Plan. The preliminary determination shall include a statement of reasons why good faith efforts have not been found, and may include additional good faith efforts that the bidder could take. The notification will designate a five (5) working day period during which the bidder shall take additional efforts. The bidder is not limited by a statement of additional efforts, but may take other action beyond any stated additional efforts in order to obtain additional DBE commitments. The bidder shall submit an amended Utilization Plan if additional DBE commitments to meet the contract goal are secured. If additional DBE commitments sufficient to meet the contract goal are not secured, the bidder shall report the final good faith efforts made in the time allotted. All additional efforts taken by the bidder will be considered as part of the bidder's good faith efforts. If the bidder is not able to meet the goal after taking additional efforts, the Department will make a pre-final determination of the good faith efforts of the bidder and will notify the designated responsible company official of the reasons for an adverse determination.

- C. The bidder may request administrative reconsideration of a pre-final determination adverse to the bidder within the five (5) working days after the notification date of the determination by delivering the request to the Department of Transportation, Division of Aeronautics, 1 Langhorne Bond Drive, Capital Airport, Springfield, IL 62707-8415 (Telefax: 217-785-4533). Deposit of the request in the United States mail on or before the fifth business day shall not be deemed delivery. The pre-final determination shall become final if a request is not made and delivered. A request may provide additional written documentation and/or argument concerning the issue of whether an adequate good faith effort was made to meet the contract goal. In addition, the request shall be considered a consent by the bidder to extend the time for award. The request will be forwarded to the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person in order to consider all issues of whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten (10) working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid nonresponsive.
- IX. CONTRACT COMPLIANCE: Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal.
  - A. No amendment to the Utilization Plan may be made without prior written approval from the Division of Aeronautics. All requests for amendment to the Utilization Plan shall be submitted to the Department of Transportation, Division of Aeronautics, 1 Langhorne Bond Drive, Capital Airport, Springfield, IL 62707-8415. Telephone number (217) 785-8514. Telefax number (217) 785-4533.
  - B. All work indicated for performance by an approved DBE shall be performed, managed and supervised by the DBE executing the Participation Statement. The Contractor shall not terminate for convenience a DBE listed in the Utilization Plan and then perform the work of the terminated DBE with its own forces, those of an affiliate or those of another subcontractor, whether DBE or not, without first obtaining the written consent of the Bureau of Small Business Enterprises to amend the Utilization Plan. If a DBE listed in the Utilization Plan is terminated for reasons other than convenience, or fails to complete its work on the contract for any reason, the Contractor shall make good faith efforts to find another DBE to

66

substitute for the terminated DBE. The good faith efforts shall be directed at finding another DBE to perform at least the same amount of work under the contract as the DBE that was terminated, but only to the extent needed to meet the contract goal or the amended contract goal. The Contractor shall notify the Division of Aeronautics of any termination for reasons other than convenience, and shall obtain approval for inclusion of the substitute DBE in the Utilization Plan. If good faith efforts following a termination of a DBE for cause are not successful, the Contractor shall contact the Division and provide a full accounting of the efforts undertaken to obtain substitute DBE participation. The Division will evaluate the good faith efforts in light of all circumstances surrounding the performance status of the contract, and determine whether the contract goal should be amended.

- C. The Contractor shall maintain a record of payments for work performed to the DBE participants. The records shall be made available to the Department for inspection upon request. After the performance of the final item of work or delivery of material by a DBE and final payment therefor to the DBE by the Contractor, but not later than thirty (30) calendar days after payment has been made by the Department to the Contractor for such work or material without regard to any retainage withheld by the Department, the Contractor shall submit a DBE Payment Report on Department form SBE 2115 to the Division's Chief Engineer. If full and final payment has not been made to the DBE, the Report shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes that the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Plan, the Department will deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages.
- D. The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.

#### Certification of Nonsegregated Facilities - as Required by 41 CFR 60-1.8

(Applicable to (1) contracts, (2) subcontracts, and (3) agreements with applicants who are themselves performing federally assisted construction contracts, exceeding \$10,000.00 which are not exempt from the provisions of the Equal Opportunity clause).

By the submission of this bid, the bidder, offeror, applicant, or subcontractor certifies that he does not maintain or provide for his employees any segregated facilities at any of his establishments and that that he does not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. He certifies further that he will not maintain or provide for his employees any segregated facilities at any of his establishments and that he will not permit his employees to perform their services at any location, under his control, where segregated facilities are maintained. The bidder, offeror, applicant, or subcontractor agrees that a breach of his certification is a violation of the Equal opportunity clause in this contract. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, or national origin, because of habit, local custom, or otherwise. He further agrees that (except where he has obtained identical certifications from proposed subcontractors for specific time periods) he will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000.00 which are not exempt from the provisions of the Equal Opportunity clause; that he will retain such certifications in his files and that he will forward the following notice to such proposed subcontractors (except where the proposed subcontractors have submitted identical certifications for specific time periods):

## NOTICE TO PROSPECTIVE SUBCONTRACTORS OF REQUIREMENT FOR CERTIFICATIONS OF NONSEGREGATED FACILITIES

A certification of Nonsegregated Facilities must be submitted prior to the award of a subcontract exceeding \$10,000.00 which is not exempt from the provisions of the Equal Opportunity clause. The certification may be submitted either for each subcontract or for all subcontracts during a period (i.e., quarterly, semiannually or annually).

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C 1001.

## CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS Instructions for Certification

- 1. By signing and submitting this proposal, the prospective primary participant is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective primary participant to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department or agency determined to enter into this transaction. If it is later determined that the prospective primary participant knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause of default.
- 4. The prospective primary participant shall provide immediate written notice to the department or agency to whom this proposal is submitted if at any time the prospective primary participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction" "debarred" "suspended" "ineligible" "lower tier covered transaction" "participant" "person" "primary covered transaction" "principal" "proposal" and "voluntarily excluded" as used in this clause have the meaning set out in the Definitions and Coverage sections of the rules implementing Executive Order 12540. You may contact the department or agency to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective primary participant agrees by submitting this proposal that should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction unless authorized by the department or agency entering into this transaction.
- 7. The prospective primary participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion Lower Tier Transaction", provided by the department or agency entering into this covered transaction without modification in all lower covered transactions and in all solicitations for lower covered transactions.
- 8. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction unless it knows that the certification is erroneous. A participant may decide the method and frequency by which it determines the eligibility of its principals. Each participant may, but is not required to check the Nonprocurement List (Tel. #).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 8 of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

## <u>Certification Regarding Debarment, Suspension, and</u> Other Responsibility Matters - Primary Covered Transactions

- 1. The prospective primary participant certifies to the best of its knowledge and belief that it and its principals:
  - a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by an Federal department or agency;
  - b. Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain or performing a public (Federal, State or Local) transaction or contract under a public transaction: violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction or destruction of records, making false statements, or receiving stolen property;
  - c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (1)(b) of this certification; and
  - d. Have not within a three-period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- 2. Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

#### <u>CERTIFICATION REGARDING LOBBYING</u> (Applicable to contracts in excess of \$100,000):

#### Certification for Contracts, Grants, Loans and Cooperative Agreements.

The undersigned bidder certifies, to the best of his or her knowledge and belief, that:

- (1) No Federal appropriated funds have paid or will be paid, by or behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an Officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- (2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying", in accordance with its instructions.
- (3) The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

#### WORKERS' COMPENSATION INSURANCE

Prior to the execution of his construction contract by the Illinois Department of Transportation, Division of Aeronautics, hereinafter referred to as "Division", the Contractor shall furnish to the Division certificates of insurance covering Workers' Compensation, or satisfactory evidence that this liability is otherwise taken care of in accordance with Section 4.(a) of the "Workers' Compensation Act of the State of Illinois" as amended.

Such insurance, or other means of protection as herein provided, shall be kept in force until all work to be performed under the terms of the contract has been completed and accepted in accordance with the specifications, and it is hereby understood and agreed that the maintenance of such insurance or other protection, until acceptance of the work by the Division is a part of the contract. Failure to maintain such insurance, cancellation by the Industrial Commission of its approval of such other means of protection as might have been elected, or any other act which results in lack of protection under the said "Workers' Compensation Act" may be considered as a breach of the contract.

## SPECIAL PROVISION FOR DOMESTIC SOURCE FOR STEEL

Control of Materials: All steel products, as defined by the Illinois Steel Products Procurement Act, incorporated into this project shall be manufactured or produced in the United States and, in addition, shall be domestically fabricated. The Contractor shall obtain from the steel producer and/or fabricator, in addition to the mill analysis, a certification that all steel products meet these domestic source requirements.

## SPECIAL PROVISION FOR MONTHLY EMPLOYMENT REPORT

Effective: April 1, 2009

In addition to any other reporting required by the contract, the Contractor shall provide to the Division of Aeronautics, Contracts Section an employment summary for all employees working on the contract from the contract execution date to the last full pay period each month for the duration of the contract. The report may include but is not limited to:

- a) A listing of the total number of employees.
- b) The employee job classification.
- c) The total hours worked and payroll for each employee.

The report shall be completed by the Contractor and each subcontractor. Employee hours worked from home office or other off-site office hours worked related directly to this contract shall be included. Engineering consulting firms performing construction layout and material testing for the Contractor shall also be included.

Hours worked for material suppliers, services provided by purchase orders, Department employees or consulting firms performing inspection or testing for the Department shall not be included in the report.

The report shall contain all hours worked under the contract from the start of the month to the last full pay period each month and shall be submitted no later than 10 business days after the end of each month.

The report shall be submitted electronically to Christina Pearce at <u>Christina.Pearce@illinois.gov</u> in a format determined by the Division of Aeronautics, Contracts Section. See attachment for potential reporting format.

Any costs associated with complying with this provision shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

### Attachment

MONTHLY PRIME AND SUBCONTRACTOR EMPLOYMENT REPORT AMERICAN RECOVERY AND REINVESTMENT ACT						
First day of reporting period (mm/dd/yyyy):	2. Last day of reporting period (mm/dd/yyyy):	3. Notice to Proceed Date (mm/dd/yyyy)				
4. NAME AND ADDRESS OF FIRM		5. FEDERAL-AID P	ROJECT NUMBER			
		6. State Project Nur	mber or ID			
7. CONTRACTING AGENCY		8. STATE (or Federal Lands Region)				
Employment Data						
Direct, On-Project Jobs		TOTAL EMPLOYEES	TOTAL HOURS	TOTAL PAYROLL		
CONSTRUCTION	NEW HIRES					
	EXISTING EMPLOYEES					
NON - CONSTRUCTION	NEW HIRES					
	EXISTING EMPLOYEES					
<b>TOTAL</b> 10. PREPARED BY: (Signature and Titl	0)			DATE		
11. REVIEWED BY: (Signature and Title	e of State Aviation Official)			DATE		

This form is issued in accordance with the American Recovery and Reinvestment Act of 2009

## CLAUSE TO BE INCLUDED IN ALL SOLICITATIONS. CONTRACTS, AND SUBCONTRACTS RESULTING FROM PROJECTS FUNDED UNDER THE AIP

The Contractor or subcontractor, by submission of an offer and/or execution of a contract, certifies that it:

- a. is not owned or controlled by one or more citizens or nationals of a foreign country included in the list of countries that discriminate against U.S. firms published by the Office of the United States Trade Representative (USTR);
- b. has not knowingly entered into any contract or subcontract for this project with a Contractor that is a citizen or national of a foreign country on said list, or is owned or controlled directly or indirectly by one or more citizens or nationals of a foreign country on said list.
- c. has not procured any product nor subcontracted for the supply of any product for use on the project that is produced in a foreign country on said list.

Unless the restrictions of this clause are waived by the Secretary of Transportation in accordance with 49 CFR 30.17, no contract shall be awarded to a Contractor or subcontractor who is unable to certify to the above. If the Contractor knowingly procures or subcontracts for the supply of any product or service of a foreign country on the said list for use on the project, the Federal Aviation Administration may direct, through the sponsor, cancellation of the contract at no cost to the Government.

Further, the Contractor agrees that, if awarded a contract resulting from this solicitation, it will incorporate this provision for certification without modification in each contract and in all lower tier subcontracts. The Contractor may rely upon the certification of a prospective subcontractor unless it has knowledge that the certification is erroneous.

The Contractor shall provide immediate written notice to the sponsor if the Contractor learns that its certification or that of a subcontractor was erroneous when submitted or has become erroneous by reason of changed circumstances. The subcontractor agrees to provide immediate written notice to the Contractor, if at any time it learns that its certification was erroneous by reason of changed circumstances.

This certification is a material representation of fact upon which reliance was placed when making the award. If it is later determined that the Contractor or subcontractor knowingly rendered an erroneous certification, the Federal Aviation Administration may direct, through this sponsor, cancellation of the contract or subcontract for default at no cost to the Government.

Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by this provision. The knowledge and information of a Contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

This certification concerns a matter within the jurisdiction of an agency of the United States of America and the making of false, fictitious, or fraudulent certification may render the maker subject to prosecution under Title 18, United States Code, Section 1001.

## MINIMUM WAGES FOR FEDERAL AND FEDERALLY ASSISTED CONSTRUCTION CONTRACTS

This project is funded, in part, with Federal-aid funds and, as such, is subject to the provisions of the Davis-Bacon Act of March 3, 1931, as amended (46 Sta. 1494, as amended, 40 U.S.C. 276a) and of other Federal statutes referred to in a 29 CFR Part 1, Appendix A, as well as such additional statutes as may from time to time be enacted containing provisions for the payment of wages determined to be prevailing by the Secretary of Labor in accordance with the Davis-Bacon Act and pursuant to the provisions of 29 CFR Part 1. The prevailing rates and fringe benefits shown in the General Wage Determination Decisions issued by the U.S. Department of Labor shall, in accordance with the provisions of the foregoing statutes, constitute the minimum wages payable on Federal and federally assisted construction projects to laborers and mechanics of the specified classes engaged on contract work of the character and in the localities described therein.

General Wage Determination Decisions, modifications and supersedes decisions thereto are to be used in accordance with the provisions of 29 CFR Parts 1 and 5. Accordingly, the applicable decision, together with any modifications issued, must be made a part of every contract for performance of the described work within the geographic area indicated as required by an applicable DBRA Federal prevailing wage law and 29 CFR Part 5. The wage rates and fringe benefits contained in the General Wage Determination Decision shall be the minimum paid by contractors and subcontractors to laborers and mechanics.

#### **NOTICE**

The most current **General Wage Determination Decisions** (wage rates) are available on the IDOT web site. They are located on the Letting and Bidding page at <a href="http://www.dot.state.il.us/desenv/delett.html">http://www.dot.state.il.us/desenv/delett.html</a>.

In addition, ten (10) days prior to the letting, the applicable Federal wage rates will be e-mailed to subscribers. It is recommended that all contractors subscribe to the Federal Wage Rates List or the Contractor's Packet through IDOT's subscription service.

PLEASE NOTE: if you have already subscribed to the Contractor's Packet you will automatically receive the Federal Wage Rates.

The instructions for subscribing are at http://www.dot.state.il.us/desenv/subsc.html.

If you have any questions concerning the wage rates, please contact IDOT's Chief Contract Official at 217-782-7806.

15A QU008

#### SECTION III SPECIAL PROVISIONS FOR

## TAXIWAY P, PHASE II - MIDDLE PAVING

TAXIWAY P (1,515' X 100') PAVEMENT AND RUNWAY 5-23 (900' X 150') PAVEMENT REMOVAL/REPLACEMENT INCLUDING EARTHWORK, TAXIWAY D & E TIE-INS, LIGHTING, UNDERDRAINS, MARKING, GROOVING, UTILITY ADJUSTMENTS, AND TURFING.

AT

QUAD CITY INTERNATIONAL AIRPORT MOLINE, ILLINOIS

ILLINOIS PROJECT: MLI-3854 A.I.P. PROJECT: 3-17-0068-XX

PREPARED BY:



MARCH 20, 2009

Check

23

25

27

29

30

32

34

35

AR501001

X 24

X 26

X 28

X 31

X 33

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

290

293

295

297

299

316

338

362

365

368

370

372

373

#### **RECURRING SPECIAL PROVISIONS**

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are Applicable to this contract and are included by reference:

#### Sheet No. Item No. Page No. 1 AR101580 Refurbish 36" Beacon 155 2 AR106000 Apron Lighting 160 3 AR119000 Airport Obstruction Lighting (Not Included) 166 4 AR127000 Airport Navaid Installation (Not Included) 167 X 5 AR150510 Engineer's Field Office 168 AR150560 Temporary Threshold 6 170 7 AR152540 Soil Stabilization Fabric 173 X 8 **AR156000** Erosion Control 175 AR156513 Separation Fabric 9 180 X 10 AR156540 Riprap 182 AR201001 Bituminous Base Course - Method I 185 11 12 AR201002 Bituminous Base Course - Method II 193 AR201003 Bituminous Base Course - Method I, Superpave 13 209 AR201004 Bituminous Base Course - Method II, Superpave 14 217 15 AR201661 Clean & Seal Bituminous Cracks 230 AR201663 Sand Mix Crack Repair 233 16 17 AR201671 Crack Control Fabric 235 18 AR302000 Asphalt Treated Permeable Subbase 237 AR401001 Bituminous Surface Course - Method I 19 245 X 20 AR401002 Bituminous Surface Course - Method II 253 AR401003 Bituminous Surface Course - Method I, Superpave 21 269 AR401004 Bituminous Surface Course - Method II, Superpave 22 277

Portland Cement Concrete - Pavement Method I

AR501002 Portland Cement Concrete - Pavement Method II

AR501003 Portland Cement Concrete - Pavement Method III

AR401640 Bituminous Pavement Grooving

AR401650 Bituminous Pavement Milling

**AR401900** Remove Bituminous Pavement

AR401655 Butt Joint Construction

AR501115 Crack and Seat Pavement

AR501540 PCC Pavement Grooving

AR501900 Remove PCC Pavement

AR605000 Silicone Joint Sealing Filler

AR501550 PCC Pavement Milling

AR510500 Tie-down/Ground Rod

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## INTERIM REVISIONS TO THE

#### Supplemental Specifications and Recurring Special Provisions, Adopted July 1, 2004

#### Adopted May 11,2007

The revisions contained herein are effective for all Division of Aeronautics projects bid on or after June 15, 2007.

The following sections of the <u>Supplemental Specifications and Recurring Special Provisions</u>, <u>Adopted July 1, 2004</u> are to be deleted and replaced with the sections referenced below. These documents may be found on the Division of Aeronautics internet website at http://www.dot.state.il.us/aero/index.html.

- Supplemental Specification for Item 402 Porous Friction Course
- Check Sheet #11 Recurring Special Provision for Item AR201001 Bituminous Base Course Method I (Under 2,500 tons/pay item/location)
- Check Sheet #12 Recurring Special Provision for Item AR201002 Bituminous Base Course Method II (Over 2,500 tons/pay item/location)
- Check Sheet #13 Recurring Special Provision for Item AR201003 Bituminous Base Course Method I, Superpave (Under 2,500 tons/pay item/location)
- Check Sheet #14 Recurring Special Provision for Item AR201004 Bituminous Base Course Method II, Superpave (Over 2,500 tons/pay item/location)
- Check Sheet #19 Recurring Special Provision for Item AR401001 Bituminous Surface Course Method I (Under 2,500 tons/pay item/location)
- Check Sheet #20 Recurring Special Provision for Item AR401002 Bituminous Surface Course Method II (Over 2,500 tons/pay item/location)
- Check Sheet #21 Recurring Special Provision for Item AR401003 Bituminous Surface Course Method I, Superpave (Under 2,500 tons/pay item/location)
- Check Sheet #22 Recurring Special Provision for Item AR401004 Bituminous Surface Course Method II, Superpave (Over 2,500 tons/pay item/location)

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF AERONAUTICS POLICY MEMORANDUM

The following IDOT-DOA Policy Memorandum are applicable to this contract and are included in this contract by reference. The latest version of these documents may be viewed and downloaded off the Division of Aeronautics internet web site at <a href="http://www.dot.state.il.us/aero/iindex.html">http://www.dot.state.il.us/aero/iindex.html</a>.

#### IDOT-DOA Policy Memorandum Numbers:

87-2	96-1
87-3	96-2
87-4	96-3
90-1	97-2
95-1	2001-1

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **INDEX TO SPECIAL PROVISIONS**

<u>ITEM</u>	<u>DESCRIPTION</u>	PAGE NO.
	GENERAL	1
DIVISION I	GENERAL PROVISIONS	2-23
20	MAINTENANCE OF TRAFFIC	2-22
150	ENGINEER'S FIELD OFFICE	23
DIVISION II	PAVING CONSTRUCTION DETAILS	24-53
151	CLEARING AND GRUBBING	24
152	EXCAVATION AND EMBANKMENT	25-31
156	EROSION CONTROL	32-34
209	CRUSHED AGGREGATE BASE COURSE	35-38
401	BITUMINOUS SURFACE COURSE	39-44
501	PORTLAND CEMENT CONCRETE PAVEMENT	45-50
605	JOINT SEALING FILLER	51
620	PAVEMENT MARKING	52-53
DIVISION IV	DRAINAGE PIPE	54-62
701	PIPE FOR STORM SEWERS AND CULVERTS	54-56
705	PIPE UNDERDRAINS, CATCH BASINS, INLETS, AND INSPECTION HOLE	S 57-58
751	MANHOLES, CATCH BASINS, INLETS, AND INSPECTION HOLES	59-61
752	CONCRETE CULVERTS, HEADWALLS, AND MISCELLANEOUS	62
	DRAINAGE STRUCTURES	
DIVISION V	TURFING	63-67
901	SEEDING	63-64
908	MULCHING	65-67
DIVISION VI	LIGHTING INSTALLATION	68-88
108	INSTALLATION OF UNDERGROUND CABLE FOR AIRPORTS	68-73
110	INSTALLATION OF AIRPORT UNDERGROUND ELECTRICAL DUCT	74-78
125	INSTALLATION OF AIRPORT LIGHTING SYSTEMS	79-88
	DETAIL DRAWINGS	89-97
	EARTH MEDIAN DITCH CHECK	89
	(IDOT 202001-01)	00.01
	TEMPORARY EROSION CONTROL SYSTEMS (IDOT 280001-04)	90-91
	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECITOR	N 92
	(IDOT 542306-02)	
	MANHOLE TYPE A, 1-8M (6') DIAMETER (IDOT 602406-03)	93-94
	TRAFFIC CONTROL DEVICES	95-97
	(IDOT 701901-01)	75 71
APPENDIX	AC 150/5370-4, PROTECTION OF EXISTING CABLES,	98
	CONTROLS, NAVAIDS, AND WEATHER BUREAU FACILITIES	

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **GENERAL**

The following Section III Special Provisions supplement the "Standard Specifications for Construction of Airports", adopted January 1985 by IDOT-DOA, the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2007 by IDOT, the "Supplemental Specifications and Recurring Special Provisions", adopted July 1, 2004, the "Interim Revisions to the Supplemental Specifications and Recurring Special Provisions", adopted May 11, 2007 by IDOT-DOA, and IDOT-DOA's Policy Memorandum Numbers 87-2, 87-3, 87-4, 90-1, 95-1, 96-1, 96-2, 96-3, 97-3, and 2001-1, all of which shall govern the construction of Illinois Project No. MLI-3854, A.I.P. Project No. 3-17-0068-XX. In case of conflict with any part or parts of said specifications, the said Section III Special Provisions shall take precedence and shall govern.

#### **DESCRIPTION OF WORK:**

The proposed improvement at the Quad City International Airport in Moline, Illinois shall include, but not be limited to, the following major work items:

- 1. Construction of earth embankments for the installation of base rock and pavements.
- 2. Construction of proposed drainage system.
- 3. Pavement milling and pavement removal as required to relocate taxiways and install proposed materials.
- 4. Installation of proposed pavements on top of proposed crushed aggregate base course material along the proposed alignments.
- 5. Installation of the proposed payement underdrains, edge lights, and guidance signs.
- 6. Relocate and/or adjust the existing utilities (edge lights, manholes, guidance signs, etc.) as required.
- 7. Final shoulder grading, turfing, and erosion control as required.
- 8. Traffic maintenance for the duration of the project.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **DIVISION I - GENERAL PROVISIONS**

#### 20-02 ALTERATION OF WORK AND QUANTITIES

ADD the following paragraphs to this Section:

The MAA reserves and shall have the right to delete all or part of the AR620510/AS620510 Pavement Marking, AR156540 Riprap, and/or AR908520 Excelsior Blanket pay items and/or contract quantities from the contract work. The Contractor shall not be entitled to any extra compensation, beyond the contract unit prices, due to change in contract quantities. The Contractor agrees to accept payment for the remaining work based upon the original contract unit rate prices without negotiating new contract unit rate prices if only partial quantities are completed.

#### 20-05 MAINTENANCE OF TRAFFIC

ADD the following paragraphs to this Section:

- 20-05.1.1 This item shall include all work necessary to control and maintain aircraft, vehicle, equipment, and personnel traffic on the airfield during the duration of this project. The Contractor shall operate his construction activities in a manner that complies with the requirements of FAA Advisory Circular No. 150/5370-2, "Operational Safety On Airport During Construction," latest edition at the time of bidding; and Subsection 20-05 and Subsection 50-09 of the Standard Specifications for Construction of Airports.
- 20-05.1.2 It is the desire of the owner to complete this project in a timely and safe manner with the least possible disruption to airport operations. The following construction limitations, as well as the safety plan included in the Construction Plans, shall be followed to achieve the above goals:

## STAGE 1 AREA, TAXIWAY P STATION 625+00 TO STATION 630+50 AND RELOCATED TAXIWAY E / D STATION 854+05 TO STATION 860+00:

1. During Stage 1, all airfield pavements shall be open to aircraft traffic, unless authorized otherwise by the Metropolitan Airport Authority (MAA). The Contractor shall not enter the runway / taxiway safety areas or the Runway 9-27 ILS critical areas unless authorized otherwise by the MAA.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A OU008

- 2. Contractor shall enter and exit the airfield at the existing locked security gate located north of the intersection of 47th Street and 73rd Avenue (just north of the airfield industrial park). While on the airfield, the contractor shall stay on the existing service road (between the construction entrance gate and the job site) or within the limits of construction as shown on the safety plan. The Contractor shall include costs in his bid to repair any damage done to this service road during the construction of this project.
- 3. The Contractor shall install the Stage 1 barricades and lath lines prior to the commencement of any work. The barricades shall be removed and reinstalled by the Contractor as required by the MAA and/or the Resident Engineer.
- 4. The Contractor shall not stockpile materials above the FAA Part 77 Civil Airport Imaginary Surface for Runway 9-27. The elevation of this surface shall be determined by the Resident Engineer. This includes the proposed soil waste material.
- 5. For hauling operations between the north borrow area and the Stage 1 area, see the temporary haul route "A" construction limitations and conditions in the following paragraphs.

#### STAGE 2, TAXIWAY D STATION 860+00 TO STATION 864+50:

- 1. During Stage 2, Taxiway D is closed between Runway 5-23 and Taxiway E. All other airfield pavements shall be open to aircraft traffic unless authorized otherwise by the MAA. The Contractor shall not enter the runway/taxiway safety areas, Taxiway OFA (which is located left 93' to right 93' of the taxiway centerline) or the Runway 9-27 ILS critical areas unless authorized otherwise by the MAA.
- 2. Contractor shall enter and exit the airfield at the existing locked security gate located north of the intersection of 47th Street and 73rd Avenue (just north of the airfield industrial park). While on the airfield, the contractor shall stay on the existing service road (between the construction entrance gate and the job site) or within the limits of construction as shown on the safety plan. The Contractor shall include costs in his bid to repair any damage done to this service road during the construction of this project.
- 3. The Contractor shall install the Stage 2 barricades and lath lines prior to the commencement of any work. The barricades shall be removed and reinstalled by the Contractor as required by the MAA and/or the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

- 4. The Contractor shall not stockpile materials above the FAA Part 77 Civil Airport Imaginary Surface for Runway 9-27. The elevation of this surface shall be determined by the Resident Engineer. This includes the proposed soil waste material.
- 5. For hauling operations between the north borrow area and the Stage 2 area, see the temporary haul route "A" construction limitations and conditions in the following paragraphs.

## STAGE 3 AREA, TAXIWAY E, STATION 851+50 TO STATION 854+05:

## A. <u>RUNWAY</u> 9-27 <u>SAFETY AREA CONDITIONS AND</u> LIMITATIONS:

- 1. The Contractor shall breakdown the proposed work within the Runway 9-27 safety area into units that can be accomplished in individual one day work periods. Each work period shall include time to regrade, clean-up, inspect, and re-open the safety area for aircraft operations. Based up
- 2. on weather conditions and operational needs, the MAA will select the one day work periods to close Runway 9-27. Due to weather considerations, the Contractor will receive no more than a one day notice of each individual work period.
- 3. Work in the Runway 9-27 safety area <u>shall not occur</u> when Runway 13-31 is not available for aircraft operations. Runway 13-31 <u>shall be open</u> to aircraft traffic when Runway 9-27 is closed.
- 3. The Contractor shall install the Stage 3 barricades and lath lines prior to the commencement of any work. The barricades shall be removed and reinstalled by the Contractor as required by the MAA and/or the Resident Engineer.
- 4. Contractor shall use the same construction entrance for Stage 3 that he utilized during Stage 1.
- 5. Runway 9-27 and Runway 13-31 shall remain open as much as possible during the construction of this project and aircraft traffic shall have priority over construction at all times. The Contractor's employees, equipment, and materials shall not enter or be left in the safety or critical areas, unless permission to do so has been granted to the Contractor by the MAA and contact has been made with the FAA Control Tower. When a runway is closed by the MAA, the

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

Contractor may proceed with his work which requires manpower, equipment, and materials in the safety and/or critical areas. The MAA reserves and shall have the right to stop work and reopen a Runway at any time during the project as required by wind conditions, weather conditions, or aircraft operations which requires the use of a runway. The Contractor shall remove all employees, equipment and materials, including stockpiles from the safety and critical areas and regrade the safety and critical areas within one hour of notification by the Resident Engineer.

- 6. Construction employees, equipment, and materials shall not be allowed in the Runway 9-27 safety area when weather conditions require the use of instrument flight rules on Runway 9-27 (approximately 11% of the time based upon historical data). This rule shall also apply to Runway 13-31 if needed for aircraft operations.
- 7. During the airfield operation hours, Runway 13-31 and Runway 9-27 shall not be closed to aircraft traffic at the same time. During the airfield operation hours, construction operations shall not occur in the Runway 9-27 safety area and the Runway 13-31 safety area simultaneously. During the airfield operation hours, the contractor shall schedule his construction activities so that only one of these runways is closed at any given time.
- 8. The Contractor shall schedule his construction activities so that the following conditions exist at the end of all work periods in the runway safety area, taxiway safety area, and Runway 9 ILS glide slope critical area.
  - A. No exposed faces in excess of one and one-half (1-1/2) inches in height will be permitted in the safety / critical areas, either longitudinal or transverse to the edge of runway.
  - B. All excavations, trenches, and removal areas have been backfilled.
  - C. All shoulder areas have been backfilled and smoothly graded.
  - D. No mounds of dirt or irregularities greater than 3" shall exist in the safety / critical areas.
  - E. Haul roads have been re-graded to a level condition.

- F. All items have been removed from the safety / critical areas.
- G. All active airfield pavements and the runway have been broom clean.

#### B. RUNWAY 9-27 SAFETY AREA CONSTRUCTION OPERATIONS:

- 1. The Contractor shall split the proposed construction operations in the Stage 3 Runway 9-27 safety area into segments of work that can be completed in non-consecutive one day work periods (maximum of two (2) each one day periods).
- 2. One day work period activities sequence:
  - A. MAA selects day for one day Runway 9-27 closure. Runway 9-27 closed to aircraft by the MAA.
  - B. Contractor to install closed runway markers on Runway 9-27.
  - C. Complete Stage 3 Runway 9-27 safety area work (removal, rock installation, paving, grading, lighting, seeding, etc.) that can be accomplished in the time frame allowed subject to the above conditions and limitations.
  - D. Clean up work area and move all equipment out of safety / critical areas. All construction debris shall be totally removed from the safety / critical areas.
  - E. The Contractor's superintendent, Resident Engineer, and MAA/FAA representatives shall inspect the safety / critical areas to ensure the runway can be opened.
  - F. Remove the closed runway markings from Runway 9-27.
  - G. MAA opens Runway 9-27 to aircraft traffic.
- 3. Repeat cycle outlined in item 2 above until all Stage 3 Runway 9-27 safety area construction activities are complete.
- 4. Contractor shall open Taxiway E (new and old sections between Runway 9-27 and Taxiway L) prior to starting stage 4.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## STAGE 4 AREA, TAXIWAY P, STATION 630+50 TO STATION 646+00 (INCLUDING RUNWAY 5-23):

## A. <u>RUNWAY 9-27 SAFETY AREA CONDITIONS AND LIMITATIONS:</u>

- 1. The Contractor shall breakdown the proposed work within the Runway 9-27 safety area into units that can be accomplished in individual one day work periods. Each work period shall include time to regrade, clean-up, inspect, and re-open the safety area for aircraft operations. Based upon weather conditions and operational needs, the MAA will select the one day work periods to close Runway 9-27. Due to weather considerations, the Contractor will receive no more than a one day notice of each individual work period.
- 2. Work in the Runway 9-27 safety area <u>shall not occur</u> when Runway 13-31 is not available for aircraft operations. Runway 13-31 <u>shall be open</u> to aircraft traffic when Runway 9-27 is closed.
- 3. The Contractor shall install the Stage 4 barricades and lath lines prior to the commencement of any work. The barricades shall be removed and reinstalled by the Contractor as required by the MAA and/or the Resident Engineer.
- 4. Contractor shall use the same construction entrance for Stage 4 that he utilized during Stage 1.
- 5. Runway 9-27 and Runway 13-31 shall remain open as much as possible during the construction of this project and aircraft traffic shall have priority over construction at all times. The Contractor's employees, equipment, and materials shall not enter or be left in the safety or critical areas, unless permission to do so has been granted to the Contractor by the MAA and contact has been made with the FAA Control Tower. When a runway is closed by the MAA, the Contractor may proceed with his work which requires manpower, equipment, and materials in the safety and/or critical areas. The MAA reserves and shall have the right to stop work and reopen a Runway at any time during the project as required by wind conditions, weather conditions, or aircraft operations which requires the use of a runway. The Contractor shall remove all employees, equipment and materials, including stockpiles from the safety and critical areas and regrade the safety and critical areas within one hour of notification by the Resident Engineer.

- 6. The Contractor shall supply a traffic control guard and tractor brush at the location where the haul route intersects Taxiway D / E during Stage 4 hauling operations. All construction traffic shall stop at the intersection and yield to all airfield traffic at all times.
- 7. Construction employees, equipment, and materials shall not be allowed in the Runway 9-27 safety area when weather conditions require the use of instrument flight rules on Runway 9-27 (approximately 11% of the time based upon historical data). This rule shall also apply to Runway 13-31 if needed for aircraft operations.
- 8. During the airfield operation hours, Runway 13-31 and Runway 9-27 shall not be closed to aircraft traffic at the same time. During the airfield operation hours, construction operations shall not occur in the Runway 9-27 safety area and the Runway 13-31 safety area simultaneously. During the airfield operation hours, the contractor shall schedule his construction activities so that only one of these runways is closed at any given time.
- 9. The Contractor shall schedule his construction activities so that the following conditions exist at the end of all work periods in the runway safety area, taxiway safety area, and Runway 9 ILS glide slope critical area.
  - A. No exposed faces in excess of one and one-half (1-1/2) inches in height will be permitted in the safety / critical areas, either longitudinal or transverse to the edge of runway.
  - B. All excavations, trenches, and removal areas have been backfilled.
  - C. All shoulder areas have been backfilled and smoothly graded.
  - D. No mounds of dirt or irregularities greater than 3" shall exist in the safety / critical areas.
  - E. Haul roads have been re-graded to a level condition.
  - F. All items have been removed from the safety / critical areas.
  - G. All active airfield pavements and the runway have been broom clean.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### B. RUNWAY 9-27 SAFETY AREA CONSTRUCTION OPERATIONS:

- 1. The Contractor shall split the proposed construction operations in the Stage 4 Runway 9-27 safety area into segments of work that can be completed in non-consecutive one day work periods (maximum of two (2) each one day periods).
- 2. One day work period activities sequence:
  - A. MAA selects day for one day Runway 9-27 closure. Runway 9-27 closed to aircraft by the MAA.
  - B. Contractor to install closed runway markers on Runway 9-27.
  - C. Complete Stage 4 Runway 9-27 safety area work (removal, earthwork, grading, lighting, seeding, etc.) that can be accomplished in the time frame allowed subject to the above conditions and limitations.
  - D. Clean up work area and move all equipment out of safety / critical areas. All construction debris shall be totally removed from the safety / critical areas.
  - E. The Contractor's superintendent, Resident Engineer, and MAA/FAA representatives shall inspect the safety / critical areas to ensure the runway can be opened.
  - F. Remove the closed runway markings from Runway 9-27.
  - G. MAA opens Runway 9-27 to aircraft traffic.
- 5. Repeat cycle outlined in item 2 above until all Stage 4 Runway 9-27 safety area construction activities are complete.

#### **TEMPORARY HAUL ROUTE "A":**

#### A. CONDITIONS AND LIMITATIONS:

1. During hauling operations along Temporary Haul Route "A", Runway 9-27 is closed. Taxiway H shall be closed between Runway 9-27 and Taxiway E. All other airfield pavements shall be open to aircraft traffic unless authorized otherwise by the MAA.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

- 2. The Contractor shall breakdown the proposed hauling operations out of the north borrow area into units that can be accomplished in individual two day work periods. Each work period shall include time to regrade, clean-up, inspect, and re-open the ILS glide slope critical and safety areas for aircraft operations. Based upon weather and operational needs, the MAA will select the two day work periods to close Runway 9-27 and Taxiway H (west of Taxiway E). Due to weather considerations, the Contractor will receive no more than a one day notice of each individual work period.
- 3. Hauling operations out of the north borrow area <u>shall not occur</u> when Runway 13-31 is not available for aircraft operations. Runway 13-31 <u>shall be open</u> to aircraft traffic when Runway 9-27 is closed.
- 4. The Contractor shall install the north borrow area barricades and lath lines prior to the commencement of any work. The barricades shall be removed and reinstalled by the Contractor as required by the MAA and/or the Resident Engineer.
- 5. Runway 9-27 and Runway 13-31 shall remain open as much as possible during the construction of this project and aircraft traffic shall have priority over construction at all times. The Contractor's employees, equipment, and materials shall not enter or be left in the safety or critical areas, unless permission to do so has been granted to the Contractor by the MAA and contact has been made with the FAA Control Tower. When a runway is closed by the MAA, the Contractor may proceed with his work which requires manpower, equipment, and materials in the safety and/or critical areas. The MAA reserves and shall have the right to stop work and reopen a Runway at any time during the project as required by wind conditions, weather conditions, or aircraft operations which requires the use of a runway. The Contractor shall remove all employees, equipment and materials, including stockpiles from the safety and critical areas and regrade the safety and critical areas within one hour of notification by the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

- 6. Construction employees, equipment, and materials shall not be allowed in the Runway 9-27 safety area when weather conditions require the use of instrument flight rules on Runway 9-27 (approximately 11% of the time based upon historical data). This rule shall also apply to Runway 13-31 if needed for aircraft operations.
- 7. During the airfield operation hours, Runway 13-31 and Runway 9-27 shall not be closed to aircraft traffic at the same time. During the airfield operation hours, construction operations shall not occur in the Runway 9-27 safety area and the Runway 13-31 safety area simultaneously. During the airfield operation hours, the contractor shall schedule his construction activities so that only one of these runways is closed at any given time.
- 8. The Contractor shall schedule his construction activities so that the following conditions exist at the end of all work periods in the runway safety area, taxiway safety area, and Runway 9 ILS glide slope critical area.
  - A. No exposed faces in excess of one and one-half (1-1/2) inches in height will be permitted in the safety / critical areas, either longitudinal or transverse to the edge of runway.
  - B. All excavations and removal areas have been backfilled.
  - C. All shoulder areas have been backfilled and smoothly graded.
  - D. No mounds of dirt or irregularities greater than 3" shall exist in the safety / critical areas.
  - E. Haul roads have been re-graded to a level condition.
  - F. All items have been removed from the safety / critical areas and taxiway Object Free Areas (limits of the OFA to be determined by the Resident Engineer).
  - G. All active airfield pavements and the runway have been broom clean.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **B. CONSTRUCTION OPERATIONS:**

- 1. The Contractor shall split the proposed hauling operations out of the north borrow area into segments of work that can be completed in non-consecutive two day work periods (maximum of six (6) each two day periods).
- 2. Two day work period activities sequence:
  - A. MAA selects days for two day Runway 9-27 closure. Runway 9-27 and Taxiway H closed to aircraft by the MAA.
  - B. Contractor to install closed runway markers on Runway 9-27. Contractor to install Taxiway H barricades.
  - C. Complete hauling operations out of the north borrow area that can be accomplished in the time frame allowed subject to the above conditions and limitations.
  - D. Clean up work area and move all equipment out of safety / critical areas. All construction debris shall be totally removed from the safety / critical areas and the taxiway object free areas (limits of the OFA to be determined by the Resident Engineer).
  - E. The Contractor's superintendent, Resident Engineer, and MAA/FAA representatives shall inspect the safety / critical areas and the taxiway object free areas (limits of the OFA to be determined by the Resident Engineer) to ensure the runway can be opened.
  - F. Remove the closed runway markings from Runway 9-27.
  - G. MAA opens Runway 9-27 to aircraft traffic.
- 3. Repeat cycle outlined in item 2 above until all hauling operations out of the north borrow area are complete.
- 20-05.1.3 The Contractor shall not be entitled to any extra compensation due to delays or inconveniences caused by above said necessary methods, procedures and measures required to protect air traffic.
- 20-05.1.4 This item shall also include the furnishing, installing, moving, maintaining and removal of all equipment, material, miscellaneous items, and incidentals necessary to control traffic to the satisfaction of the Metropolitan Airport Authority and the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **EQUIPMENT AND MATERIALS**

- 20-05.2.1 This item shall include, but not be limited to, the following work and supplies:
  - (a) Barricades, cones, warning signs, and hazard markings: Provide, placement and maintenance.
  - (b) Material for providing temporary runway closure markings.
  - (c) Traffic control devices for construction and airport vehicular traffic.
  - (d) Temporary traffic connections necessary for ingress to and egress from the airfield.
  - (e) Temporary security measures at the point(s) of ingress/egress to the airfield (guard, fencing, gates, chain, locks, etc.)
  - (f) Cleaning and maintaining airfield pavements used during construction.
  - (g) Constructing, cleaning and maintaining haul roads and/or service roads
  - (h) Radio equipment for communication with the FAA control tower.
  - (i) Identification and marking devices for construction personnel and equipment.
  - (j) All measures necessary to comply with the safety plan included in the Construction Plans.
  - (k) All measures necessary to comply with the special provisions to Section 20-05 "Maintenance of Traffic" included in this Special Provision.
  - (l) Restoration of staging areas, storage areas, haul roads, construction access roads, service drives, borrow areas, and any other areas damaged during construction.
  - (m) Demobilization and mobilization of manpower and equipment to open and/or close runways as required by the Metropolitan Airport Authority.
  - (n) Installation and removal of any temporary electrical power and/or telephone facilities required by the Contractor and/or contract during construction to the satisfaction of the MAA and Resident Engineer.
  - (o) Installation and maintenance of safety area lath lines as shown on the Safety Plan in the Construction Plans. Lath lines shall consist of 2"x2" wood posts spaced at 15' intervals and driven into the ground with rope or heavy twine tied between the posts. Six inch wide yellow plastic warning ribbon shall be wrapped around the rope or heavy twine between the posts.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

(p) All other items as necessary to maintain control of the project as outlined in the Construction Plans and specification or as directed by the Resident Engineers.

#### **CONSTRUCTION METHODS**

- 20-05.3.1 The traffic maintenance equipment and materials shall be provided, placed, and maintained during the construction as indicated in the plans or as directed by the Resident Engineer.
- 20-05.3.2 The traffic maintenance equipment and materials shall be removed, and reinstalled by the Contractor during the construction of the project as directed by the Resident Engineer and/or as dictated by the current construction activity location.
- 20-05.3.3 After the construction has been completed and accepted by the Resident Engineer the traffic maintenance equipment and materials shall be removed by the Contractor. The removal of traffic maintenance equipment and materials shall not commence until approval by the Resident Engineer has been received. The Contractor shall clean up all debris resulting from maintaining traffic.
- 20-05.3.4 Work included in this item shall conform to applicable FAA Regulations and shall be approved in advance by the Resident Engineer and the MAA.

#### METHOD OF MEASUREMENT

20-05.4.1. The quantity of traffic maintenance to be paid for under this item shall be measured per lump sum for furnishing all materials, equipment, and labor required for this construction including, but not limited to maintenance of traffic, compliance with safety plan, compliance with Section 20-05 "Maintenance of Traffic" items, restoration, and all other necessary items to complete the construction operations for this project.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **BASIS FOR PAYMENT**

20-05.5.1 Payment will be made at the contract unit price per lump sum for Traffic Maintenance. This price shall be full compensation for furnishing all materials and for all preparation, assembly, installation, removal, reinstallation as required of these materials and for all labor, equipment, tools and incidentals necessary to complete this item.

Payment will be made under:

ITEM AR150530 -- TRAFFIC MAINTENANCE -- per lump sum.

#### 20-06 REMOVAL OF EXISTING STRUCTURES

REVISE the first paragraphs to read as follows:

All existing structures encountered within the established lines, grades, grading sections, or as indicated in the Construction Plans shall be removed by the Contractor, unless such existing structures are otherwise specified to be relocated, adjusted up or down, salvaged, abandoned in place, reused in the work or to remain in place. The cost of removing and disposing of such existing structures shall not be measured or counted for separately as a contract pay item. The cost for removing and disposing of such existing structures shall be included in the contract unit prices.

## 30.06 CONSTRUCTION LAYOUT CONSTRUCTION LAYOUT STAKES

ADD: The Contractor shall furnish and place construction layout for this project. This includes construction layout stakes spaced at 25' intervals for pavement milling.

#### 30-12 LOAD RESTRICTIONS

ADD the following to this Section:

The Contractor shall coordinate construction access with the County Superintendent of Highways and/or the Township Road Commissioner. The Contractor shall be responsible for damage to any public road caused by his construction operations. The Contractor shall repair any damage caused by his construction traffic to the satisfaction of the Owner.

The Contractor shall provide and install any warning signs (trucks entering highway, etc.) as required by the County Superintendent of Highways.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following Sub-Section:

#### 30-12.1 PERMITS:

The Contractor shall procure all required permits for entering, operating, and hauling on public roadways. The Contractor shall meet all requirements of said permits.

#### 30-18 PLANS AND WORK DRAWINGS

REVISE references to "approval" in first paragraph to "review".

The following information shall be clearly marked on each shop, working, and layout drawing, catalog cut, pamphlet specifications sheet, etc. submitted.

PROJECT LOCATION: Quad City International Airport

PROJECT NUMBERS: Illinois Project MLI-3854

AIP Project 3-17-0068-XX

CONTRACT ITEM: (E.G. 751-5.20)

SUBMITTED BY: (Contractor/Subcontractor Name)

DATE: (current date)

#### 50-10 BARRICADES, WARNING SIGNS, AND HAZARD MARKINGS

ADD the following paragraphs to this Section:

It will be the responsibility of the Contractor to properly mark the closed runway; and, when the runway is reopened, to remove the marking. A detail drawing of the closed runway marking is included on the proposed safety plan. The Contractor will be responsible for placing and removing the crosses as the runway is closed and opened.

Any cost of labor and equipment which is necessary to insure safety at the airport during the duration of the project will be included in the Traffic Maintenance contract unit price. No additional reimbursement beyond the contract unit price shall occur.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### 50-12 PROTECTION AND RESTORATION OF PROPERTY

ADD the following paragraphs to this Section:

The Contractor shall take special precautions during construction so as not to damage the existing roads, parking lots, runways, aprons, taxiways, building and other existing improvements.

Any such existing improvements damaged by the Contractor during construction shall be repaired or replaced by him at his own expense.

The Contractor shall take special care when working in the vicinity of existing airport lighting systems so as not to damage them. Should the Contractor damage any of the lighting systems and/or underground cables, he shall immediately repair or replace them, and make any necessary repairs to place them in working order. The cost of equipment and making the repairs will be the responsibility of the Contractor. If during the course of construction it is necessary to interrupt any lighting circuits, temporary cables shall be installed as needed to make the circuit operational.

The proposed minimum utility protection information shown on the Construction Plans is approximate and included for informational purposes only to help educate the Contractor on the scope of the work to be included in the contract unit prices. The Contractor is responsible to determine what additional protection is required to prevent damage to the existing utilities/improvements. The Contractor shall be responsible for all repair or replacement costs for damaged utilities/improvements.

The Contractor shall maintain the premises in reasonably clean condition and shall not allow any sizable accumulation of rubbish on the premises.

He shall leave the premises in broom-clean condition upon completion of the project.

#### 50-13 RESPONSIBILITY FOR DAMAGE CLAIMS

REVISE the second line of the first paragraph to read as follows:

"...indemnify and save harmless the Division, the Owner, the Consultant Engineers, Subconsulting Engineer, and the F.A.A...."

ADD the following three paragraphs between the first and second paragraphs of this Section:

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

To the fullest extent permitted by law, CONTRACTOR shall indemnify and hold harmless the OWNER, PARTICIPATING AGENCIES (the Division and the FAA), SUBCONSULTANTS, CONSULTANT ENGINEERS, and their respective agents and employees (indemnities) from and against any and all claims, damages, losses, economic losses and expenses, including but not limited to attorney's fees, arising out of or resulting from performance of the Work (including specifically claims arising under the Illinois Structural Work Act), provided that such claim, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury or destruction of tangible property (other than the Work itself), including loss of use resulting therefrom, but only to the extent caused in whole or in part by negligent acts or omission of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, excluding any proportionate amount of any claim, damage, loss or expense which is caused by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge or reduce other rights or obligations of indemnity which would otherwise exist as to a party or person described in this Paragraph.

In claims against any person or entity indemnified under this Paragraph by an employee of the Contractor, a Subcontractor, anyone directly employed by them or anyone for whose acts they be liable, the indemnification obligation under this Paragraph shall not be limited by a limitation on the amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts.

This indemnification shall also include, but not be limited to, any penalties, fines or other actions imposed by the U. S. Department of Labor or the State of Illinois under the Occupational Safety and Health Act (O.S.H.A.) as a result of the Contractor's acts or omissions on this project.

REVISE the last paragraph of this Section to read as follows:

"The Contractor, prior to execution of the contract, shall file with the Division and the Consultant Engineer, copies of completed certificates of insurance, satisfactory to the Division and the Consultant Engineer, to afford protection against all claims for damages to public or private property, and injuries to persons, arising out of and during the progress of the work to its completion, as defined by Section 60-12. The policy of insurance shall include the Owner, the participating agencies (the Division and the FAA), Subconsultant Engineers, and Consultant Engineers, as additional insured or provide separate coverages with individual protective policies for all of the above named parties. The minimum amounts of insurance shall be as follows, except no restrictions or occurrence limits will be permitted:

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

General Public Liability Insurance: \$1,000,000/Person

\$2,000,000/Occurrence

Property Damage Insurance: \$1,000,000/Occurrence

In addition to the above policies, Contractor shall provide an "Umbrella" policy covering his entire operation in the amount of \$3,000,000.

All such insurance must include an endorsement whereby the insurer agrees to notify the Division and the Consultant Engineer at least 30 days prior to nonrenewal, reduction or cancellation. Contractor shall furnish to the Division and the Consultant Engineer a copy of the endorsement in addition to any other insurance certificate required. The Contractor shall cease operations on the project if the insurance is canceled or reduced below the required amount of coverage. All costs for insurance as specified herein will not be paid for separately, but shall be considered as incidental to the contract."

## 50-17 CONTRACTOR'S RESPONSIBILITY FOR UTILITY SERVICE AND FACILITIES OF OTHERS

ADD the following to this Section:

Utility Service or Facility	Person to Contact	Telephone <u>Number</u>
Airport Facilities	Metropolitan Airport Authority	757-1743
Airport Lighting	Metropolitan Airport Authority	757-1752
FAA Control and Communications Cable	Airways Facility Unit	799-7303
Water Mains	Metropolitan Airport Authority	764-9621
Electric Cables Mid-American Energy Company	JULIE (Joint Utility Locating Information for Excavators)	1-800-892-0123
Telephone Cables Illinois Bell	JULIE	1-800-892-0123
Telephone Company		

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

AT&T of Illinois Gas Mains

JULIE

1-800-892-0123

Mid-American Energy Company

#### 50-25 CONTRACTOR'S WARRANTY

ADD the following paragraphs to this Section:

Airport lighting equipment and materials covered by F.A.A. Specifications to be supplied to this project, shall have the prior manufacturer's approval by the F.A.A. and listed in the most current Advisory Circular for Approved Airport Lighting Equipment.

All other equipment and materials covered by other referenced specifications shall be subject to acceptance through <u>manufacturer's certification of compliance</u> with the applicable specifications.

#### 60-07 TEMPORARY SUSPENSION OF THE WORK

DELETE the first two paragraphs and INSERT the following:

The Contracting Agent (IDOT-DOA and/or the MAA) reserves the right to temporarily suspend the work wholly, or in part, for such periods as they may deem necessary, due to unsuitable weather, airport operation considerations, or other such conditions as are considered unfavorable for the prosecution of the work or for such time as is necessary due to the failure on the part of the Contractor to carry out orders given or perform any or all provisions of the contract.

All measures necessary to comply with the temporary suspension of the work, as required by the Contracting Agent (IDOT-DOA and/or the MAA), shall be included in the traffic maintenance contract unit price. The Contractor shall not be entitled to any additional compensation (beyond this pay item) due to delays or inconveniences caused by the temporary suspension of the work.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following special Sections:

#### HAUL ROUTE

The Contractor <u>will use only</u> the designated haul route as shown on Sheets 4, 5, 6 and 7 of the Construction Plans. The Contractor's men and equipment shall not traverse outside the designated work areas to other locations on the airport or off of airport property. The designated haul route will be the <u>only</u> vehicular access to the construction site.

It will be the Contractor's responsibility to procure all required permits from public agencies for entering, operating, and hauling materials on public roadways. The Contractor shall meet all requirements of said permits.

It will be the Contractor's responsibility to clear and build the haul routes and construction staging area as required to complete the contract work. The Contractor shall restore the haul routes and construction staging area upon completion of the project. All costs for clearing, maintaining, and restoring the haul routes and construction staging area shall be included in contract unit prices.

Failure to use the prescribed haul route or adhere to the safety requirements will result in the suspension of work.

#### **EQUIPMENT PARKING**

The Contractor shall park equipment in the areas designated for construction staging. This area is shown on Sheet 4 of the Construction Plans.

#### **SCHEDULING OF OPERATIONS**

The Contractor shall coordinate all work on this project with the Resident Engineer and the Metropolitan Airport Authority to insure that the construction will cause the least amount of inconvenience possible to normal airport activity.

The Contractor will be required to submit a work schedule to the State of Illinois, Division of Aeronautics, and to the Resident Engineer showing proposed sequence of work.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

In the event that other construction projects are in progress at the airport at the same time as this project, the Contractor will be required to cooperate with all other Contractors and the Metropolitan Airport Authority in the coordination of the work. The earthwork Contractor shall cooperate and coordinate his earthwork activities with the other Contractors' activities in order to provide an orderly and properly sequenced progression of construction. Any disagreement between Contractors will be settled by the Contracting Agent (IDOT-DOA). No extra compensation will be due to the earthwork Contractor for delays caused by sequencing of construction events. Cooperation and coordination shall occur between the Contractors during the construction of these projects.

The Metropolitan Airport Authority will at all times have jurisdiction over the safety of air traffic during construction. Whenever the safety of air traffic during construction is concerned, his decision as to methods, procedures, and measures used shall be final, and any and all Contractors performing work must be governed by such decisions.

The Contractor shall not be entitled to any extra compensation due to delays or inconvenience caused by said necessary methods, procedures, and measures to protect air traffic, delays caused by sequencing of construction events, and/or delays caused by coordination with others.

#### SITE INSPECTION

The Contractor shall be responsible for an on-site inspection prior to submitting a bid on this project. Upon receipt of a bid, it shall be assumed that the Contractor is fully familiar with the construction site.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO RECURRING SPECIAL PROVISION FOR ITEM AR150510 (CHECK SHEET #5)

#### **ENGINEER'S FIELD OFFICE**

EFFECTIVE: JULY 1, 2004

ADD the following Section:

#### METHOD OF MEASUREMENT

3.1 The quantity of Engineer's Field Office to be paid for under this item shall be measured per lump sum for furnishing all materials, equipment, labor, and all other necessary items required to complete this item in accordance with this special provision.

#### **BASIS OF PAYMENT**

DELETE Section 3.1 and insert the following:

4.1 This item will be paid for at the contract price per lump sum for a field office, which price shall include all utility costs (including long distance telephone service for the Resident Engineer and his representatives) and shall reflect the salvage value of the building or mobile unit, equipment, and furniture which becomes the property of the Contractor after release by the Resident Engineer.

Payment will be made under:

ITEM AR150510 -- ENGINEER'S FIELD OFFICE -- per lump sum.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### <u>DIVISION II – PAVING CONSTRUCTION DETAILS</u>

#### **EARTHWORK**

## MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM AR 151

#### **CLEARING AND GRUBBING**

EFFECTIVE: JULY 1, 2004

#### DESCRIPTION

#### 151-1.1 DELETE the second paragraph and ADD the following:

The clearing and grubbing for this project shall occur in the areas designated on the Construction Plans. The cost of disposal of all spoil materials shall be included in the contract unit price. It shall be the Contractor's responsibility to comply with all local ordinances.

#### **CONSTRUCTION METHODS**

#### 151-2.1 GENERAL:

ADD the following:

The approximate areas and estimated quantities for clearing and grubbing shown on the plans have been determined by aerial mapping and are subject to change at the time of construction. The actual area of clearing and grubbing will be marked for removal by the Resident Engineer at the time of construction.

Prior to the start of construction, the MAA will drop the larger trees in the clearing and grubbing area as shown on the Construction Plans. The Contractor will be responsible to remove and dispose of the downed timber, stumps, logs, brush, undergrowth, and all other natural obstructions remaining in the area.

#### **BASIS OF PAYMENT**

#### 151-4.1 DELETE the first paragraph and insert the following:

Payment shall be made at the contract unit price per acre for CLEARING AND GRUBBING. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, permits, and incidentals (including disposal of all spoil materials) necessary to complete the item.

Payment will be made under:

ITEM AR151450 -- CLEARING AND GRUBBING -- per acre.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# DIVISION II – PAVING CONSTRUCTION DETAILS EARTHWORK MODIFICATIONS TO SUPPLEMENTAL SPECIFICATION FOR ITEM 152-EXCAVATION AND EMBANKMENT

EFFECTIVE: JULY 1, 2004

#### **DESCRIPTION**

#### 152.1.1 ADD the following to this Section:

This item shall include, but not be limited to, all work necessary to remove existing soils from the proposed cut areas, stockpile soils as required, haul soils from the proposed cut areas or stockpile areas to the proposed embankment areas, installation of soils/topsoils, and backfill, compaction of soils where required, final grading, disposal of waste soils and other miscellaneous grading and backfilling as shown on the Construction Plans or as required by the Resident Engineer.

The Contractor shall remove existing topsoil materials, complete earthwork and then reinstall topsoil materials as required to guarantee the final 4" of soil materials will support vegetation growth. If Contractor installs soil that will not support vegetation growth, the Contractor shall remove the top 4" of the soil materials and haul in topsoil materials at his own expense without additional compensation beyond the contract unit prices.

The Contractor will be paid for hauling the soil materials one time only. The cost of moving, stockpiling, removing, reinstalling, etc. of the soil materials as required to complete the contract work shall be included in the 152 Earthwork cubic yard prices as defined in this Special Provision.

#### 152-1.2 CLASSIFICATION

ADD the following to this Section:

All materials excavated, regardless of the source and type, including vegetation strippings, concrete materials and solid rock materials shall be defined as "UNCLASSIFIED EXCAVATION", "ON-SITE BORROW, and/or "OFFSITE BORROW EXCAVATION". These contract items shall include the removal and off site disposal of existing concrete slabs, broken concrete, concrete footings, concrete drainage structures, seal coat/gravel service roads, and solid rock materials from the proposed excavation areas.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A OU008

152410-UNCLASSIFIED EXCAVATION shall include all materials which are moved with the local areas. The three local areas are the Taxiway P construction site area, north on-site borrow area, and south offsite borrow excavation area. The Taxiway P construction site area includes the Taxiway D, Taxiway E, Taxiway P, and Runway 5-23 areas. 152410-UNCLASSIFIED EXCAVATION shall include all other materials that are not contained in the below pay items (152441, and 152442).

152441-ON-SITE BORROW shall include all materials which are moved between the proposed north on-site borrow area and the Taxiway P construction site area.

152442-OFFSITE BORROW EXCAVATION shall include all materials which are moved between the proposed south offsite borrow excavation area and the Taxiway P construction site area.

#### **CONSTRUCTION METHODS**

#### 152-2.1 GENERAL

ADD the following to this Section:

The payments under items 152410-UNCLASSIFIED EXCAVATION, 152441-ON-SITE BORROW, AND 152442-OFFSITE BORROW EXCAVATION shall be based upon measuring the volume of cubic feet of soils removed as shown in the Construction Plans. The following information is approximate and included for informational purposes only to help educate the Contractor on the scope of the work to be included in the contract unit prices. A twenty-five (25) percent shrinkage factor is included in the calculations for necessary compacted embankment materials. Separate measurement for payments and/or payments shall not be made for the individual functions or steps required to complete the earthwork activities. The Contractor shall include all costs in the contract items 152410-UNCLASSIFIED EXCAVATION, 152441-ON-SITE BORROW, AND 152442-OFFSITE BORROW EXCAVATION cubic yard prices. The below figures are approximate and no adjustments to the contract unit prices shall be made for minor variations.

ILL. PRJT. No. MLL-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# QCIA, TAXIWAY P, PHASE II- MIDDLE PAVING EARTHWORK SUMMARY

		REMARKS	BORROW NEEDED = 71,775 C.Y. – 11,306 C.Y. = 60,469 C.Y.	BORROW NEEDED = 5,114 C.Y 1,050 C.Y. = 4,064 C.Y.	BORROW NEEDED = 15,320 C.Y 1,153 C.Y. = 14,167 C.Y.	BORROW NEEDED = 8,020 C.Y 332 C.Y. = 7,688 C.Y.	WASTE TO AREA 1 = 2,815 C.Y 1,005 C.Y =. 1,810 C.Y.	WASTE TO AREAS 1 THROUGH 4 = 35,720 C.Y.	WASTE TO AREA 1 THROUGH 4 = 48,858 C.Y.	PROJECT SHRINKAGE PROVIDED = 25%
	ADDITIVE ALTERNATE 2	AT152442 OFFSITE BORROW							2,743	2,743
		AT152441 ON-SITE BORROW						1,200		1,200
	ADDITIV	AT152410 AT152441 UNCLASSIFIED ON-SITE EXCAVATION BORROW		1,050						1,050
3R (C.Y.)	ATE 1	AS152442 OFFSITE BORROW								0
AADE UNDI	ADDITIVE ALTERNATE	AS152441 ON-SITE BORROW								0
PAYMENT MADE UNDER (C.Y.)	ADDITIN	ASI52410 ASI52441 UNCLASSIFIED ON-SITE EXCAVATION BORROW	167							167
		AR 152442 OFFSITE BORROW							46,115	46,115
	BASE BID	AR152441 ON-SITE BORROW						34,520		34,520
	B/	AR152410 UNCLASSIFIED EXCAVATION	11,139		1,153	332	2,815			15,439
	FILL WITH	SHRINKAGE (C.Y.)	71,775	5,114	15,320	8,020	1,005	0	0	101,234
	RAW	FILL (C.Y.)	57,420	4,091	12,256	6,416	804	0	0	80,987
	RAW	CUT (C.Y.)	11,306	1,050	1,153	332	2,815	35,720	48,858	101,234
		ITEM/LOCATION	TXWY P WEST, STA. 627+15 TO STA. 641+50	TXWY P EAST, STA. 641+50 TO STA. 645+30	TXWY D/E, NORTH STA. 851+85 TO STA. 856+50	TXWY D/E, SOUTH, STA. 859+00 TO STA. 863+63	RNWY 5-23 BASE BID DRAINAGE SWALE STA. 25+89 TO STA. 31+94	NORTH ON-SITE BORROW AREA, STA. 218+00 TO STA. 226+50	SOUTH OFFSITE BORROW EXCAVATION AREA, STA. 0+00 TO STA. 6+00	TOTALS
	ITEM	NUMBER	1	2	B	4	S	9	7	

# NOTES:

- No measurements or payments shall be made for stripping, stockpiling, topsoils, and/or minor erosion control ditches. The above earthwork summary table does not include volumes or earthwork for items not measured and/or paid for.
- Item AR152441 On-site Borrow materials will be hauled from the North on-site borrow area to the Taxiway P area where it will be used as compacted sand fill. ri

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **CONSTRUCTION METHODS**

#### 152-2.2 EXCAVATION

ADD the following to this Section:

Compaction control testing shall be accomplished for aircraft weights of 60,000 pounds or more.

#### 152-2.4 DITCH EXCAVATION

ADD the following to this Section:

The Contractor shall transport materials along the haul roads only. The locations of all haul roads shall be approved by the Resident Engineer prior to beginning any work on this item. The Contractor shall also be responsible for placing, maintaining, and removing any necessary drainage structures to allow crossing the various drainage ditches located on airport property. The Contractor shall take special precautions when hauling excavated materials so as not to create deep ruts. All existing graded, turfed, sodded and/or formed areas which are disturbed or rutted by the Contractor, during his hauling operations, shall be regraded, returfed and refinished at his own expense and to the satisfaction of the Resident Engineer. No additional payment for haul will be allowed the Contractor.

#### 152-2.6 STRIPPING

DELETE this Section and Insert the following:

All vegetation such as brush, heavy sods, heavy growth of grass, decayed vegetable matter, rubbish, and any other unsuitable material within 10' of the future paved areas shall be stripped or otherwise removed before embankment operations are started. Strippings from under the future paved areas may be stockpiled and used for topsoil and/or may be placed in the shoulder embankment area outside the limits of future pavement (as directed by the Resident Engineer), scarified, and broken by means of a disc harrow, plow or other approved equipment to the satisfaction of the Resident Engineer.

All vegetation such a brush, heavy sods, heavy growth of grass, decayed vegetable matter, rubbish, and any other unsuitable material 10' or more outside the future paved areas shall be stripped or otherwise removed before earthwork operations are started. Strippings from outside the future paved areas shall be stockpiled and used for topsoil upon the completion of the earthwork activities. These materials shall be scarified, and broken by means of a disc harrow, plow or other approved equipment to the satisfaction of the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

No direct payment and/or measurements shall be made for the work performed under this section. The costs for all strippings, stockpiling, topsoil placement, and minor erosion control measures shall be included in the 152 Earthwork contract unit prices.

#### 152-2.9 PREPARATION AND PROTECTION OF THE TOP OF THE SUBGRADE

#### ADD the following to this Section:

At all times during construction, the ground surface shall be properly graded to promote rapid clearing of rainwater. The Contractor shall install temporary drainage ditches as requested by the Resident Engineer. Any water that accumulates on the ground surface shall be immediately removed by the Contractor. Excessively wet or disturbed soils at the base of any excavation or fill areas shall be removed prior to the placement of any additional fill. Any ground surface which will be exposed to weather and not immediately worked shall be bladed off with a motor grader and compacted with a smooth roller to seal the ground surface and prevent infiltration of moisture as approved by the Resident Engineer. When requested by the Resident Engineer and/or when it is predicted that inclement weather may develop, the Contractor shall cease embankment construction and seal the embankment ground surface.

#### 152-2.12 TOPSOIL

#### ADD the following to this Section:

Topsoil shall be salvaged from strippings or other grading operations. Strippings shall be stockpiled during excavation operations so that soils can be removed. The strippings shall be reinstalled after excavation operations are complete. Grade stakes for topsoil placement shall not be set. No direct payment or measurements will be made for topsoil.

No direct payment or measurements shall be made for the work performed under this section. The costs for all stripping, stockpiling, topsoil placement, and minor erosion control ditches shall be included in the 152 Earthwork contract unit prices.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **METHOD OF MEASUREMENT**

#### 152-3.1 DELETE:

The phrase "and stripped" from the last sentence of the first paragraph.

Add to this Section:

Excavation or handling of soils shall be paid for only once. Stockpiling of soils for later reuse and redistribution shall be done at the Contractor's expense. Redistribution or spreading of stockpiled soils shall be done at the Contractor's expense.

No direct measurements shall be made for stripping, stockpiling, topsoil placement, minor fill-in of abandoned structures and ditches, minor erosion control ditches, and the removal and disposal of existing concrete slabs, footings, drainage structures, and storm sewers. These items shall be considered incidental to the 152 Earthwork contract unit prices.

- 152-3.2 DELETE the entire Article.
- 152-3.3 DELETE the entire Article and insert the following:

Borrow material paid for shall be the number of cubic yards measured in its original position in excavation, and pay quantities shall be computed by the method of average end areas.

ADD the following to this Section:

- 152-3.4 Only materials excavated and hauled away from the north on-site borrow area shall be measured under items AR152441 and AT152441 ON-SITE BORROW.
- 152-3.5 Only materials excavated and hauled away from the south offsite borrow excavation area shall be measured under items AR152442 and AT152442 OFFSITE BORROW EXCAVATION.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **BASIS OF PAYMENT**

152-4.3 DELETE the entire article.

ADD the following to this Section:

- 152-4.5 Payment shall be made at the contract unit price per cubic yard for "ON-SITE BORROW". This price shall be the full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.
- 152-4.6 Payment shall be made at the contract unit price per cubic yard for "OFFSITE BORROW EXCAVATION". This price shall be the full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

ITEM AR152410 -- UNCLASSIFIED EXCAVATION -- per cubic yard.

ITEM AR152441 -- ON-SITE BORROW -- per cubic yard.

ITEM AR152442 -- OFFISTE BORROW EXCAVATION -- per cubic yard.

ITEM AS152410 -- UNCLASSIFIED EXCAVATION -- per cubic yard.

ITEM AT152410 -- UNCLASSIFIED EXCAVATION -- per cubic yard.

ITEM AT152441 -- ON-SITE BORROW -- per cubic yard.

ITEM AT152442 -- OFFISTE BORROW EXCAVATION -- per cubic yard.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## MODIFICATIONS TO RECURRING SPECIAL PROVISION FOR ITEM AR156000 (CHECK SHEET #8)

#### **EROSION CONTROL**

EFFECTIVE: JULY 1, 2004

#### METHOD OF MEASUREMENT

DELETE Sections 4.1 and 4.2 and INSERT the following:

4.1 The quantity of Temporary Erosion Control to be paid for under this item shall be measured per lump sum for furnishing all materials, equipment, overhead, and labor required for the construction and administration of this project including, but not limited to, compliance with the storm water pollution prevention plan, IEPA construction site activities NPDES Permit No. ILR100000, IEPA regulations, and all other necessary items to complete this item. The contractor shall comply with the applicable provisions of the Illinois Environmental Protection Agency's "Standards and Specifications for Soil Erosion and Sediment Control" and the FAA's Advisory Circular 150/5370-10A "Standards For Specifying Construction of Airports".

#### **BASIS OF PAYMENT**

DELETE Section 5.1 and INSERT the following:

Payment will be made at the contract unit price per lump sum for Temporary Erosion Control. This price shall be full compensation for furnishing all materials and for all preparation, assembly, installation, removal, reinstallation as required of these materials and for all labor, equipment, tools and incidentals necessary to complete this item.

Payment will be made under:

ITEM AR156500 -- TEMPORARY EROSION CONTROL -- per lump sum.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM AR156540 (CHECK SHEET #10)

#### **RIPRAP**

EFFECTIVE: JULY 1, 2004

#### **DESCRIPTION**

#### 1.1 ADD:

Item AR156540- RIPRAP materials will be used in locations where the existing ground is too soft to support construction operations as determined by the Resident Engineer. The minimum thickness of the riprap stone shall be 12 inches. The MAA reserves and shall have the right to delete part or all of the AR156540 pay item from the proposed contract work. The Contractor shall not be entitled to any extra compensation for the deletion of this pay item or quantities.

#### **MATERIALS**

#### 2.1 ADD:

IDOT Coarse Aggregate Gradation Number RR-1, RR-2, CA-3, and/or a similar graded material, as approved by the Resident Engineer, shall be used in the locations (as determined by the Resident Engineer) for the AR156540 Riprap materials.

#### **CONSTRUCTION METHODS**

#### 3.1 DELETE the first paragraph and insert the following:

Prior to placement of the riprap material, the Contractor shall undercut the designated area to a depth that is determined by the Resident Engineer. The Contractor shall dispose of the undercut material removed at a suitable location off of airport property. The Contractor is responsible for finding a suitable disposal area. The Contractor shall include the costs for removing and disposing of the undercut materials in the AR156540-Riprap contract unit rate. The undercut materials shall not be measured for payment.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### METHOD OF MEASUREMENT

4.1 ADD the following to this Section:

Riprap used for aggregate pipe bedding shall not be measured for payment under this item.

The minimum thickness of the riprap stone shall be 12 inches.

#### **BASIS OF PAYMENT**

5.1 ADD the following to this Section:

Riprap used for aggregate pipe bedding shall not be paid for under this item.

Payment will be made under:

ITEM AR156540 -- RIPRAP -- per square yard.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### MODIFICATIONS TO SUPPLEMENTAL SPECIFICATION FOR ITEM 209 – CRUSHED AGGREGATE BASE COURSE

#### **DESCRIPTION**

#### 209-1.1 ADD:

The item 209511 Crushed Aggregate Base Course material will be used to construct a 10" base for the proposed Taxiway P pavement, a 8" base for the proposed Taxiway D / E pavement and a variable depth base for the proposed Runway 5-23 pavement. Maximum pay width for the base material shall be 12 inches beyond the edge of the proposed pavement. If the Contractor requires additional width for pavement installation, the additional materials shall meet the same specifications, but will be considered incidental.

This item shall also include furnishing and installing geotextile fabric on Taxiway P, Taxiway D, and Taxiway E proposed aggregate base course areas as indicated on the Construction Plans or as otherwise required by the Resident Engineer. Geotextile fabric used for pipe installation shall not be included for payment in this item.

#### **MATERIALS**

#### 209-2.3 ADD:

Sieve designation B, 1 1/2 inch maximum, TABLE 1, shall be used in the locations as indicated on the Construction Plans for the 209510 Crushed Aggregate Base Course.

ADD the following Section:

#### 209-2.4 GEOTEXTILE FABRIC

The geotextile fabric shall consist of woven or nonwoven filaments of polypropylene, polyester, nylon or polyethylene. Nonwoven fabric may be needle punched, heat-bonded, resin-bonded or combinations thereof. The fabric shall be inert to commonly encountered chemicals, rot proof, dimensionally stable (i.e. fibers must maintain their relative position with respect to each other), resistant to delamination, and conform to the following physical properties.

Weight (oz./sq. yd.)	6.0	- ASTM D1910
Grab tensile strength (lbs.)	300 min.*	- ASTM D1682
Grab Elongation at break (%)	15 min.*	- ASTM D1682
Burst strength (psi)	250 min.*	- ASTM D751
Trapezoidal tear strength (lbs.)	75 min.**	- ASTM D2263
Equivalent opening size (EOS)		

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A OU008

Sieve No.

50 min.\*\* - CW 02215-77

- \* For woven fabric, test results shall be referenced to orientation with warp or fill, whichever case may be. Both woven and nonwoven fabrics shall be tested wet.
- \*\* Manufacturer's certification of fabric to meet requirement.

<u>Handling and Storage:</u> Fabric shall be delivered to the job site in such a manner as to facilitate handling and incorporation into the work without damage. In no case shall the fabric be stored or exposed to direct sunlight that might significantly diminish its strength or toughness.

#### **CONSTRUCTION METHODS**

#### 209-3.2 EQUIPMENT

ADD the following paragraphs to this Section:

Provisions shall be made by the Contractor for furnishing water at the plant <u>and</u> at the site of the work by equipment of ample capacity and of such design as to assure uniform mixing and application.

#### 209-3.6 FINISHING AND COMPACTING

DELETE the fifth sentence in the first paragraph and insert the following sentence in its place:

Rolling shall continue until the base material has been compacted to not less than <u>95%</u> density, as determined by the compaction control tests specified in Division VII.

Compaction control testing shall be accomplished for aircraft weights of 60,000 pounds or more.

ADD the following Section:

#### 209-3.11 GEOTEXTILE FABRIC

Prior to installation of the fabric, surface shall be cleared of debris, sharp objects and trees. Tree stumps shall be either removed or cut to the level of the ground surface. In the case of subgrades, all wheel tracks or ruts in excess of 2 inches in depth shall be graded smooth or otherwise filled with soil to provide a reasonably smooth surface.

Fabric sections shall be joined by overlapping the upper strip over the next lower strip, and also overlapping longitudinal edge joints by at least 2 feet. The fabric shall be held

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

firmly in place by pinning the overlapped joints with wire staples made from No. 11 gage or heavier wire, width 1 or 2 inches at the throat and 6 inches from top to bottom after bending. The staples shall be packaged in cartons.

Torn fabric shall be repaired in place by cutting and placing a piece of the same fabric over the tear. The dimensions of the patch shall be at least two (2) feet larger than the largest dimension of the tear, and it shall be pinned securely to prevent the stone from causing lap separation.

#### METHOD OF MEASUREMENT

#### 209-4.1 ADD the following to this Section:

The quantity of Crushed Aggregate Base Course to be paid for shall be the number of tons of material placed, bonded and accepted by the Resident Engineer in the completed base course. Aggregate in excess of 12" beyond the pavement edge will not be measured for payment but shall be considered incidental to this pay item.

ADD the following Sections:

209-4.2 The quantity of geotextile fabric to be paid for shall be the number of square yards as specified, in place, completed, and accepted. The overlapped areas will not be measured for payment, but shall be included in the contract unit price. Geotextile fabric used for pipe installation shall not be measured for payment under this item.

#### **BASIS OF PAYMENT**

#### 209-5.1 ADD the following to this Section:

Payment will not be made for aggregate in excess of 105 percent of the amount specified by the Resident Engineer nor for aggregate placed outside the design width.

The tonnage of each type of aggregate base measured as provided above shall be paid for at the contract unit price per ton for each type of aggregate base course, which price and payment shall constitute full compensation for removal and disposal of existing materials as required to install proposed materials, preparing subgrade; furnishing, hauling and placing the materials; for spreading, sprinkling (if required), compacting and rolling, for refilling test holes (when necessary); and for furnishing all labor, equipment, tools, water and incidentals necessary to complete the work. This item shall not include aggregate materials required for paving operations (form setting and/or slip form machinery).

ADD this Section:

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

209-5.2 The number of square yards of geotextile fabric measured as provided above shall be paid for at the contract unit price per square yard for furnishing, storing, and installing the geotextile fabric. This price shall be full compensation for all labor, materials, and equipment necessary to complete this item. Geotextile fabric used for pipe installation shall not be paid for under this item.

Payment will be made under:

ITEM AR209510 -- CRUSHED AGGREGATE BASE COURSE -- per ton.

ITEM AR209600 -- GEOTEXTILE FABRIC -- per square yard.

ITEM AS209510 -- CRUSHED AGGREGATE BASE COURSE -- per ton.

ITEM AS209600 -- GEOTEXTILE FABRIC -- per square yard.

ITEM AT209510 -- CRUSHED AGGREGATE BASE COURSE -- per ton.

ITEM AT209600 -- GEOTEXTILE FABRIC -- per square yard.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO THE INTERIM REVISIONS TO THE RECURRING SPECIAL PROVISIONS FOR ITEM AR401002 (CHECK SHEET #20)

#### BITUMINOUS SURFACE COURSE-METHOD II

EFFECTIVE: MAY 11, 2007

#### 401-1.1 ADD the following to this Section:

Item AR401610 Bituminous Surface Course shall include all work necessary to supply and install the bituminous surface course material for Taxiway D and Taxiway E.

#### 401-3.2 JOB MIX FORMULA (JMF)

ADD the following:

Marshall Design Criteria for aircraft over 60,000 pounds shall be used for this project.

Mix gradation B (3/4" maximum), TABLE 4, shall be used unless otherwise specified by the Resident Engineer.

#### 401-4.9 TRANSPORTING, SPREADING, AND FINISHING

ADD the following paragraph after the fourth paragraph:

No bituminous pavement shall be installed until the underlying surface has been cleaned, prepared, tack coated and accepted by the Resident Engineer.

Prior to the application of the tack coat materials, the pavement to be overlaid shall be cleared of all dirt, dust, and loose materials. Power brooms, sweepers and high pressure air shall be used to remove dust and debris to the satisfaction of the Resident Engineer. Placement of bituminous paving materials must be delayed until the tack coat is properly cured as determined by the Resident Engineer.

The first lane of all lifts of the bituminous surface course shall be started at the center of the pavement with a taut stringline (guide wire) set to grade at both sides of the paver. The automatic grade control system of the paver shall be used to control grade at both sides of the paver from these reference stringlines. The grade control for the adjacent lanes of pavement shall be maintained by using a matching shoe with the previous laid pavement and a stringline on the outer edge of the next lane. A stringline and matching shoe shall be used to pave all remaining lanes of all lifts of surface course. The maximum lift thickness shall be two (2) inches compacted unless otherwise authorized by the Resident Engineer.

#### 401-4.12 SHAPING EDGES

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following as the second paragraph to this Section:

All pavement edges including the pavement ends must be left in proper alignment as shown on the plans. This may be accomplished by a trimming method or, at the Contractor's option, by sawing after the paving has been completed. No additional compensation will be made if the sawing method is used.

#### **BASIS OF PAYMENT**

Payment will be made under:

ITEM AR401610 -- BITUMINOUS SURFACE COURSE -- per ton.

ITEM AR401630 -- BITUMINOU SURFACE TEST SECTION -- per each.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM AR401650 (CHECK SHEET #24)

#### **BITUMINOUS PAVEMENT MILLING**

EFFECTIVE: JULY 1, 2004

#### **DESCRIPTION**

1.1 ADD the following to this section:

This item shall consist of milling and planning materials from the existing pavement to produce a pavement surface texture consisting of a uniform pattern of discontinuous longitudinal striations interspersed on an otherwise smooth flat surface.

#### **EQUIPMENT**

ADD the following paragraphs:

2.2 The machines used for milling and planning shall be self-propelled grinding machines. The grinding machines shall be capable of accurately and automatically establishing profile grades by referencing from a taut string line or an independent grade reference control system to provide a milled surface with a tolerance of 3/16 inches in 16 feet when tested with a 16 foot straightedge. The machines shall have a positive means for controlling cross slope elevations. The machines shall have an effective means for removing excess materials from the surface and for preventing dust resulting from the operation from escaping into the air. The machines used for milling and planning the pavement shall have a twelve foot (12') wide, or equal, drum that is at least twenty-eight inches (28") in diameter and capable of removing a layer of material that is at least 1 1/2 inches in depth in a single pass. The Contractor may substitute a multiple number of smaller width machines (that will mill the total width of the proposed paving lanes in a single pass) for the above referenced 12' wide machine.

The cutting teeth used in the milling operation shall be the GTE AM 722, or an approved equivalent. When the teeth become worn so they will not produce the required surface texture, they shall be changed at the same time (as a unit). Occasionally, individual teeth may be changed if they lock up or break, but this method shall not be used to avoid changing the set of teeth as a unit.

The moldboard shall be straight, true, and free of excessive nicks or wear, and it shall be replaced as necessary to uniformly produce the required surface texture.

#### **CONSTRUCTION METHODS**

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following paragraphs:

3.2 The Contractor shall be required to make saw cuts to the depths required by the Resident Engineer where the existing pavements to be removed abuts the existing pavement to remain-in-place. The saw cut lines shall be not more than ±1" from the line marked by the Resident Engineer. All sawing shall be accomplished to provide a smooth vertical face on a straight horizontal line. After the saw cutting is complete, the pavement surface shall be milled to a depth as indicated on the Construction Plans. The milling equipment must be capable of milling the surface to the elevation and grade shown on the Cross Sections. Disposal of the milling material shall be at a location off airport property and shall be accomplished by the Contractor. Prior to the placement of the proposed pavement materials, all milled areas shall be broomed and blown clean to the satisfaction of the Resident Engineer.

It shall be the responsibility of the Contractor to determine the type and thickness of the existing pavement to be milled. No additional compensation will be allowed because of variations from the assumed thickness or from the thickness shown on the plans.

The pavement milling and pavement removal Contractor shall review the requirements of <u>Section 20-05</u>, <u>Maintenance of Traffic</u> located in <u>Division I-General Provisions</u> found in this Special Provision and the safety plan found in the Construction Plans for restrictions on pavement milling, hauling pavement millings and pavement removal on this project.

3.3 Surface Texture: Each tooth on the cutting drum shall produce a series of discontinuous longitudinal striations. There shall be 16 to 20 striations (tooth marks) for each tooth for each 6 ft. in the longitudinal dimension, and each striation shall be 1.7 ± 0.2 in. in length after the area is planed by the moldboard. Thus the planed length between each pair of striations shall be 2.3 ± 0.2 in. There shall be 80 to 96 rows of discontinuous longitudinal striations for each 5 ft. in the transverse dimension. The pattern of striations shall be such that a line connecting striations in adjacent rows shall form approximately a 70 degree skew angle with the pavement centerline. The areas between the striations in both the longitudinal and transverse directions shall be flat-topped and coplanar. The moldboard shall be used to cut this plane, and any time the operation fails to produce this flat plan interspersed with a uniform pattern of discontinuous longitudinal striations, the operation shall be stopped and the cause determined and corrected before recommencing.

When tested with a 16 foot straightedge, the planed or milled surface shall have no surface variations in excess of 3/16 inches.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### METHOD OF MEASUREMENT

ADD the following paragraphs:

4.2. The quantity of pavement milling to be paid for shall be the number of square yards completed and accepted by the Resident Engineer based upon the widths and lengths of the milled areas as measured in place. Double payments for the same surface area shall not be made for overlapping passes of the milling planer.

Measurements shall not include any areas of pavement milled by the Contractor outside the limits set by the Resident Engineer. If the Contractor mills pavement outside the limits set by the Resident Engineer, the Contractor shall clean, tack coat, and fill the unauthorized milled out area with 401 Bituminous Surface Course at his own expense and no additional compensation of measurements will be allowed for this extra work.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

### MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM AR401900

## REMOVE BITUMINOUS PAVEMENT (CHECK SHEET # 26)

EFFECTIVE: JULY 1, 2004

#### **CONSTRUCTION METHODS**

3.1.1 This item shall include the removal of the existing Taxiway D and Taxiway E bituminous pavement as indicated on the Construction Plans.

The Contractor shall remove the existing pavement full depth as shown on the plans or as directed by the Resident Engineer. The removal shall include any PCC Concrete or Aggregate Base Course beneath the Bituminous Concrete Surface. No additional compensation will be made for removing the base and/or subbase materials. Where removal areas are adjacent to areas which are to remain in service, a full depth saw cut shall be made before breaking and removing the pavement.

It shall be the responsibility of the Contractor to determine the type and thickness of the existing pavement to be removed, and the extent to which it is reinforced. No additional compensation will be allowed because of variations from the assumed thickness or from the thickness shown on the plans, or for variations in the amount of reinforcement.

The Contractor shall dispose of the material removed to a suitable location off airport property. The Contractor is responsible for finding a suitable disposal area.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM 501002 (CHECK SHEET #28)

#### PORTLAND CEMENT CONCRETE PAVEMENT - METHOD II

EFFECTIVE: JULY 1, 2004

#### 501-1.1 ADD the following to this Section:

The Item 501512 PCC Pavement for this project shall be used to construct the Runway 5-23 and Taxiway P 12" thick P.C. concrete pavement. The proposed pavements shall be constructed on an existing prepared surface in accordance with these specifications and shall conform to the lines, grades, thicknesses, and cross sections found in the Construction Plans.

#### 501-2.5 JOINT SEALER

REWRITE this item as follows:

Type A and B joints shall include hot poured joint sealer per Item 605 of the Standard Specifications using ASTM D6690 joint sealing materials.

The joint sealing material for Type C, D, E, E-1, F, G and H joints shall be a neoprene compression seal meeting the requirements of ASTM D-2628, as manufactured by D. S. Brown Corporation or an approved equal. The sealing material shall be installed per manufacturer's instructions by mechanical methods approved by the Resident Engineer. The lubricant/adhesive for installation of the compression seal shall be a one component compound conforming to the requirements of ASTM D-2835. Where a hot poured joint sealer is specified, the materials shall meet the requirements of ASTM D6690 - Joint Sealants, hot poured for concrete and asphalt pavements on "Taxiways and Runways Only." The Contractor shall comply with these special provisions and Item 605 of the Standard Specifications for Construction of Airports.

The Contractor shall submit the following samples for approval at least two weeks prior to beginning work.

- 1. Joint sealant, 3 foot length for each size.
- 2. Lubricant/adhesive, 1 U.S. quart.
- 3. Two copies of certified test results demonstrating conformance to the applicable material specifications.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

4. Two copies of the manufacturers recommendations for installation procedures.

The Contractor will not be allowed to begin installation until the above items are furnished in full. Failure to furnish these items can be cause for rejection of the material.

The Contractor shall store the lubricant/adhesive at a temperature between 40° F and 85° F and shall be used within 270 days of its manufacture.

Atmospheric and pavement temperatures shall be between 40° F and 85° F at the time of joint seal installation.

#### 501-2.6 STEEL REINFORCEMENT

ADD the following to this Section:

Steel reinforcement shall be installed in the odd shape concrete panels as indicated on the Construction Plans. Reinforcing shall consist of welded wire fabric conforming to the requirements of ASTM A185.

#### 501-2.7 DOWEL AND TIE BARS

ADD the following to this Section:

Tie Bars shall not be bent and restraightened on this project. Tie bars and dowels shall be drilled and installed into the newly poured slabs using a polyester resin based adhesive that is on the IDOT approved materials list and/or the use of threaded couplings shall occur on this project.

Both dowel bars and tie bars shall be epoxy coated according to the requirements of AASHTO M254.

#### 501-2.9 COVER MATERIAL FOR CURING

ADD to this Section the following:

Curing materials conforming to Section (a) shall be used on this project.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **CONSTRUCTION METHODS**

#### 501-3.2 FORM SETTING

ADD to this Section:

If formed construction is utilized, the built-up forms shall be provided with adequate devices for setting so that when in placed they will withstand, without visible spring or settlement, the impact and vibration of the consolidating and finishing equipment. If, in the opinion of the Resident Engineer, the forms are inadequately braced or bedded, the Contractor shall, at his expense, cease all paving operations and provide additional bracing and/or bedding to the satisfaction of the Resident Engineer prior to commencing and/or continuing any paving operations. If built-up forms are used, the form with the greatest vertical dimension shall be placed at the bottom.

#### 501-3.6(A) PROPORTIONS

DELETE: Entire Section.

#### 501-3.7 FIELD TEST SPECIMENS

REWRITE the first and second paragraphs as follows:

"Concrete samples shall be taken in the field by the Contractor's quality control personnel to determine consistency (slump), air content, and strength of the concrete as directed by the Resident Engineer and outlined in this Special Provision. A slump test per ASTM C143 and air test per ASTM C231 shall be taken by the Contractor, under the direction and supervision of the Resident Engineer, for each test beam and at a minimum of one test per 300 cubic yards of concrete. A minimum of one random flexural strength sample or one random compressive strength sample shall be taken by the Contractor for every 300 cubic yards for acceptance testing. A sample shall consist of two (2) beam breaks for flexural strength testing and/or two (2) cylinders for compression strength testing. <u>If cylinders are used, the Contractor</u> shall deliver the cylinders to a testing facility as designated by the Resident and Chief Engineer. The Contractor shall be responsible for all costs incurred to accomplish this testing. At the start of paving operations and when the aggregate source, aggregate characteristics, or mix design is changed, additional samples may be required by the Chief and/or Resident Engineer until he is satisfied that the concrete mixture being manufactured complies with the strength requirements of these specifications and that the concrete allowable water-cementitious ratio is not exceeded. The additional test samples shall be taken by the Contractor for 3, 7, and 14 day testing. All samples shall be prepared in accordance with ASTM C31. Ten (10) steel beam molds (Rainhart Cat. No. 421 beam mold or equivalent) and two (2) beam mold strippers (Rainhart Cat. No. 425 beam mold strippers or equivalent) meeting the approval of the Resident Engineer

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

shall be supplied by the Contractor. Following completion of the project, these items shall become the property of the MAA. The remainder of the beam molds needed for the project will be supplied by the MAA. After completion of the proposed project, the Contractor shall return all beam molds to the MAA in a clean, straight, and good condition. The Contractor shall be responsible for molding, removing from the molds, curing and placing properly cured beams according to ASTM C31 in the field trailer at the time and place specified by the Resident Engineer. The Contractor shall furnish and maintain a beam tank or tanks of adequate size and maintain its condition in accordance with ASTM C31. All samples shall be tested by the Resident Engineer in accordance with ASTM C78. Flexural strength testing under ASTM C78 will require a Rainhart Series 416 Recording Beam Tester or equivalent.

#### 501-3.10 PLACING CONCRETE

ADD:

The Contractor shall place the concrete in a manner such that <u>no concrete trucks will</u> <u>drive over the aggregate base course</u> material in the paving lane. The Contractor shall utilize a belt loader (or other method as approved by the Engineer) to side load the concrete into the paving lane.

#### 501-3.14 SURFACE TEXTURE

ADD:

The surface texture shall meet the requirements for Burlap Drag Finish.

#### 501-3.15 SKID RESISTANT SURFACES

ADD to this Section:

Saw cut grooves shall be required on the runway P.C.C. and Bituminous pavements. Saw cut grooves are not required on the taxiway pavements. Both P.C.C. pavements grooving and Bituminous pavement grooving shall be measured and paid for under contract Item AR501540.

#### 501-3.17 CURING

ADD:

Curing shall meet the requirements for Impervious Membrane Method except during cold weather, when the requirements of Curing in Cold Weather shall apply.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### **BASIS OF PAYMENT**

Payment will be made under:

ITEM AR501512 -- 12" PCC PAVEMENT -- per square yard.

ITEM AR501530 -- PCC TEST BATCH -- per each.

ITEM AR501540 -- PCC PAVEMENT GROOVING -- per square yard.

ITEM AS501512 -- 12" PCC PAVEMENT -- per square yard.

ITEM AT501512 -- 12" PCC PAVEMENT -- per each.

ITEM AT501540 -- PCC PAVEMENT GROOVING -- per square yard.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### MODIFICATIONS TO RECURRING SPECIAL PROVISIONS FOR ITEM AR501900 (CHECK SHEET #33)

REMOVE PCC PAVEMENT

EFFECTIVE: JULY 1, 2004

#### **CONSTRUCTION METHODS**

#### ADD the following Section:

3.1.1 The Contractor shall remove the existing pavement full depth as shown on the plans or as directed by the Resident Engineer. The removal shall include any Bituminous Concrete or Crushed Aggregate Base Course required to be removed that lies beneath the PCC Pavement. No additional compensation will be made for removing the base and/or subbase materials. Where removal areas are adjacent to areas which are to remain in service, a full depth saw cut shall be made before breaking and removing the pavement.

It shall be the responsibility of the Contractor to determine the type and thickness of the existing pavement to be removed, and the extent to which it is reinforced. No additional compensation will be allowed because of variations from the assumed thickness or from the thickness shown on the plans, or for variations in the amount of reinforcement.

The Contractor shall dispose of the material removed at a suitable location off airport property. The Contractor is responsible for finding a suitable disposal area.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

## MODIFICATIONS TO SUPPLEMENTAL SPECIFICATIONS FOR ITEM 605000 JOINT SEALING FILLER

EFFECTIVE: JULY 1, 2004

#### **MATERIALS**

#### 605-2.1 JOINT SEALING MATERIALS

DELETE Section (c) ASTM D3405 and ADD the following:

(c) ASTM D6690-Joint sealants, hot-poured, for concrete and asphalt pavements on taxiways and runways only. This ASTM D6690 material shall be used for hot-poured joint sealant on this project.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### <u>ITEM 620 – PAVEMENT MARKING</u>

#### **DESCRIPTION**

#### 620-1.1 ADD the following to this Section:

The MAA reserves and shall have the right to delete the pavement marking pay item from the proposed contract work. The sponsor may opt to complete this work with their own work force. Prior to ordering any materials or starting any work, the Contractor shall confirm the status of this work with the MAA. The Contractor shall not be entitled to any extra compensation for the deletion of these pay items.

The pavement markings shown on the Construction Plans shall be applied as approved by the Resident Engineer.

#### **MATERIALS**

620-2.2 PAINT

ADD:

The paint for this project shall be Waterborne.

DELETE the entire paragraphs:

2. EPOXY

#### **CONSTRUCTION METHODS**

#### 620.3.3 LAYOUT OF MARKINGS

ADD:

The Contractor or painting subcontractor shall be responsible for the layout of the proposed paint markings. Paint shall not be applied until the condition of the surface have been reviewed by the Resident Engineer. If, in the opinion of the Resident Engineer, the markings applied do not conform with these special provisions or the Construction Plans the Contractor shall remove and correct the markings at his own expense.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### 620-3.5 APPLICATION

CHANGE the first sentence of the second paragraph to read:

The paint shall be mixed in accordance with the manufacture's instructions and applied to the pavement with a marking machine in two separate applications, each at the rate(s) shown in Table 1.

Table 1. Application Rates for Paint and Glass Beads

Paint Type	Paint	Glass Beads, Type I, Gradation A
	Square feet per gallon, ft <sup>2</sup> /gal	Pounds per gallon of paint, lb/gal
Permanent		
Waterborne	115 ft <sup>2</sup> /gal maximum	10 lb/gal minimum
Markings		

DELETE the last sentence of the fourth paragraph.

ADD the following paragraphs:

A period of 24 hours shall elapse prior to the first application of paint if TT-P-1952 is used.

#### METHOD OF MEASUREMENT

#### 620-4.1 ADD the following to this Section:

Measurements for payment shall be made for the pavement marking surface area only once. The contract unit price shall include costs for all applications of paint on the pavement marking surface area.

#### **BASIS OF PAYMENT**

Payment will be made under:

ITEM AR620510 -- PAVEMENT MARKING -- per square foot.

ITEM AS620510 -- PAVEMENT MARKING -- per square foot.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### DIVISION IV – DRAINAGE PIPE

#### MODIFICATIONS TO SUPPLEMENTAL SPECIFICATIONS FOR ITEM 701 – PIPE FOR STORM SEWERS AND CULVERTS

#### **DESCRIPTION**

#### 701-1.1 ADD:

Bedding material consisting of IDOT Gradation number CA-11 (as described in Section 1004 of the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2007), IDOT Gradation RR-3, Quality Designation "A" and/or a similar graded material, as approved by the Resident Engineer (and described in Section 1005 of the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2007) as well as geotechnical fabric and porous backfill as shown on the plan details shall be included in this item.

This item shall also include the installation, maintenance, and removal of all dewatering items required to insure the bedding and pipes are installed in a dry excavation. Ground water flows into the pipe trenches shall not be allowed. The Contractor shall not install bedding materials or lay pipes in a wet excavation. The costs for dewatering shall be included in the "701 – Pipe for Storm Sewers and Culverts" contract unit prices.

#### **MATERIALS**

#### 701-2.1 GENERAL

ADD:

Reinforced concrete pipe shall conform to ASTM C76. Pipe joints shall be rubber gasket conforming to ASTM C443.

The geotechnical fabric for pipe bedding shall consist of nonwoven filaments formed from a plastic yarn of a long-chain synthetic polymer composed of at least 85 percent by weight of polyolefins, or polyesters, and shall contain stabilizers and/or inhibitors added to the base plastic to make the filaments resistant to deterioration due to ultraviolet and heat exposure. After forming, the fabric shall be a processed so that the filaments retain their relative positions with respect to each other. The fabric shall be free of defects or flaws which significantly affect its physical and/or filtering properties.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

The filter fabric shall be formed in widths of not less than 6 feet. Sheets of fabric may be sewn together with thread of a material meeting the chemical requirements given for the plastic yard to form fabric widths as required. The sheets of filter fabric shall be sewn together at the point of manufacturer or another approved location.

Requirements: The texture of the fabric shall be such that the bedding and riprap will remain in an equilibrium state and not slip or slide. The filter fabric shall be rot proof, insect resistant and have a high dimensional stability when wet, good soil filtration characteristics and a high resistance to tear propagation in all directs, and meet the following minimum conditions and ASTM Tests for the gradation of riprap specified:

Weight of Fabric (oz/yd) ASTM D 3776 (Mod.) (Note 2)	6.0
Burst Strength (psi) ASTM D 3786 (Note 1)	250
Trapezoidal Tear Strength (lbs) ASTM D 1117 (Note 2)	60
Grab Tensile Strength (lbs) ASTM D 4632 (Note 2)	160
Grab Tensile Elongation (%) ASTM D 4632 (Note 2)	20

Note 1. Manufacturer's certification of fabric to meet requirements.

Note 2. Test sample shall be tested wet.

The vendor shall furnish certified test reports with each shipment of material attesting that the fabric meets the requirements of this specification.

# **CONSTRUCTION METHODS**

# 701-3.3 CRADLES

DELETE:

Entire Section.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### 701-3.7 BACKFILLING

ADD:

All proposed pipes shall be backfilled with compacted materials meeting the requirements for Porous Material No. 1 in Item 705-2.15 as shown in the plan details. Local soil materials excavated on this site shall not be used for Trench Backfill or Porous Material No. 1 backfill. Porous Material No. 1 shall not be measured or paid for separately, but shall be included in the 701 contract unit prices.

# METHOD OF MEASUREMENT

# 701-4.1 ADD:

Geotextile fabric, aggregate bedding, porous backfill, and dewatering items installed to construct the storm sewer and culvert pipes will not be measured for payment under this item or any other contract item. These necessary items shall be considered incidental to the contract unit price for the specified type, class, and size of pipe being installed.

# **BASIS OF PAYMENT**

# 701-5.1 ADD to this Section:

The costs for geotextile fabric, aggregate bedding, porous backfill and dewatering items installed to construct the storm sewer and culvert pipes shall be included in the contract unit price for the specified type, class, and size of pipe being installed.

Payment will be made under:

ITEM AR701442 -- 42" RCP, CLASS III -- per lineal foot.

ITEM AR701512 -- 12" RCP, CLASS IV -- per lineal foot.

ITEM AR701524 -- 24" RCP, CLASS IV -- per lineal foot.

ITEM AR701713 -- RCEP SPAN 30 RISE 19 -- per lineal foot.

ITEM AR701900 -- REMOVE PIPE -- per lineal foot.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO SUPPLEMENTAL SPECIFICATIONS FOR ITEM 705 - PIPE UNDERDRAINS FOR AIRPORT

# **DESCRIPTION**

# 705-1.1 DELETE the third paragraph from this Section and ADD the following:

The perforated underdrain pipe on this project shall be 6" dia. Corrugated polyethylene (PE) tubing and IGS fittings (perforated and non-perforated) meeting the requirements of Section 705-2.12. The perforated polyethylene (PE) tubing shall be wrapped or covered with a filter fabric envelope that meets the requirements of Section 705-2.13.

The bid price per linear foot of pipe shall include fittings, pipe bedding and backfilling of the pipe trench as detailed in the Construction Plans. Porous Material No. 2 as described in Section "705-2.15 Porous Backfill" shall be supplied and installed by the Contractor. No separate measurement or payment shall be made for the Porous Material No. 2 Backfill and/or bedding. The cost of the Porous Material No. 2 Backfill shall be included in the 705 Pipe Underdrain contract unit price per lineal foot.

# **CONSTRUCTION METHODS**

#### 705-3.3 LAYING AND INSTALLING PIPE

(C) ALL TYPES OF PIPE

ADD to this Section:

All pipe underdrains to be placed parallel to the runway and/or taxiway shall be placed below the minimum depth as shown on the detail drawings in the Plans, except those area that are noted as "Variable Depth" on the Plans. The 705 Pipe Underdrain contract unit prices shall include the variable depth excavation required.

# 705-3.6 BACKFILLING

DELETE the second sentence in the first paragraph and ADD:

The material supplied and installed by the Contractor for backfill shall meet the requirements of Porous Material No. 2. The Contractor shall not substitute or allow the original materials excavated to be returned into the trench.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# METHOD OF MEASUREMENT

# 705-4.2 DELETE this Section and ADD the following:

Pipe fittings, porous bedding and backfill materials as indicated on the Construction Plans installed to construct the pipe underdrains will not be measured for payment under this item or any other contract item. The costs for these items shall be included in the 705 Pipe Underdrain contract unit price for the specified type, class, and size of pipe being installed.

# **BASIS OF PAYMENT**

ADD the following:

Payment will be made under:

ITEM AR705506 -- 6" PERFORATED UNDERDRAIN -- per lineal foot.

ITEM AS705506 -- 6" PERFORATED UNDERDRAIN -- per lineal foot.

ITEM AT705506 -- 6" PERFORATED UNDERDRAIN -- per lineal foot.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO SUPPLEMENTAL SPECIFICATIONS FOR ITEM 751 - MANHOLES, CATCH BASINS, INLETS AND INSPECTION HOLES

# **DESCRIPTION**

# 751-1.1 ADD the following to this Item:

This item shall include the adjustment or reconstruction of existing manholes, inlets and special structures in accordance with Section 602 <u>Catch Basin, Manhole, Inlet, Drainage Structures, and Valve Vault Construction, Adjustment and Reconstruction</u> of the "Standard Specifications for Road and Bridge Construction" adopted January 1, 2007, including all addendum at the time of bidding. The Contractor shall be required to replace any frame and lid damaged during the adjustment with a similar frame and lid at his expense.

This item shall also include supplying and installing proposed manholes and inlets as shown on the plans, complete with castings. The cone section and/or flat slab tops for the proposed manholes shall be precasted with a frame lip notch as detailed in the Construction Plans.

# **MATERIALS**

DELETE Sections 751-2.1 and 751-2.5 and ADD the following:

No brick construction will be allowed on this project.

Materials for manhole, inlet and special structure adjustments, reconstructions and removals shall conform to the provisions of Section 602.02-<u>Materials</u> of the "Standard Specification for Road and Bridge Construction," as adopted January 1, 2007, including all addendums at the time of bidding.

# 751-2.6 FRAMES, COVERS, AND GRATES

ADD the following to this Section:

Under Item AR751410, Inlet (Double), the Contractor shall supply a Neenah R-3475-3 or equal frame and grate.

Under Item AR751415, Inlet Special (Single), the Contractor shall supply a Neenah R-3475 or equal frame and grate.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

Under Item AR751540, Manhole 4'; AR751550, Manhole 5'; AR751560, Manhole 6'; AR751570, Manhole-Special; AS751570, Manhole-Special; and AT751570, Manhole-Special, the Contractor shall supply a Neenah R-3493A or equal frame and solid lid.

The cost of installing the above described items shall be included in the 751 Inlet and Manhole contract unit prices.

# **CONSTRUCTION METHODS**

# 751-3 ADD to this Section as follows:

The method of construction for manhole, inlet and special structure adjustments shall conform to Section 602 - CATCH BASIN, MANHOLE, INLET, DRAINAGE STRUCTURES, AND VALVE VAULT CONSTRUCTION ADJUSTMENT AND RECONSTRUCTION of the "Standard Specifications for Road and Bridge Construction," as adopted January 1, 2007, including all addendums at the time of bidding.

DELETE Section 602.05 - BRICK MASONRY; Section 602.06 - CONCRETE MASONRY UNITS; Section 602.11 - EXCAVATION AND BACKFILLING; and Section 602.15 - BASIS OF PAYMENT.

DELETE all references to brick construction. No brick construction will be allowed. Adjustments shall be made using precast adjustment rings laid out in full mortar beds.

The method of construction for removing manholes and catch basins shall conform to Section 605 Removing or Filling Existing Manholes, Catch Basins, and Inlets of the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2007, including all addendum at the time of bidding.

# METHOD OF MEASUREMENT

# 751-4.1 ADD to this Section as follows:

The number of manholes, inlets, manhole removals, and catch basin removals to be paid for shall be the number of each size and type, as classified, counted in place, and accepted by the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A OU008

Separate measurements for payment shall not be made for removing and replacing existing castings, installation of porous backfill #1, excavation around and removal of manhole sections, and any concrete adjusting rings necessary to bring manholes to the specified grade. The cost of these items shall be included in the Item 751 contract unit prices.

# **BASIS OF PAYMENT**

# 751-5.1 ADD to this Section as follows:

The number of manholes, inlets, manhole removals, and catch basin removals shall be paid for at the contract unit price per each type, complete and in place. This price shall be full compensation for furnishing all materials and for all preparation saw cutting, existing concrete backfill removal, disposal of waste material, excavating, replacement of frame and lid (if required), soil backfilling (in turf), concrete backfilling (in pavement), porous granular backfill (under pavement), and placing of materials as may be required to complete the items as shown on the plans, and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

ITEM AR751410 -- INLET -- per each.

ITEM AR751415 -- INLET-SPECIAL -- per each.

ITEM AR751540 -- MANHOLE 4' -- per each.

ITEM AR751550 -- MANHOLE 5' -- per each.

ITEM AR751560 -- MANHOLE 6' -- per each.

ITEM AR751570 -- MANHOLE-SPECIAL -- per each.

ITEM AR751903 -- REMOVE MANHOLE -- per each.

ITEM AR751906 -- REMOVE CATCH BASIN -- per each.

ITEM AR751945 -- ADJUST MANHOLE-NON PAVEMENT -- per each.

ITEM AR751963 -- RELOCATE MANHOLE -- per each.

ITEM AS751570 -- MANHOLE-SPECIAL -- per each.

ITEM AT751570 -- MANHOLE-SPECIAL -- per each.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO SUPPLEMENTAL SPECIFICATIONS FOR ITEM 752 – CONCRETE CULVERTS, HEADWALLS, AND MISCELLANEOUS DRAINAGE STRUCTURES

# **DESCRIPTION**

#### 752-1.1 ADD to this Section:

The precast concrete pipe end sections shall conform to IDOT Highway Standard 542301 or 542306 as modified by these Special Provisions and the Construction Plans. Bedding materials, granular backfill and geotechnical fabric as described in Item 701 and shown on the plan details shall be included in this item.

# <u>MATERIALS</u>

# **752-2.1 CONCRETE**

Precast concrete pipe end sections and elbows shall conform to ASTM C 76, Wall B Reinforced Concrete Pipe. The pipe joints shall be rubber gasket conforming to ASTM C443.

# METHOD OF MEASUREMENT

# 752-4.1 ADD the following to this Section:

Geotextile fabric, aggregate bedding, and granular backfill installed to construct the pipe end sections and elbows will not be measured for payment under this item or any other contract item. These items shall be considered incidental to the contract unit price for the specified size of pipe end section being installed.

# **BASIS OF PAYMENT**

# 752-5.1 Payment will be made under:

ITEM AR752424 -- PRECAST REINFORCED CONC. FES 24" -- per each.

ITEM AR752442 – PRECAST REINFORCED CONC. FES 42" -- per each.

ITEM AR752724 -- P R CONC. FES EQ. ROUND SIZE 24" -- per each.

ITEM AR752900 -- REMOVE END SECTION -- per each.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **DIVISION V - TURFING**

# MODIFICATIONS TO SUPPLEMENTAL SPECIFICATION FOR ITEM 901-SEEDING

# **DESCRIPTION**

# 901-1.1 ADD to this Section as follows:

This item shall include, but not be limited to, all work necessary to seed all areas disturbed by the construction of this project. Areas disturbed which are outside the limits of construction/seeding shall be seeded according to this Special Provision by the Contractor, but shall not be measured for payment or paid for.

# **MATERIALS**

# 901-2.1 SEED

ADD to this Section as follows:

The seeds shall be planted at a depth between 1/4 inch and 1/2 inch below the final ground surface. All sowing of seed shall not begin prior to March 15 and shall be completed by May 15, or shall not begin prior to August 15 and shall be completed by October 15.

The seeding operation for any area shall be completed within forty-eight (48) hours following the application of fertilizer to that area.

# **CONSTRUCTION METHODS**

# 901-3.4 MAINTENANCE OF SEEDED AREAS:

ADD the following to this Section:

It will be the responsibility of the Contractor to establish a good stand of grass of uniform color and density to the satisfaction of the Resident Engineer. In areas where the seeds sown fail to grow, in the opinion of the Resident Engineer, the Contractor shall reseed the areas as required and as many times as required until the Resident Engineer is satisfied with the results. No measurements for payment or payments will be made for areas requiring reseeding.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **METHOD OF MEASUREMENT**

# 901-4.1 ADD to this Section as follows:

The areas to be seeded will consist of the areas designated on the plans. Areas disturbed due to Contractor carelessness or for the convenience of the Contractor, such as haul roads, parking areas, storage areas, soil waste areas, etc., shall be seeded but will not be measured for payment. Areas requiring more than one application of seeding shall be measured for payment only once.

# **BASIS OF PAYMENT**

ADD to this Section as follows:

ITEM AR901510 -- SEEDING -- per acre.

ITEM AT901510 -- SEEDING -- per acre.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# MODIFICATIONS TO SUPPLEMENTAL SPECIFICATION FOR ITEM 908-MULCHING

# **DESCRIPTION**

# 908-1.1 ADD to this Section as follows:

This item shall include, but not be limited to, all work necessary to hydraulic mulch all areas disturbed by the construction of this project. Areas disturbed which are outside the limits of construction/seeding shall be hydraulic mulched according to this Special Provision by the Contractor, but shall not be measured for payment or paid for.

This item shall also include, but not be limited to, all work necessary to supply and install excelsior blanket in accordance with Section 251 Mulch of the "Standard Specifications for Road and Bridge Construction" adopted January 1, 2007, including all addendum at the time of bidding. The location of the excelsior blanket shall be determined by the Resident Engineer in the field at the time of construction. The MAA reserves and shall have the right to delete part or all of the AR908520 pay item from the proposed contract work. The Contractor shall not be entitled to any extra compensation for the deletion of this pay item or quantities.

# **MATERIALS**

ADD the following Section:

# 908-2.2 Excelsior Blanket Materials

Materials for excelsior blanket shall conform to the provisions of Section 251 of the "Standard Specifications for Road and Bridge Construction" adopted January 1, 2007, including all addendum at the time of bidding.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **CONSTRUCTION METHODS**

ADD the following Sections:

#### 908-3.3 CARE AND REPAIR

It will be the responsibility of the Contractor to establish a good stand of grass of uniform color and density to the satisfaction of the Resident Engineer. In areas where the seeds sown fail to grow, in the opinion of the Resident Engineer, the Contractor shall re-mulch the areas as required and as many times as required until the Resident Engineer is satisfied with the results. No measurements for payment or payments will be made for areas requiring remulching. Hydraulic mulch will be required in all areas where additional applications area necessary.

#### 908-3.4 EXCELSIOR BLANKET

The method of construction for excelsior blanket shall conform to Section 251-<u>Mulch</u> of the "Standard Specifications for Road and Bridge Construction" adopted January 1, 2007, including all addendum at the time of bidding..

# METHOD OF MEASUREMENT

# 908-4.1 ADD to this Section as follows:

The areas to be hydraulic mulched will consist of the areas designated on the plans. Areas disturbed due to Contractor carelessness or for the convenience of the Contractor, such as haul roads, parking areas, storage areas, stockpile areas, etc., shall be hydraulic mulched, but will not be measured for payment. Areas requiring more than one application of mulch shall be measured for payment only once.

ADD the following Section:

# 908-4.2 EXCELSIOR BLANKET

The quantity of excelsior blanket to be paid for shall be the number of square yards of actual surface area covered as specified, in place, completed, and accepted by the Resident Engineer. The overlapped areas will not be measured for payment, but shall be included in the contract unit price.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **BASIS OF PAYMENT**

# 908-5.1 DELETE the entire Article and insert the following:

Payment will be made at the contract unit price per acre for MULCHING-METHOD 3. This price shall be full compensation for furnishing all materials and for placing and anchoring the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

ADD the following Section:

# 908-5.2 EXCELSIOR BLANKET

The number of square yards of excelsior blanket measured as provided above shall be paid for at the contract unit price per square yard for furnishing, storing, and installing the excelsior blanket. This price shall be full compensation for all labor, materials, and equipment necessary to complete this item.

Payment will be made under:

ITEM AR908513 -- MULCHING-METHOD 3 -- per acre.

ITEM AR908520 -- EXCELSIOR BLANKET -- per square yard.

ITEM AT908513 -- MULCHING-METHOD 3 -- per acre.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **DIVISION VI - LIGHTING INSTALLATION**

# ITEM 108 - INSTALLATION OF UNDERGROUND CABLE FOR AIRPORTS

# **DESCRIPTION**

# 108-1.1 ADD the following to this Section:

This item of work shall consist of the installation of cable at the locations shown on the plans and in accordance with these specifications.

Contract Item AR108962-REPLACE CABLE consists of the replacement of the existing S.S.I. Type V sensor extension cable in the north on-site borrow area.

If the Contractor wishes to lay cable on a line other than that shown on the plans, he shall obtain approval of the Resident Engineer before doing so. Any additional cable or wire needed because of such change will be at the Contractor's expense.

At locations where the existing cable to be replaced might obstruct or interfere with the efficient operation of the electrical system and in locations indicated on the Construction Plans, the existing cable shall be removed and disposed of by the Contractor. The Contractor shall install pull cords and plugs in the existing conduits where existing cables are removed and no new cable is proposed. The costs of removing and disposing of any existing cable, new pull cords, and new plugs shall be considered as incidental to the contract unit price and no additional compensation will be allowed.

When required, the Contractor shall pull out and reinstall existing cables in the existing facilities as indicated on the Construction Plans. The costs of pulling and reinstalling the existing cables and proposed cables shall be included in the 108 Underground Cable contract unit price.

In areas where there is a congestion of buried cables or where the proposed cable crosses an existing cable, the Contractor shall be required to hand dig the proposed cable into place or hand dig to remove an existing cable. In all other areas, the Contractor has the option to either trench or plow the proposed cable in unit duct into place.

Prior to excavating any area, the Contractor shall be required to megger all existing light circuit cables at the regulators in the transformer. All readings shall be submitted to the Resident Engineer.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

Upon completion of the project, similar megger readings shall be made on both new and existing light circuit cables to insure that existing cable has not been damaged due to construction. All readings shall be submitted to the Resident Engineer.

The Contractor shall be required to provide a 24-hour answering service with a one hour response to enact repairs to existing lighting cable damaged due to construction as authorized by the Owner. All costs borne to repair such damaged cable shall be the responsibility of the Contractor.

In order to avoid existing underground cable, the Contractor shall connect a thumper to all existing circuits after which the cables shall be staked in all areas requiring trenching or excavation. Contractor shall also note that low voltage, FAA, cables also run underground throughout these areas.

# **EQUIPMENT AND MATERIALS**

# 108-2.2 CABLE

REVISE this Section to read as follows:

Underground cable shall conform to the requirements of F.A.A. Advisory Circular 150/5345-7D, "Specifications for L-824 Underground Electrical Cable for Airport Lighting Circuits." Cable used for the runway and taxiway lighting circuits shall be (Tamaqua Cable Products Corporation or approved equal) No. 8, 5000 Volt, EPR, MV 90, L-824 Type B, one or two conductors, stranded, cable with PVC jacket meeting ICEA S-68-516, in unit duct. The proposed cable and unit duct shall be factory assembled and delivered to the site on reels. The unit duct shall be manufactured from yellow polyethylene complying with NEMA standard for high density, smooth wall, and coilable polyethylene electrical plastic duct Pub. No. TC7-1978. The unit duct surface shall have four integral black stripes with a separation angle of 90 degrees. Airfield series circuit cables shall be unit assembly with one inch (1") diameter unit duct. Homerun cables and cables to guidance signs shall be two of the above cables in one unit duct, 1-1/2" assembly. Field terminate homeruns in manholes or splice cans with a minimum of three each 2" diameter conduit openings.

Contract Item AR108962-REPLACE CABLE shall conform to the requirements of FAA Advisory Circular 150/5320-13B, "Runway Surface Condition Sensor Specification Guide". The Type V sensor extension cable shall be supplied by Surface Systems, Inc. of St. Louis, MO (or approved equal). Splice kits shall be SSI P/N 24051016 (FP 2000) or approved equal. All splices shall be made in splice cans. All splices shall be per manufacturer's instructions.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

It is the desire of the Owner to have interchangeable lighting cable throughout the airport, therefore the Metropolitan Airport Authority reserves the right to select and/or approve electrical cable and materials to be supplied for this project.

15 KV rated cable shall be shielded power cable Type MV-90 compact copper conductor Class B strand. Insulation type shall be ethylene propylene rubber (EPR) with polyvinyl chloride (PVC) outer jacket.

Cable shall meet or exceed requirements of ICEA S-68-516 and AEIC CS6 standard for EPR insulated wire and cable.

Cable gauge and number of conductors shall be as detailed on the plans.

# **CONSTRUCTION METHODS**

# 108-3.1 GENERAL

ADD the following to this Section:

The cable quantities as shown on the Construction Plans are based on straight line measurement and do not consider any vertical distances or the required cable slack as stated under Item 108-3.4 in Illinois Standard Specifications for Construction of Airports, January 1985.

All cable shall be installed direct buried or plowed as indicated on the drawings, using new and existing cable ducts under runways, roads, home runs to transformer vaults, etc.

Each day, prior to leaving the job site, the Contractor, in the presence of the Owner's representative, shall activate all airport lighting circuits to insure operation.

At base mounted lights and splice cans the unit duct shall be attached to the base can rigid steel conduits with fittings as indicated on the Construction Plans.

#### 108-3.2 INSTALLATION IN DUCT OR CONDUIT

ADD the following to this Section:

The unit duct will be run continuous through all ducts.

# 108-3.4 INSTALLATION IN TRENCHES

CHANGE the first sentence to read as follows:

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

Except for installation of cable (or cables) in unit duct, the Contractor shall <u>not</u> use a cable plow for installing the cable.

# ADD the following to this Section:

At locations, such as in an existing duct or wireway, in the existing electrical vault area, existing electrical manhole, utility tunnel, duct bank or near a proposed light location, where the existing cable to be replaced might obstruct or interfere with the efficient operation of the electrical system, it shall be removed and disposed of by the Contractor. The cost of removing and disposing of this existing cable shall be considered as incidental to the contract unit price per linear foot for underground cable installed in trench or duct, and no additional compensation will be allowed.

Any and all trenches will be backfilled to a smooth grade to the satisfaction of the Resident Engineer. The disturbed areas will be either sodded or seeded, limed and fertilized. Lime will be applied at the rate of two (2) tons per acre. Any combination of the following nutrient materials is acceptable providing the minimum requirements are met: complete fertilizer, sulphate of ammonia, ammonium nitrate, ammonium phosphate or muriate of potash.

# FERTILIZER APPLICATION RATES

Minimum Pounds of Available Nutrient	<u>P</u>	lant Food Per Acre
N		90
$P_2O_5$		350
$K_2O$		<u>240</u>
	Total	680

The sodding, seeding and fertilizing of trench areas as described will be incidental to Item 108 and no additional compensation will be allowed. Seed used shall be Alta Fescue, applied at the rate of 100 lbs. of pure live seed per acre.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following to this Section:

The unit duct shall be installed so that it is possible to withdraw a cable and pull in a new one. Sweeping long radius bends shall be used. Any run with a kink or short radius bend will be rejected. The cable in unit duct will be installed continuous between lights without any splices in cable or unit duct. Splices in homeruns shall be made inside an approved splice box as directed by the Resident Engineer.

Where two or more cables are laid parallel in the trench, they shall be placed laterally a minimum distance of three (3) inches apart, and the trench will be widened sufficiently to accomplish this.

Color code all phase wiring by use of colored wire insulation and/or colored tape. Where tape is used, the wire insulation shall be black. Black and red shall be used for single-phase, three wire systems and black, red and blue shall be used for three-phase systems. Neutral conductors, size No. 6 AWG or smaller, shall be identified by a continuous white or natural gray outer finish along its entire length. Neutral conductors larger than No. 6 AWG shall be identified either by a continuous white or natural gray outer finish along its entire length or by the use of white tape at its terminations and inside accessible wireways.

<u>Circuit</u>	MIMIC Panel Colors
R9-27 Circuit 1	White
R5-23 Circuit	White
T-D Circuit	Orange
T-E Circuit	Yellow
T-F Circuit 2	Lime

All branch circuit conductors connected to a particular phase shall be identified with the same color. The color coding shall be extended to the point of utilization.

Direction of primary cables shall be identified by color coding as follows: When facing light with back to pavement, cable to the left is coded red and cable to right is coded blue. This applies to stake mounted lights and base mounted lights where the base has only one entrance.

In control wiring the same color shall be used throughout the system for the same function, such as 10%, 30%, 100% brightness control, etc.

All power and control circuit conductors shall be copper, <u>aluminum shall not be</u> accepted. This includes wire, cable, busses, terminals, switch/panel components, etc.

Low voltage (600 V.) and high voltage (5000 V.) conductors shall be installed in separate wireways.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

108-3.9 ADD to this Section the following:

Bare copper counterpoise wire will not be required on the proposed edge light circuits.

ADD the following Section:

# METHOD OF MEASUREMENT

108-4.1 REVISE the first paragraph in this Section to read as follows:

The footage of cable or counterpoise wire installed or replaced in trench, duct, or conduit to be paid for shall be the number of linear foot of cable installed or replaced in trench, duct, or conduit measured in place by direct measurement, completed, ready for operation and accepted as satisfactory with no allowance being made for overrun due to required slack, turns, splices, etc. The Contractor shall take this into consideration in preparing his bid for the items concerned. Existing cables moved, replaced, and/or relocated as part of removing and replacing concrete duct banks shall not be measured for payment and/or paid for under this item.

Cable trenching shall not be measured for payment or paid for separately. The costs of cable trenching shall be included in the "Underground Cable in Unit Duct" contract unit prices.

# **BASIS OF PAYMENT**

Payment will be made under:

ITEM AR108158 -- 1/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ITEM AR108258 -- 2/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ITEM AR108962 -- REPLACE CABLE -- per lineal foot.

ITEM AS108158 -- 1/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ITEM AS108258 -- 2/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ITEM AT108158 -- 1/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ITEM AT108258 -- 2/C #8 5 KV UG CABLE IN UD -- per lineal foot.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# ITEM 110 - INSTALLATION OF AIRPORT UNDERGROUND ELECTRICAL DUCT

# **DESCRIPTION**

# 110-1.1 ADD the following to this Section:

This item of work shall include, but not be limited to, all work necessary to install, concrete encased duct (1-way, 2-way, 4-way, and 6-way), electrical manholes, remove concrete duct banks, and remove electrical manholes as detailed in the Construction Plans and in accordance with the standard specifications and these Special Provisions. All materials for these items shall be in accordance with FAA Standard Specification Item 110 "EQUIPMENT AND MATERIALS".

In locations where existing active cables are to be encased in duct banks or where existing active cables are present in existing duct banks to be removed and replaced, the contractor shall use split duct in the proposed duct bank. Cost of split duct to be included in the unit price for the DUCT BANK.

All waste materials resulting from the removal of the existing ducts and duct banks shall be disposed of by the Contractor at an approved location off of Airport property.

Proposed item AT110710-ELECTRICAL MANHOLES shall be constructed in accordance to <a href="Item">Item</a> 751-MANHOLES, CATCH BASINS, INLETS AND INSPECTION HOLES as modified by the detail drawing found in the construction plans. The proposed electrical manholes shall be constructed around existing cables. The Contractor shall protect the existing cables from damage during construction. If any cables are damaged during construction, all costs for repairing the damaged cables, including cable replacement and cable splices, shall be the responsibility of the Contractor. Replacement cables (if required) <a href="shall not">shall not</a> be measured for payment and/or paid for. The Contractor shall supply a Neenah R-3493-A or equal frame and lid (with "electrical" marked on the center of the lid) with this item.

Proposed Item AT110907-REMOVE ELECTRICAL MANHOLE shall be in accordance with <u>SECTION 605-REMOVING OR FILLING EXISTING MANHOLES</u>, <u>CATCH BASINS AND INLETS</u> of the "Standard Specifications for Road and Bridge Construction" adopted by the Illinois Department of Transportation on January 1, 2002, including all addendum at the time of bidding. Existing active cables are found inside the existing electrical manholes to be removed. The Contractor shall protect the existing cables from damage during the removal of the manhole. If any cables are damaged during the removal of the manhole, all costs for repairing the damaged cables, including cable replacement and cable splices, shall be the responsibility of the Contractor. Replacement cables (if necessary) <u>shall not</u> be measured for payment

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

and/or paid for. The Contractor shall furnish, place and compact sand backfill in the hole formed by the removal of the structure to the satisfaction of the Resident Engineer. All waste materials resulting from the removal of the existing manholes shall be disposed of by the Contractor at an approved location off of airport property.

Existing in-turf concrete cable markers damaged by the Contractor during construction, shall be replaced by the Contractor at his expense. New in-turf concrete cable markers are not required for this project. New in-pavement brass duct markers are required for this project. The costs for the brass duct markers shall be included in the 401 and/or 501 PAVEMENT contract unit prices.

# **CONSTRUCTION METHODS**

#### 110-3.1 GENERAL

ADD to this Section the following:

All electrical ducts and conduits shall be installed as indicated on the plans. All excavation required to install new duct and conduit shall be incidental to the cost of the duct. Spacers for separation of individual ducts meeting the approval of the Resident Engineer shall be required and installed in place prior to pouring concrete. The installation of pull cords, plugs, reinforcement bars, duct markers, and concrete encasement, as shown on the plans, shall be included in the 110 contract unit prices.

# 110-3.3 DUCT WITHOUT CONCRETE ENCASEMENT

ADD the following to this Item:

All rigid steel duct, jacked under pavement shall be installed to a minimum depth of 36 inches below the proposed finished grade at the locations shown on the Construction Plans.

# 110-3.4 DUCT MARKERS

ADD the following to this Section:

All existing ducts within the limits of this project under existing asphalt surfaces shall be marked with a 3" diameter brass marker located 2' in from the edge of pavement, of a type approved by the Resident Engineer. The brass markers shall be pre-stamped or chiseled on the job with the words "Electrical Duct \* - way" on the cap. (\* = 1, 2, or 4 as appropriate for duct bank). Existing ducts within the limits of this project under existing concrete surfaces shall be marked with a "D" chiseled into the existing concrete two feet in from each edge of pavement directly over the duct. New or

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

existing ducts located under new asphalt or concrete pavements shall be marked with a 3" diameter brass marker located 2' in from the edge of pavement, of a type approved by the Resident Engineer, marked on the cap as indicated above. The costs for duct markers shall be included in the 401 and/or 501 PAVEMENT contract unit prices.

ADD the following Sections to this Item:

# 110-3.7 ITEM AT110710 ELECTRICAL MANHOLE

This item shall be constructed in accordance to <u>ITEM 751-MANHOLES</u>, <u>CATCH BASINS</u>, <u>INLETS AND INSPECTION HOLES</u> of the Standard Specifications as modified by this special provision and detailed in the Construction Plans.

# 110-3.8 ITEM AR110901 CONCRETE DUCT REMOVAL

This item shall include all work necessary to remove and dispose of existing concrete encased duct banks as outlined in this special provision and detailed in the Construction Plans. Existing active cables are found inside the existing duct banks to be removed. The Contractor shall remove the concrete and ducts in a manner that will not damage the existing active cables. The Contractor shall protect the existing cables from damage during the removal of the concrete duct bank. If any cables are damaged during the removal of the concrete duct bank, all costs for repairing the damaged cables, including cable replacement and cable splices, shall be the responsibility of the Contractor. Replacement cables (if required) shall not be measured for payment and/or paid for. The Contractor shall furnish, place, and compact sand backfill in the trench formed by the removal of the concrete duct bank to the satisfaction of the Resident Engineer. All waste materials resulting from the removal of the existing concrete duct bank shall be disposed of by the Contractor at an approved location off of airport property.

# 110-3.9 ITEM AT110907 REMOVE ELECTRICAL MANHOLE

This item shall be construction in accordance to <u>SECTION 605-REMOVING OR FILLING EXISTING MANHOLES</u>, <u>CATCH BASINS AND INLETS</u> of the "Standard Specifications for Road and Bridge Construction" adopted by the IDOT as modified by this special provisions and detailed in the Construction Plans.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# METHOD OF MEASUREMENT

ADD the following to this Section:

110-4.3 The number of electrical manholes and remove electrical manholes to be paid for shall be the number of each size and type, as classified, counted in place, and accepted by the Resident Engineer.

The quantity of underground concrete duct bank removed to be paid for under these items shall be the number of lineal foot of duct and concrete duct bank removed, measured in place prior to removal, completed, and accepted by the Resident Engineer. Separate measurements shall not be made for the various types and sizes and number of ducts in each concrete duct bank.

If any existing cables are damaged during the removal process, the Contractor shall replace the damaged cables between manholes. The replacement cables <u>shall not</u> be measured for payment and/or paid for under any contract pay item. The Contractor shall be responsible for all costs associated with cable repair and replacement.

# **BASIS FOR PAYMENT**

ADD the following to this Section:

- 110-5.2 The accepted number of electrical manholes and removed electrical manholes will be paid for at the contract unit price per each, complete and in place or removed. This price shall be full compensation for furnishing all materials and for all preparation, excavating, cable protection, jumper cables, saw cutting, removals, disposal of waste, replacement cables (if required), cable splices (if required), compacted sand backfill, and placing of materials as may be required to complete these items as detailed on the plans, and for all labor, equipment, tools, and incidentals necessary to complete these items.
- 110-5.3 Payment will be made at the contract unit price per lineal foot for concrete duct bank removed completed and accepted. This price shall be full compensation for furnishing all materials and for all preparation, excavating, cable protection, jumper cables, saw cutting, removals, disposal of waste, replacement cables (if required), cable splices (if required), compacted sand backfill, and placing of materials as may be required to complete these items as detailed on the plans, and for all labor, equipment, tools, and incidentals necessary to complete these items.

Cables installed to replace damaged cables <u>shall not</u> be paid for under any contract pay item. The Contractor shall be responsible for all costs associated with repairing and/or replacing existing cables.

Payment will be made under:

ADD to this Section as follows:

ITEM AR110502 -- 2-WAY CONCRETE ENCASED DUCT -- per lineal foot.

ITEM AR110901 -- CONCRETE DUCT REMOVAL -- per lineal foot.

ITEM AS110502 -- 2-WAY CONCRETE ENCASED DUCT -- per lineal foot.

ITEM AT110501 -- 1-WAY CONCRETE ENCASED DUCT -- per lineal foot.

ITEM AT110502 -- 2-WAY CONCRETE ENCASED DUCT -- per lineal foot.

ITEM AT110710 -- ELECTRICAL MANHOLE -- per each.

ITEM AT110907 -- REMOVE ELECTRICAL MANHOLE -- per each.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# ITEM 125 - INSTALLATION OF AIRPORT LIGHTING SYSTEMS

# **DESCRIPTION**

# 125-1.2 ADD to this Section the following:

This item shall consist of base mounted MIRL units, base mounted HIRLQ units, taxi guidance signs, splice cans, remove guidance signs, replace guidance signs, relocate base mounted lights, replace guidance sign panels, and supply guidance sign panels as indicated on and at the locations shown on the Construction Plans in accordance with these special provisions. Also included in this item will be the testing of the installed, relocated, refurbished items and all other incidentals necessary to place and/or replace the lighting, and scan systems back into operation complete to the satisfaction of the Resident Engineer.

The existing equipment and materials scheduled to be removed, refurbished, and/or relocated shall be removed by the Contractor with care so that all materials considered suitable for future use by the Resident Engineer may be salvaged. Equipment and materials having salvage value shall be removed without damage and those having no salvage value shall be removed and disposed of by the Contractor in a suitable location off of airport property. The Contractor shall clean the salvageable materials and equipment to the satisfaction of the Resident Engineer. Any components damaged by the Contractor during removal, refurbished, and/or relocation shall be replaced or repaired by him at no additional cost with a similar unit (approved by the Resident Engineer) that is compatible with the remainder of the system. All salvageable equipment and materials removed and not reused shall remain the property of and be delivered to the Metropolitan Airport Authority. The Contractor shall deliver the salvaged items to a location designated by the Airport Maintenance Manager. All excavating required to remove existing equipment and materials shall be backfilled with compacted sand.

The Contractor shall field inspect the existing runway/taxiway lighting system, guidance signs, surface sensor system and scan system, prior to purchasing the proposed equipment and cables, to ensure the new equipment and cables are compatible to the existing system. Any noncompatible components furnished by the Contractor shall be replaced by him at no additional costs with a similar unit (approved by the Resident Engineer) that is compatible with the remainder of the system.

All new equipment supplied by the Contractor shall appear on the current approved Equipment List found in AC 150/5345-53A and -2 (Airport Lighting Equipment Certification Program and/or Airport Electronic Bulletin Board Number 14).

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **EQUIPMENT AND MATERIALS**

# 125-2.1 GENERAL

ADD the following to this Section:

(d) The existing L-862 high intensity runway edge/threshold lights on Runway 9-27 and Runway 13-31 are supplied with quartz light fixtures. All new lights shall have an overall height of 20 inches.

Existing light fixtures:

A. Runway Edge Lights:

```
R9-27 and R13-31 = L-862/120 watt, quartz. R5-23 and R10-28 = L-861/30W.
```

B. Runway Threshold Lights:

```
R9-27 and R13-31 = L-862/200 watt, quartz. R5-23 and R10-28 = L-861E/45W.
```

C. Taxiway edge lights = L-861T/30 watt, 6.6 AMP.

Existing isolation transformers:

A. Runway Edge Lights:

```
R9-27 and R13-31 = L-830-4, 100 watt.
R5-23 and R10-28 = L-830-1, 30W/45W.
```

B. Runway Threshold Lights:

```
R9-27 and R13-31 = L-836-6, 200 watt.
R5-23 and R10-28 = L-830-1, 30W/45W.
```

- C. Taxiway edge lights = L-830-1, 30/45 watt, 6.6/6.6 AMP.
- (e) It is the desire of the Owner to have interchangeable lighting equipment throughout the airport, therefore the Metropolitan Airport Authority reserves the right to select and/or approve electrical equipment and materials to be supplied for this project.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following paragraphs to this Section:

#### 125-2.14 ANTI-SEIZE COMPOUND

Prior to reinstallling the existing light fixtures, the Contractor will apply an oxide inhibiting, anti-seizing compound to all screws, nuts, breakable coupling and all places where metal comes into contact with metal. The anti-seize compound will be as manufactured by I.T.T. brand "Contax" or an approved equal.

# 125-2.15 STAINLESS STEEL BOLTS

All base plate and stake mounting bolts shall be stainless steel. The Contractor shall supply and install new stainless steel bolts, washers, and nuts as required.

#### 125-2.16 SIGNS

Signs shall be double faced; Type L-858Y, L-858R, L-858L, or L-858B as indicated on the Construction Plans; and in accordance with the requirements of the latest revision of FAA Advisory Circular 15/5345-44, Specifications for Taxiway and Runway Signs.

Each sign shall be supplied with sign panels as indicated in the Construction Plans. New sign panels shall be supplied and installed on all signs scheduled to be replaced. The Contractor may reuse existing sign panels as indicated on the Construction Plans, if the panels are in acceptable condition, as determined by the Resident Engineer.

Per FAA AC 150/5345-44G, Item 3.2.5.9e.; all replacement sign panels must be supplied by the original equipment manufacturer (OEM) or fabricated using a process approved by the OEM unless no longer in business or manufacturing the sign.

Signs shall be compatible in all respects with each other and with signs currently in place at the airport. Signs shall be Lumacurve or approved equal. Each sign installation shall include a sign splice can with it. The cost of the sign splice can shall be included in the sign contract unit price.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# **CONSTRUCTION METHODS**

# 125-3.1 GENERAL

ADD the following to this Section:

Upon completion of the signage work, all frames, legend panels, and associated parts shall be sealed watertight with a durable silicone caulking compound approved by the Resident Engineer.

ADD the following to this Section:

# 125-3.4 IDENTIFICATION NUMBERS

Per instructions from the MAA, identification numbers will not be required on this project.

125-3.5 ITEMS: AR125443 TAXI GUIDANCE SIGN, 3 CHARACTER; AR125444 TAXI GUIDANCE SIGN, 4 CHARACTER; AR125446 TAXI GUIDANCE SIGN 6 CHARACTER; AND AS125448 TAXI GUIDANCE SIGN 8 CHARACTER

These items shall include all work necessary to furnish and install new taxiway guidance signs as detailed in the Construction Plans. Proposed sign bases for proposed signs being installed adjacent to another existing or proposed signs shall be continuous with the base of the adjacent sign. Separate payments for individual items required to construct the sign shall not be counted or paid for. The cost to furnish and install all items shown on the sign detail that is found in the Construction Plans (including splice cans) shall be included in the contract unit price.

125-3.6 ITEMS: AS125510 MIRL, BASE MOUNTED AND AT125510 MIRL, BASE MOUNTED

These items shall include all work necessary to furnish and install a new base mounted L-861 MIRL unit at the proposed locations as indicated on and detailed in the Construction Plans.

# 125-3.7 ITEM AR125520 HIRLQ, BASE MOUNTED

This item shall include all work necessary to furnish and install new base mounted L-862 HIRLQ units at the proposed locations as indicated on and detailed in the Construction Plans.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

#### 125-3.8 ITEM AR125565 SPLICE CAN

This item or work shall consist of furnishing and installing electrical splice cans with lids complete, in accordance with this specification and as detailed on the Construction Plans. The concrete backfill around the can shall conform to Item 610 Structural Concrete, but will not be measured for payment or paid for separately. A solid metal lid shall be provided (L-867, size B, 12" steel cover). Splice cans installed or relocated as part of installing or relocating taxiway guidance signs shall not be counted for payment under this item, but shall be included in the unit price costs for sign installation or relocation.

# 125-3.9 AR125902 REMOVE BASE MOUNTED LIGHT/ AR125903 REMOVE IN-PAVEMENT LIGHT/

These items shall include all work necessary to remove existing MITL and HIRLQ base mounted and/or in-pavement edge lights and splice cans as detailed in the Construction Plans. The work to be included in these items includes, but is not limited to, disconnecting light fixtures, excavating base can, disconnecting unit duct, removing base can, removing PC concrete base pad (in-pavement lights only), transporting lighting equipment, backfilling excavation with compacted sand, disposal of waste materials, supplying and replacing damaged equipment, and all other incidentals necessary to remove the existing equipment and return the remaining lighting systems back into operation, completed to the satisfaction of the Resident Engineer. The Contractor shall either reuse the equipment removed at a new location or deliver the salvaged items to a location designated by the airport maintenance manager.

# 125-3.10 AR125904 REMOVE TAXI GUIDANCE SIGN

This item shall include all work necessary to remove existing taxi guidance signs as detailed in the Construction Plans. The work to be included in this item includes, but is not limited to, disconnecting existing cables, transformers, and signs, removing existing signs, covers, and mounting plates, excavating transformer can and light base; disconnecting unit duct, removing transformer can and sign base, removing and disposal of concrete pad not being reused, backfilling excavation with compacted sand, seed area, transporting transformer can and sign equipment, disposal of waste materials, and all other incidentals necessary to remove the existing sign equipment and return the remaining lighting system back into operation, completed to the satisfaction of the Resident Engineer.

The Contractor shall deliver the salvaged items to a location designated by the airport maintenance manager.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

# 125-3.11 ITEM AR125942 ADJUST BASE MOUNTED LIGHT

After the existing Taxiway pavements have been reconstructed, the Contractor shall vertically adjust the existing Taxiway edge lights as indicated on the Construction Plans.

This item shall also include vertical adjustments to existing splice cans. Splice cans requiring vertical adjustments shall be modified in accordance to this Special Provision and the edge light vertical adjustment details found in the Construction Plans. For payment purposes, splice can vertical adjustments will be counted as base mounted light vertical adjustments. Splice cans to be vertically adjusted as part of a taxiway guidance sign adjustment shall not be counted for payment under this item, but shall be included in the unit price costs for guidance sign adjustment.

The work to be included in this item includes, but is not limited to, excavating, disconnecting cables and unit duct, removing base can and equipment, installation and compaction of sand leveling cushion pad, setting base, reconnecting cables and unit duct, reinstalling equipment, concrete backfill, backfilling with compacted sand, testing, supplying and replacing damaged equipment, adjustment rings, and all other incidentals necessary to adjust the existing edge lights/splice cans and return the system back into operation, complete to the satisfaction of the Resident Engineer. Separate payments for these items shall not be made.

The cost to complete these items shall be included in the contract unit prices. The Contractor shall replace any item damaged during the adjustment of the edge lights/splice cans with a similar unit (approved by the Resident Engineer). The Contractor shall ascertain that the equipment and cables furnished by him are compatible in all respects with the existing equipment and cables. Any noncompatible components shall be replaced by the Contractor at no additional costs with a similar compatible unit.

# 125-3.12 ITEM AR125944 ADJUST TAXI GUIDANCE SIGN

After the existing taxiway pavements have been reconstructed, the Contractor shall vertically adjust the existing taxiway guidance signs as indicated on the construction plans.

This item shall include all work items that are necessary to vertically adjust the existing guidance signs as detailed in the construction plans. The work to be included in this item includes, but is not limited to, disconnecting existing unit duct, cables, transformers, and signs; excavating; removing transformer can and sign base; removing and disposal of concrete pads not being reused; installation and compaction of leveling sand; reset transformer can and sign base; elevating and reconnecting existing unit duct/cable and/or installing new unit duct/cable; reinstallation and reconnection of

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

equipment; backfilling with compacted sand; testing, supplying and replacing damaged equipment; resealing adjusted signs; and all other incidentals necessary to vertically adjust the existing equipment and return the system back into operation, complete to the satisfaction of the Engineer and the MAA. Separate payment for these shall not be made.

The cost to complete these items shall be included in the contract unit prices. The Contractor shall replace any item damaged during the vertical adjustment of the guidance sign with a similar unit (approved by the Resident Engineer). The Contractor shall ascertain that the equipment and cables furnished by him are compatible in all respects with the existing equipment and cables. Any noncompatible components shall be replaced by the Contractor at no additional costs with a similar compatible unit.

Separate payments shall not be made for the different sizes of signs. Vertical adjustment of existing 1,2,3, and/or 4 module signs shall be paid for at the same single contract unit price.

The Contractor may reuse the existing equipment as much as possible. Contractor shall furnish and install items which can not be reused. Vertical adjustment sign shall be resealed watertight with a durable silicone caulking compound approved by the Engineer.

# 125-3.13 ITEM AR125962 RELOCATE BASE MOUNTED LIGHT

This item shall include all work items that are necessary to remove and reinstall existing base mounted edge lights as detailed in the construction plans. The work to be included in this item includes, but is not limited to, disconnecting light fixtures, excavating base can, disconnecting unit duct, removing base can, transporting base can, relocating short sections of existing edge light cable in unit duct, backfilling excavation with compacted sand, excavating new can location, installation and compaction of sand leveling cushion, reconnecting unit duct, concrete backfill, backfilling with compacted sand, reinstalling equipment, testing, supplying and replacing damaged equipment, and all other incidentals necessary to relocate the existing equipment and return the system back into operation, completed to the satisfaction of the Resident Engineer. Separate payments for these items shall not be made.

The cost to complete these items shall be included in the contract unit prices. The Contractor shall replace any item damaged during the relocation of the edge lights with a similar unit (approved by the Resident Engineer). The Contractor shall ascertain that the equipment and cables furnished by him are compatible in all respects with the existing equipment and cables. Any noncompatible components shall be replaced by the Contractor at no additional costs with a similar compatible unit.

# 125-3.14 ITEM AR801605 REPLACE TAXI GUIDANCE SIGN PANEL

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

This item shall include all work items that are necessary to remove existing and supply/install new taxiway guidance sign panels as directed by the Resident Engineer. The work to be included in this item includes, but is not limited to, supplying new lumacurve sign panels, removing existing sign panels, disposal of removed sign panels, installing new lumacurve sign panels, resealing sign, and all other incidentals necessary to replace the existing sign panels and return the system back into operation, completed to the satisfaction of the Resident Engineer and the MAA.

The costs to complete the above items shall be included in the contract unit price. The Contractor shall replace any item damaged during the sign panel replacement with a similar unit (approved by the Engineer). The Contractor shall ascertain that the equipment furnished by him is compatible in all respects with the existing equipment. Any noncompatible components shall be replaced by the Contractor at no additional costs with a similar compatible unit.

#### 125-3.15 ITEM AT801614 SUPPLY TAXI GUIDANCE SIGN PANEL

This item shall include all work items that are necessary to supply and deliver new taxiway guidance sign panels to be installed by the MAA in existing signs as directed by the Resident Engineer. The work to be included in this item includes, but is not limited to, supplying and delivering new lumacurve sign panels to the MAA maintenance building at the airport. The proposed sign panel legends shall be identified in the field at the time of construction.

# 125-3.16 ITEM AR801628 RELOCATE TAXI GUIDANCE SIGN PANEL

This item shall include all work items that are necessary to relocate existing taxiway guidance sign panels between existing signs as directed by the Resident Engineer. The work to be included in this item includes, but is not limited to, removing sign panels, transporting sing panels, re-sealing signs, and all other incidentals necessary to relocate existing sign panels and return the system back into operation, completed to the satisfaction of the Resident Engineer and the MAA.

The costs to complete the above items shall be included in the contract unit price. The Contractor shall replace any item damaged during the sign panel relocation with a similar unit (approved by the Engineer). The Contractor shall ascertain that the equipment furnished by him is compatible in all respects with the existing equipment. Any noncompatible components shall be replaced by the Contractor at no additional costs with a similar compatible unit.

# METHOD OF MEASUREMENT

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ADD the following to this Section:

125-4.2 The quantity of new light units, existing light units, splice cans, inpavement lights, and guidance signs to be installed, removed, adjusted and/or relocated, and existing taxi guidance sign panels to be replaced to be paid for under this item shall be the number, counted in place as indicated in this special provision, of each type and style installed, removed, adjusted, relocated and/or replaced as complete and accepted by the Resident Engineer.

# **BASIS OF PAYMENT**

125-5.1 REVISE the first sentence of this Section to read as follows:

Payment will be made at the contract unit price per each complete light, splice can, guidance sign, and/or guidance sign panel installed in place, removed, adjusted, relocated, and/or replaced by the Contractor and accepted by the Resident Engineer.

Payment will be made under:

ITEM AR125443 -- TAXI GUIDANCE SIGN, 3 CHARACTER -- per each.

ITEM AR125444 -- TAXI GUIDANCE SIGN, 4 CHARACTER -- per each.

ITEM AR125446 -- TAXI GUIDANCE SIGN, 6 CHARACTER -- per each.

ITEM AR125510 -- MIRL, BASE MOUNTED -- per each.

ITEM AR125520 -- HIRLQ, BASE MOUNTED -- per each.

ITEM AR125565 -- SPLICE CAN -- per each.

ITEM AR125902 -- REMOVE BASE MOUNTED LIGHT -- per each.

ITEM AR125903 -- REMOVE INPAVEMENT LIGHT -- per each.

ITEM AR125904 -- REMOVE TAXI GUIDANCE SIGN -- per each.

ITEM AR125942 -- ADJUST BASE MOUNTED LIGHT -- per each.

ITEM AR125944 -- ADJUST TAXI GUIDANCE SIGN -- per each.

ITEM AR125962 -- RELOCATE BASE MOUNTED LIGHT -- per each.

ILL. PRJT. No. MLI-3854 A.I.P. PRJT. No. 3-17-0068-XX 15A QU008

ITEM AR801605 -- REPLACE TAXI GUIDANCE SIGN PANEL -- per each.


ITEM AR801628 -- RELOCATE TAXI GUIDANCE SIGN PANEL -- per each.


ITEM AS125448 -- TAXI GUIDANCE SIGN, 8 CHARACTER -- per each.


ITEM AS125510 -- MIRL, BASE MOUNTED -- per each.


ITEM AT125510 -- MIRL, BASE MOUNTED -- per each.


ITEM AT801614 -- SUPPLY TAXI GUIDANCE SIGN PANEL -- per each.























# SPECIAL PROVISION FOR PROTECTION OF CABLES, CONTROLS, NAVAIDS AND WEATHER BUREAU FACILITIES

The Contractor is hereby informed that there are installed on the airport FAA MAVAIDS; including, without limitation, ASR, UHF and VHF Receivers and Transmitters; U.S. Weather Bureau facilities; electric cables and control relating to such NAVAIDS and facilities, and other electric power cables serving other facilities. Such NAVAIDS, Weather Bureau and other facilities and electric cables must be fully protected during the entire construction time. Work under this contract can be accomplished in the vicinity of these facilities and cables only at approved periods of time. Approval is subject to withdrawal at any time because of changes in the weather, emergency conditions on the existing airfield areas, anticipation of emergency conditions, and for any other reason determined by the Engineers acting under the orders and instructions of the airport management and/or the designated FAA representative. Any instructions to this Contractor to clear any given area, at any time, by the Engineers, the airport management, or the FAA control tower (by radio or other means) shall be immediately executed. Construction work will be commenced in the cleared area only when additional instructions are issued by the proper authorities.

The Contractor shall be responsible for contacting the appropriate agencies for locations. Power and control cables leading to and from any FAA NAVAIDS, Weather Bureau, and other facilities will then be marked in the field by those agencies for the information of the Contractor, before any work in their general vicinity is started. Thereafter, through the entire time of this construction they shall be protected from any possible damage, including crossing with unauthorized equipment, etc.

These special provisions intend to make perfectly clear the need for protection of FAA NAVAIDS, Weather Bureau, and other facilities and cables by this Contractor at all times.

The Contractor shall immediately repair, with identical material by skilled workmen, any underground cables serving FAA NAVAIDS, Weather Bureau and other airport facilities, which are damaged by his workmen, equipment, or work. Prior approval of the FAA must be obtained for the materials, workmen, time of day or night, method of repairs, and for any temporary or permanent repairs the Contractor proposes to make to any FAA NAVAIDS and facilities damaged by the Contractor. Prior approval of the Engineer or of the representative designated by the airport management must be obtained for the materials, workmen; time of day or night, and for the method of repairs for any temporary or permanent repairs the Contractor proposes to make to any other airport facilities and cables damaged by this Contractor. COSTS INCIDENTAL TO 108. CONTRACT UNIT PRICES.