

SUMMARY OF QUANTITIES

SEQ NO.	DESCRIPTION	UNIT	BASE BID			AA1			AA2			AA3		
			ITEM NO	ESTIMATED QUANTITY	RECORD QUANTITY	WEST RIAT ROAD			TXY E			TXY B3		
1	1/C #8 5 KV UG CABLE	LF	AR108108	7,065.00					AT108108	767.00		AU108108	590.00	
2	1/C #8 5 KV UG CABLE IN UD	LF	AR108158	1,502.00					AT108158	1,570.00		AU108158	635.00	
3	2" STEEL DUCT, DIRECT BURY	LF	AR110212	6,729.00					AT110212	730.00		AU110212	562.00	
4	SPLIT DUCT	LF	AR110550	350.00					AT110550	160.00				
5	EXTEND 2-WAY DUCT	LF										AU110552	120.00	
6	MITL-BASE MOUNTED	EACH	AR125415	84.00					AT125415	12.00				
7	TAXI GUIDANCE SIGN, 1 CHARACTER	EACH	AR125441	1.00										
8	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	AR125442	1.00					AT125442	2.00				
9	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	AR125445	1.00					AT125445	1.00				
10	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	AR125446	2.00										
11	TAXI GUIDANCE SIGN, 8 CHARACTER	EACH	AR125448	2.00										
12	REMOVE BASE MOUNTED LIGHT	EACH	AR125902	78.00					AT125902	15.00				
13	REMOVE TAXI GUIDANCE SIGN	EACH	AR125904	6.00					AT125904	3.00				
14	REPLACE BASE MOUNTED LIGHT	EACH	AR125922	2.00					AT125922	4.00				
15	ENGINEER'S FIELD OFFICE	LS	AR150510	1.00										
16	FIELD LABORATORY	LS	AR150515	1.00										
17	MOBILIZATION	LS	AR150520	1.00										
18	HAUL ROUTE	LS	AR150540	1.00										
19	UNCLASSIFIED EXCAVATION	CY	AR152410	1,608.00		AS152410	1,966.00		AT152410	210.00		AU152410	1,006.00	
20	SOIL STABILIZATION FABRIC	SY	AR152540	6,372.00		AS152540	8,520.00		AT152540	825.00		AU152540	5,113.00	
21	SILT FENCE	LF	AR156510	1,600.00		AS156510								
22	BALES	EACH	AR156512	72.00		AS156512								
23	RIPRAP	SY				AS156540	285.00							
24	POROUS GRANULAR EMBANKMENT	CY	AR208515	80.00		AS208515	100.00		AT208515	11.00		AU208515	50.00	
25	CRUSHED AGG. BASE COURSE - 8"	SY				AS209608	8,520.00							
26	CRUSHED AGG. BASE COURSE - 11"	SY	AR209611	21,465.00					AT209611	2,850.00		AU209611	3,415.00	
27	BITUMINOUS SURFACE COURSE	TON	AR401610	9,090.00		AS401610	2,130.00		AT401610	1,450.00		AU401610	2,035.00	
28	BITUMINOUS SURFACE TEST SECTION	EACH	AR401630	1.00										
29	BITUMINOUS PAVEMENT MILLING	SY	AR401650	39,767.00					AT401650	6,493.00				
30	BUTT JOINT CONSTRUCTION	SY	AR401655	800.00					AT401655	255.00		AU401655	248.00	
31	15" PCC PAVEMENT	SY	AR501515	23,907.00										
32	PCC TEST BATCH	EACH	AR501530	1.00										
33	BITUMINOUS PRIME COAT	GAL	AR602510	6,213.00		AS602510	2,530.00		AT602510	838.00		AU602510	1,475.00	
34	BITUMINOUS TACK COAT	GAL	AR603510	3,950.00		AS603510	965.00		AT603510	1,095.00		AU603510	725.00	
35	PAVEMENT MARKING - WATERBORNE	SF	AR620520	19,680.00		AS620520	732.00		AT620520	3,540.00		AU620520	1,280.00	
36	PAVEMENT MARKING - BLACK BORDER	SF	AR620525	18,732.00					AT620525	3,160.00		AU620525	1,925.00	
37	18" CMP	LF				AS701218	102.00							
38	METAL END SECTION 18"	EACH				AS752218	6.00							
39	L-804 RGL ELEVATED, BASE MOUNTED	EACH	AR800816	2.00					AT800816	2.00				
40	AGGREGATE DRAINAGE DITCH	LF	AR800817	200.00										
41	ADJUST MONITORING WELL	EACH	AR800863	2.00										
42	SOIL GUARD	SY	AR800868	25,562.00		AS800868	11,500.00		AT800868	2,832.00		AU800868	3,565.00	
43	SEEDING	ACRE	AR901510	5.30		AS901510	2.40		AT901510	0.60		AU901510	0.75	
44	TOPSOILING (FROM OFF SITE)	CY	AR905520	1,023.00		AS905520	100.00		AT905520	100.00		AU905520	100.00	
45	GUARD RAIL	LF	AR910400	30.00										

RO016



**Chicago Rockford
International
Airport**



**Rockford, Illinois
Greater Rockford
Airport Authority**

**AIP: 3-17-0088-XX
RFD-3862**

**Rehab. Txy B South
(Phase 1)**

Revisions

Date	Description

0 1
THIS BAR IS EQUAL TO 1"
AT FULL SCALE (17 X 11)

DESIGN BY: CMT-RFD
DRAWN BY: CMT-RFD
CHECKED BY: CMT-RFD
APPROVED BY: JGP
DATE: 2-27-2009
JOB No: 06258-04-00

**SUMMARY OF
QUANTITIES
(QTY1)**

2

SHEETS 10-12, 21-24

SHEETS 8-9, 25-34, 46, 52

SHEETS 25-30, 46, 52

SHEETS 13-15, 41-45, 47-51

**SUMMARY OF QUANTITIES
(QTY1)**