



RECONSTRUCTION OF RUNWAY END 17

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	2,257	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	56	
AR125410	MITL - STAKE MOUNTED	EACH	13	
AR125415	MITL - BASE MOUNTED	EACH	2	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	1	
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EACH	1	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	6	
AR125545	MI THRESHOLD LIGHT BASE MTD	EACH	2	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	31	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	2	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	2	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	1,312	
AR156511	DITCH CHECK	EACH	2	
AR156520	INLET PROTECTION	EACH	2	
AR156530	TEMPORARY SEEDING	ACRE	3.9	
AR208540	OVERSIZED AGGREGATE	TON	831	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	791	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	3,351	
AR501510	10" PCC PAVEMENT	S.Y.	2,160	
AR501900	REMOVE PCC PAVEMENT	S.Y.	3,129	
AR701512	12" RCP, CLASS IV	L.F.	243	
AR701900	REMOVE PIPE	L.F.	398	
AR705410	POROUS BACKFILL	C.Y.	21	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	863	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	4	
AR705900	REMOVE UNDERDRAIN	L.F.	1,389	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	3	
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	2	
AR751411	INLET-TYPE A	EACH	2	
AR751540	MANHOLE 4'	EACH	2	
AR751900	REMOVE INLET	EACH	1	
AR751903	REMOVE MANHOLE	EACH	2	
AR901510	SEEDING	ACRE	3.9	
AR904510	SODDING	S.Y.	261	
AR908510	MULCHING	ACRE	3.8	

ST. LOUIS REGIONAL AIRPORT  EAST ALTON, ILLINOIS A.I.P. PROJ.: 3-17-0002-842	IGI Project No. B3706RWTD.0800 Filename R-003FLP.DWG Scale N/A Date 02/07/08	LAYOUT MDR 02/07/08 DRAWN MDR 02/07/08 REVIEWED CAH 07/11/08
	 Hanson Professional Services Inc. 1000 S. Main Street Springfield, IL 62703-2886 Offices Nationwide	RUNWAY SAFETY AREA IMPROVEMENTS SUMMARY OF QUANTITIES FOR RUNWAY END 17