

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CODE NO	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	3165	542A0229	PIPE CULVERT, CLASS A, TYPE 1 24"	FOOT	125
20400800	FURNISHED EXCAVATION	CU YD	5715	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3
20900150 21000310	TRENCH BACKFILL GRANULAR EMBANKMENT, SPECIAL	CU YD CU YD	52.9 270	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1213	60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5400	60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M4.06	FOOT	84
25000312	SEEDING, CLASS 4A	ACRE	4.50	60608582	COMBINATION CONCRETE CURB AND GUTTER, TYPE M4.24	FOOT	44
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405	* 60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	224
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405	61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	1250
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405	61100605	MISCELLANEOUS CONCRETE	CU YD	1.7
25000700	AGRICULTURAL GROUND LIMESTONE	TON	9.0	61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	300
25100115	MULCH, METHOD 2	ACRE	4.50	61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	300
25100630	EROSION CONTROL BLANKET	SQ YD	90	61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	300
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450	61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	300
28000305	TEMPORARY DITCH CHECKS	FOOT	410	61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	1580	61139900	STORM SEWERS (SPECIAL), 6"	FOOT	150
28000500	INLET AND PIPE PROTECTION	EACH	6	61140000	STORM SEWERS (SPECIAL), 8"	FOOT	150
28100205	STONE RIPRAP, CLASS A3	TON	12	61140100	STORM SEWERS (SPECIAL), 10"	FOOT	150
28200200	FILTER FABRIC	SQ YD	25	61140200	STORM SEWERS (SPECIAL), 12"	FOOT	150
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	9336	Δ 63200310	GUARDRAIL REMOVAL	FOOT	25
30201500	LIME	TON	233.4	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1068	67100100	MOBILIZATION	L SUM	1
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	92	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
* 40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	4686	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1852	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
* 40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	466	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	179	72000100	SIGN PANEL - TYPE 1	SQ FT	74
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	6065	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	196
42001300	PROTECTIVE COAT	SQ YD	6134	Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	26
42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SQ FT	25283	Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2450
42400800	DETECTABLE WARNINGS	SQ FT	78	Δ 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	132
48203025	HOT-MIX ASPHALT SHOULDERS, 7"	SQ YD	544	Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	61
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	2951	Δ 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	60
542A0223	PIPE CULVERT, CLASS A, TYPE 1 18"	FOOT	103	Δ 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	12427

CODE NO	ITEM	UNIT	TOTAL QUANTITY
Δ 78009005	MODIFIED URETHANE PAVEMENT MARKING - LINE 5"	FOOT	361
Δ 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	844
Δ 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	334
Δ 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	48
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	29
* X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	1
* X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1

* "SEE SPECIAL PROVISIONS, HIGHWAY STANDARDS, GENERAL NOTES, AND/OR DETAILS IN PLANS" Δ SPECIALTY ITEMS



© Copyright Hanson Professional Services Inc. 2015

LAYOUT	RSJ	03/30/11
DRAWN	RSJ	02/22/11
REVIEWED	MH	

FILE NAME =	C:\601-W_50.dgn
USER NAME =	heyan00951
DESIGNED -	
DRAWN -	
CHECKED -	
DATE -	

REVISED	4-9-15
REVISED	
REVISED	
REVISED	

PLOT SCALE =	1.0000' / 1" =
PLOT DATE =	1/7/2015

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES PROPOSED OLYMPIAN DRIVE	
SCALE: NTS	SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
813	11-00290-00-PV	CHAMPAIGN	26	3
			CONTRACT NO.	91469
ILLINOIS FED. AID PROJECT				