



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 8, 2020

SUBJECT: FAP Route 330 (US 12)
Project NHPP-TT9T(943)
Section 2019-104-RS&SW
Cook County
Contract No. 62J82
Item No. 11, April 24, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 114 to the Special Provisions
4. Revised sheets.4 & 5 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS -JOBSITE SAMPLING (BDE)	82
MOBILIZATION (BDE)	87
PORTLAND CEMENT CONCRETE (BDE)	88
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	88
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	100
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	101
TEMPORARY PAVEMENT MARKING (BDE)	101
TRAFFIC CONTROL DEVICES - CONES (BDE)	104
TRAINING SPECIAL PROVISIONS (BDE)	104
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	107
WARM MIX ASPHALT (BDE)	109
WEEKLY DBE TRUCKING REPORTS (BDE)	111
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	112
REBUILD EXISTING HANDHOLE, SPECIAL	114
REMOVE AND REINSTALL BRICK PAVER	114

Revised 4/8/2020

REBUILD EXISTING HANDHOLE, SPECIAL

This item shall consist of rebuilding and bringing to grade a double handhole at a location shown on the plans or as directed by the Engineer. The work shall consist of removing the handhole frame and cover and the walls of the handhole to a depth of eight (8) inches below the finished grade.

Upon completion of the above work, four (4) holes, four (4) inches in depth and one half (1/2) inch in diameter, shall be drilled into the remaining concrete; one hole centered on each of the four handhole walls. Four (4) #3 steel dowels, eight (8) inches in length, shall be furnished and shall be installed in the drilled holes with a masonry epoxy.

All concrete debris shall be disposed of outside the right-of-way.

The area adjacent to each side of the handhole shall be excavated to allow forming. All steel hooks, handhole frame, cover, and concrete shall be provided to construct a rebuilt handhole according to applicable portions of Section 814 of the Standard Specification and as modified in 814.01TS HANDHOLES Special Provision. The existing frame and cover shall be replaced if it was damaged during removal or as determined by the Engineer.

Basis of Payment.

This work shall be paid for at the contract unit price each for REBUILD EXISTING HANDHOLE, SPECIAL which price shall be payment in full for all labor, materials, and equipment necessary to complete the work described above and as indicated on the drawings.

REMOVE AND REINSTALL BRICK PAVER

This work shall include the removal, reinstallation, and disposal of unnecessary existing brick paver sidewalk at locations impacted by the installation of new sidewalk curb ramps in accordance with the applicable portions of Section 424 of the Standard Specifications and as directed by the Engineer. Remove and Reinstall Brick Paver Sidewalk shall include the complete removal and storage of the existing pavers, reinstallation of brick pavers, leveling and jointing sand, and compacted aggregate base. Leveling sand shall be sound, sharp, washed natural sand or crushed stone complying with gradation requirements of ASTM C33 for fine aggregate. Sand for paver joints shall be fine, sharp, washed, natural sand or crushed stone with 100 percent passing No.16 sieve and no more than 10 percent passing No. 200 sieve. Bricks no longer required due to a change in material identified in the plans or installation of detectable warning strips will be the responsibility of the contractor and disposed of off-site.

Basis of Payment: The work to remove, reinstall and disposal of the existing brick paver sidewalk to the elevations as determined by the Engineer shall be paid for at the contract unit price per square feet for REMOVE AND REINSTALL BRICK PAVER which price shall include all necessary labor, material and equipment necessary to complete the work. Earth Excavation shall be paid for separately.

Added 4/8/2020