



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 15, 2020

SUBJECT: FAP Route 327 (US 50)
Project NHPP-9E2E(410)
Section 14-14HB-2-BP-1
Clinton County
Contract No. 76N46
Item No. 90, April 24, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 5 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

The cones as shown on the traffic control detail in the plans shall remain until the Bridge Cleaning & Painting has been completed. During the bridge cleaning, painting, median & median island removal and patching, pavement marking operations, the traffic control and protection special detail shall govern.

Any barricades and barrels necessary to facilitate the closure of lanes of Walnut Street and adjacent roadways shall be included in the cost of Traffic Control and Protection, Special.

This work shall be paid for at the contract unit bid price per **each** for TRAFFIC CONTROL AND PROTECTION, SPECIAL.

STATUS OF UTILITIES TO BE ADJUSTED

NO UTILITIES TO BE ADJUSTED

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Sections 102, 103, and Articles 105.07 and 107.20 of the Standard Specifications for Road and Bridge Construction shall apply.

If any utility adjustment or removal has not been completed when required by the Contractor's operation, the Contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's operations were affected.

CLEANING AND PAINTING EXISTING STEEL STRUCTURES

Effective: October 2, 2001

Revised: April 22, 2016

Description. This work shall consist of the preparation of all designated metal surfaces by the method(s) specified on the plans. This work also includes the painting of those designated surfaces with the paint system(s) specified on the plans. The Contractor shall furnish all materials, equipment, labor, and other essentials necessary to accomplish this work and all other work described herein and as directed by the Engineer.

Materials. All materials to be used on an individual structure shall be produced by the same manufacturer.

The Bureau of Materials and Physical Research has established a list of all products that have met preliminary requirements. Each batch of material, except for the penetrating sealer, shall be tested and assigned a MISTIC approval number before use. The specified colors shall be produced in the coating manufacturer's facility. Tinting of the coating after it leaves the manufacturer's facility is not allowed.

The paint materials shall meet the following requirements of the Standard Specification and as noted below:

<u>Item</u>	<u>Article</u>	
(a) Waterborne Acrylic	1008.04	
(b) Aluminum Epoxy Mastic	1008.03	
(c) Organic Zinc Rich Primer	1008.05	Revised April 15,2020