

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	0059	
			WINNEBAGO COUNTY	TOTAL QUANTITY
40600990	TEMPORARY RAMP	SQ YD	25	25
40604050	HOT- MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	120	120
42001300	PROTECTIVE COAT	SQ YD	720	720
X50300250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	432	432
67100100	MOBILIZATION	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	625	625
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	2
Z0012130	BRIDGE DECK SCARIFICATION, 3/4"	SQ YD	720	720
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY, 2 1/2"	SQ YD	720	720
Z0018051	DRAINAGE SCUPPERS TO BE ADJUSTED	EACH	1	1
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	648	648
Z0041895	POLYMER CONCRETE	CU FT	3.4	3.4

 MODEL: Default
 FILE: MainE_Planroom.dwg
 PROJECT: P:\Projects\Operations\Bridges_Section\Winnebago\101-0186647\101-CADD\DD2-shr-cover.dgn

USER NAME = dossdd	DESIGNED - _____	REVISED - _____
DRAWN - _____	CHECKED - _____	REVISED - _____
PLOT SCALE = 100.0000' / in.	DATE - _____	REVISED - _____
PLOT DATE = Jan-15-2020 10:35:09 AM		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**
SUMMARY OF QUANTITIES

SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(17R-1BR)BDR	WINNEBAGO	17	3
			CONTRACT NO. 64P10	
ILLINOIS FED. AID PROJECT				