

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2706	2006-020 TS	LAKE	29	2
FED. ROAD DIST. NO. 1		ILLINOIS	CONTRACT NO. 60B48	
D-91-351-06				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		IL.43 @ DEERFIELD ROAD.	IL.43 @ ELDER LN./ HAZEL AVE.	IL.43 @ GREENWOOD	IL.43 @ NORTH AVE.	IL.43 @ OFFICE PLAZA ENT.	IL.43 @ IL.22	INTERCONNECT
				Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	0.25	0.25	0.25	0.25	0.25	0.25	0.50
67100100	MOBILIZATION	L SUM	1	0.14	0.14	0.14	0.14	0.14	0.14	0.16
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.14	0.14	0.14	0.14	0.14	0.14	0.16
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.14	0.14	0.14	0.14	0.14	0.14	0.16
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	4471							4471
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	657							657
81400100	HANDHOLE	EACH	7							7
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4471							4471
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6	1	1	1	1	1	1	
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	4		1	1	1	1		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5		1	1	1	1	1	
88500100	INDUCTIVE LOOP DETECTOR	EACH	31		4	6	4	5	12	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.6 2C	FOOT	105		40	25		10	30	
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14FT.	EACH	6		3	1		2		
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16FT.	EACH	5		2	2		1		
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18FT.	EACH	7		2	1		1	3	
87900200	DRILL EXISTING HANDHOLE	EACH	5					2	3	
88024120	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1						1	
88024310	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1						1	
88024320	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3		2				1	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	10		2	1	3	3	1	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	15	2	4		2	3	4	
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5	1			1	1	2	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	11	5		1	1	1	3	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5		2	1	1	1		
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	4			4				
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	6	2	2	1			1	
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	51.4					51.4	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. 43 (WAUKEGAN RD.) FROM
IL. 22 (HALFDAY RD.) TO DEERFIELD RD.

PLOT DATE: 2/1/2008

2/1/2008
c:\projects\traffic\0600\01\43deer\0122.dgn

13:35:30 02/01/2008