

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2706	2006-020 TS	LAKE	29	3
FED. ROAD DIST. NO. 1	ILLINOIS	CONTRACT NO. 60B48		

D-91-351-06

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 80% F.B.D. 20% STATE	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		IL.43 @ DEERFIELD ROAD.	IL.43 @ ELDER LN./HAZEL AVE.	IL.43 @ GREENWOOD	IL.43 @ NORTH AVE.	IL.43 @ OFFICE PLAZA ENT.	IL.43 @ IL.22	INTERCONNECT
				Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F	Y 031-1F
88030330	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION BRACKET MOUNTED	EACH	1						1	
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	20	8	6	4	2			
88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	2			1	1			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	24	5	4	2	4	4	5	
88700200	LIGHT DETECTOR	EACH	4					2	2	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	2					1	1	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	14		6	5	3			
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	6	1	1	1	1	1	1	
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	6197							6197
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	105		40	25		10	30	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	650					230	420	
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	650					230	420	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	825						825	
X0325706	RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE IV CABINET (SPECIAL)	EACH	1						1	
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1					1		
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	4		1	1	1		1	
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1						1	
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	13157							13157
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1						1	
X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	2					1	1	
X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL 2	EACH	4	1	1	1	1			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	36						36	
89100400	ILLUMINATED SIGN, L E D	EACH	4						4	

* 100% COST WILL BE PAY BY DEERFIELD-BANNOCKBURN CENTRAL FIRE PROTECTION - Y031-3D

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES IL. 43 (WAUKEGAN RD.) FROM IL. 22 (HALFDAY RD.) TO DEERFIELD RD.
NAME	DATE	
		PLOT DATE: 2/1/2008