

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE SFTY-2A					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 016-2535 RAMP	SN 016-1165 TAYLOR ST.					CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
50102400	CONCRETE REMOVAL	CU YD	6.3	3.1	3.2															
50300255	CONCRETE SUPERSTRUCTURE	CU YD	6.4	3.2	3.2															
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	980	490	490															
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	30		30															
52000110	PREFORMED JOINT STRIP SEAL	FOOT	35.7	17.8	17.9															
66411900	TEMPORARY FENCE	FOOT	80		80															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1.5	1.5															
67100100	MOBILIZATION	L SUM	1	0.5	0.5															
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1															
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1															
X0320887	POLYMER CONCRETE	CU FT	3.12	3.12																
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	23	23																
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5															
XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1	0.5	0.5															
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3		3															
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	72		72															

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
**TAYLOR STREET OVER I-90/94**  
**S.N. 016-1165 AND S.N. 016-2535**

PLOT DATE: 3/10/2008

3/10/2008 8:48:03 AM C:\PROJECTS\STRUCT\016-1165.dgn

Rev.