

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652 X-B-R-1	DU PAGE	29	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 60C53				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE Y080-2A				
42001165	BRIDGE APPROACH PAVEMENT	SO YD	322	322				
42001300	PROTECTIVE COAT	SO YD	900	900				
44000700	APPROACH SLAB REMOVAL	SO YD	322	322				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	85.1	85.1				
50300260	BRIDGE DECK GROOVING	SO YD	607	607				
15030305	CONCRETE WEARING SURFACE, 5"	SO YD	617	617				
50400105	PRECAST CONCRETE BRIDGE SLAB	SO FT	299	299				
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SO FT	6691	6691				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14400	14400				
50800515	BAR SPLICERS	EACH	108	108				
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	249	249				
51500100	NAME PLATES	EACH	1	1				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	141	141				
60607100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18 (MODIFIED)	FOOT	80	80				
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	128	128				
67100100	MOBILIZATION	L SUM	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9	9				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2434	2434				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	238	238				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	238	238				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	69	69				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2276	2276				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	121	121				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	97	97				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% STATE Y080-2A				
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	340	340				
*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	12	12				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	95	95				
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	14	14				
78300100	PAVEMENT MARKING REMOVAL	SO FT	69	69				
78300105	PAVEMENT MARKING REMOVAL	FOOT	2494	2494				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	86	86				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SO FT	299	299				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	125	125				
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	92	92				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2				
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2				

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.P. 311/ US 34 (OGDEN AVE.)  
OVER WEST BRANCH DU PAGE RIVER  
PLOT DATE: 2/21/2008

Rev.

2/21/2008 11:15:11 AM 41313037444100 006500