

ROUTE: RT 52 (DELANY RD TO BAKER RD)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
DELANY RD	RANCH OAKS RD	NB	1	6	25	150	17			17				
DELANY RD	RANCH OAKS RD	SB	1	12	280	3360	373	373						
DELANY RD	RANCH OAKS RD	SB	1	12	129	1548	172	172						
DELANY RD	RANCH OAKS RD	NB	1	12	455	5480	607	607						
DELANY RD	RANCH OAKS RD	SB	1	12	137	1644	183	183						
RANCH OAKS RD	BAKER RD	NB	1	12	40	480	53	53						
RANCH OAKS RD	BAKER RD	NB	1	12	66	792	88	88						
RANCH OAKS RD	BAKER RD	SB	1	12	35	420	47	47						
RANCH OAKS RD	BAKER RD	NB	1	12	57	684	76	76						
RANCH OAKS RD	BAKER RD	NB	1	12	100	1200	133	133						
RANCH OAKS RD	BAKER RD	NB	1	12	950	11400	1287	1287						
RANCH OAKS RD	BAKER RD	NB	1	12	4	48	5			5				
RANCH OAKS RD	BAKER RD	SB	1	12	4	48	5			5				
JUST SOUTH OF BAKER		SB	1	4	43	172	19	19						
JUST SOUTH OF BAKER		NB	1	12	60	720	80	80						
JUST SOUTH OF BAKER		NB	1	12	270	3240	360	360						
JUST SOUTH OF BAKER		SB	1	12	610	7320	813	813						

TOTALS:

4298
SY

4271
SY

27
SY

2530
FT

59
EACH

(4-9-08)

FILE NAME * n:\projects\136308\design_aa.dgn	USER NAME * wlgreendp	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE US 52				F.A.P. RTE. VAR.	SECTION 2008-012 PP	COUNTY WILL	TOTAL SHEETS 33	SHEET NO. 10
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 60E38		
PLOT DATE = 4/9/2008	DATE -	REVISED -	REVISED -										