

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3561	2223 RS-2	COOK	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
20200100	EARTH EXCAVATION	CU YD	34	34				
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	275	275				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4				
25200110	SODDING, SALT TOLERANT	SQ YD	275	275				
25200200	SUPPLEMENTAL WATERING	UNIT	3	3				
28000400	PERIMETER EROSION BARRIER	FOOT	125	125				
28000510	INLET FILTERS	EACH	1	1				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	62	62				
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	62	62				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9				
40600300	AGGREGATE (PRIME COAT)	TON	44	44				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	145	145				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	175	175				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1880	1880				
42001300	PROTECTIVE COAT	SQ YD	130	130				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	100				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21683	21683				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	85	85				
44000600	SIDEWALK REMOVAL	SQ FT	100	100				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	600				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1400	1400				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1380	1380				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	18	18				
60404940	FRAMES AND GRATES, TYPE 23	EACH	18	18				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	150	150				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2				
67100100	MOBILIZATION	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2445	2445				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8960	8960				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	520	520				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	220	220				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	815	815				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8960	8960				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	520	520				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	220	220				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	180	180				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	180	180				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1119	1119				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	128.5	128.5				
X0325560	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER	EACH	1	1				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	942	942				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 WILLOW ROAD FROM I-94 TO HIBBARD ROAD

1/25/2008 10:00:00 AM