F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
374	3268F-R-1	COOK	279	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62387

	CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL/20% STATE						80% FED/13.34% STATE/6.66% PROSPECT HTS.	80% FED/13.34% STATE/3.33% PROSPECT HTS./3.33% MT. PROSPECT	100% PROSPECT HTS. FIRE PROTECTION DISTRICT		100% MT. PROSPECT	50% STATE/50% GLENVIEW		50% STATE/50% PROSPECT HTS.	100% GLENVIEW
					NHF	BRF	NHF				NHF	NHF							
					ROADWAY	BRIDGE IL 21 OVER DES PLAINES RIVER	LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS IL 21/US 45	TRAFFIC SIGNALS IL 21/SANDERS RD	TRAFFIC SIGNALS IL 21/APPLE DRIVE	TRAFFIC SIGNALS US 45/ SEMINOLE LANE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/APPLE DRIVE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/US 45	TRAFFIC SIGNALS EVP EQUIPMENT US 45/SEMINOLE LANE	NEW SIDEWALK	STORM SEWER	NEW SIDEWALK	WATERMAIN
					CONSTRUCTION TYPE CODES														
					J000-2A	X071-2A	Y030-1E	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y031-3D	Y031-3D	SFTY-1B	Y060	SFTY-1B	Y060
	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2															2
1	~~59100100~~	~~GEOCOMPOSITE WALL DRAIN~~	~~SQ YD~~	~~125~~		~~125~~													
	60100945	PIPE DRAINS 12"	FOOT	44.5	44.5														
	60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	947	947														
	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	203		203													
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1														
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	68	68														
	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1														
	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2														
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	4	4														
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	67	67														
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	31	31														
	60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2														
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11														
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	24	24														
	60247900	JUNCTION CHAMBER, SPECIAL	EACH	1	1														
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1														
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1														
	60260100	INLETS TO BE ADJUSTED	EACH	2	2														
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1														
	60500040	REMOVING MANHOLES	EACH	11	11														
	60500050	REMOVING CATCH BASINS	EACH	39	39														
	60500060	REMOVING INLETS	EACH	15	15														
	60600605	CONCRETE CURB, TYPE B	FOOT	858.0	858.0														
	60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	22.0	22.0														
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	662.0	662.0														
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	325.0	325.0														
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	18,320.0	18,320.0														
	60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	146.5	146.5														
	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	201.0	201.0														
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2,992	2,992														
	60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	2,691	2,691														
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	4,287	4,287														
	60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	4,823	4,823														
	60624600	CORRUGATED MEDIAN	SQ FT	157	157														
	60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2														
	60900515	CONCRETE THRUST BLOCKS	EACH	2	2														
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2412.5	2,412.5														

○ NON-PARTICIPATING

* SPECIALTY ITEM

1 Rev. 4-14-08

STV Incorporated
engineers/architects/scientists/construction managers
200 W Monroe - Suite 1650
Chicago, Illinois 60606

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES - 4

SCALE: NTS
DATE 02/05/08

DRAWN BY RDT
CHECKED BY GC

\civil\proj\3968csum.dgn 2/7/2008 11:10:10 AM