F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
374	3268F-R-1	COOK	279	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62387

	CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODES														
					NHF	BRF	80% FEDERAL/20% STATE NHF				NHF 80% FED/13.34% STATE/6.66% PROSPECT HTS.	NHF 80% FED/13.34% STATE/3.33% PROSPECT HTS./3.33% MT. PROSPECT	100% PROSPECT HTS. FIRE PROTECTION DISTRICT		100% MT. PROSPECT	50% STATE/50% GLENVIEW		50% STATE/50% PROSPECT HTS.	100% GLENVIEW
					ROADWAY	BRIDGE IL 21 OVER DES PLAINES RIVER	LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS IL 21/US 45	TRAFFIC SIGNALS IL 21/SANDERS RD	TRAFFIC SIGNALS IL 21/APPLE DRIVE	TRAFFIC SIGNALS US 45/ SEMINOLE LANE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/APPLE DRIVE	TRAFFIC SIGNALS EVP EQUIPMENT IL 21/US 45	TRAFFIC SIGNALS EVP EQUIPMENT US 45/SEMINOLE LANE	NEW SIDEWALK	STORM SEWER	NEW SIDEWALK	WATERMAIN
					J000-2A	X071-2A	Y030-1E	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-3D	Y031-3D	Y031-3D	SFTY-1B	Y060	SFTY-1B	Y060
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	3					1		1	1							
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	3					1		1	1							
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	290						290									
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,696						600			291	455	350				
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,497					3,150	840	1,665	1,842							
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,254					800	615	543	296							
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6,515					2,770	415	1,690	1,640							
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	150							30	120							
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	9					5		2	2							
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4					1		2	1							
*	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2					1			1							
*	87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	2					2										
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	3							1	2							
*	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1					1										
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1							1								
*	87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1					1										
*	87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1							1								
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	60					28		16	16							
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	12					4		4	4							
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	90.5					47		23.5	20							
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	11							11								
*	87900200	DRILL EXISTING HANDHOLE	EACH	3				1		2									
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	18					8		6	4							
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10					5		2	3							
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4					2		2								
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	3					1		1	1							
*	88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2					1			1							
*	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1								1							
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	21					9		7	5							
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	21					8		7	6							
*	88600100	DETECTOR LOOP, TYPE I	FOOT	631							183	448							
*	88700200	LIGHT DETECTOR	EACH	5									2	3					
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	2									1	1					
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4					1	1	1	1							
*	89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	3											3				
*	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1											1				
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4,209			2,854	100		1,255									

○ NON-PARTICIPATING

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES - 7

STV Incorporated
engineers/architects/scientists/construction managers
200 W Monroe - Suite 1650
Chicago, Illinois 60606

SCALE: NTS
DATE 02/05/08
DRAWN BY RDT
CHECKED BY GC