

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90		COOK	37	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62992

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	QUANTITY	URBAN
				100% STATE JOOO
20200100	EARTH EXCAVATION	CU YD	608	608
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	57	57
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	511	511
25000210	SEEDING, CLASS 2A	ACRE	0.21	0.21
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25	25
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	25
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	25
25000800	GROUND PREPARATION FOR SEEDING	ACRE	0.15	0.15
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.06	0.06
25100630	EROSION CONTROL BLANKET	SQ YD	1,283	1,283
42001300	PROTECTIVE COAT	SQ YD	112	112
50300225	CONCRETE STRUCTURES	CU YD	8.9	8.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.4	7.4
50300300	PROTECTIVE COAT	SQ YD	282	282
50300510	RUSTICATION FINISH	SQ FT	95	95
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,270	1,270
60618324	CONCRETE MEDIAN SURFACE, 6" (SPECIAL)	SQ FT	815	815
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	2,477	2,477
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2670	2670
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	668	668
X0324640	FLUTED KNEE WALL	FOOT	2621	2621
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	0.06	0.06
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	193	193
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030020	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2
44002300	CURB REMOVAL (PARTIAL)	FOOT	138	138
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1

**INDEX OF SHEETS**

SHEET	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES AND PROJECT COMMITMENTS
3	SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-9	ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS
10-16	EXISTING AND PROPOSED KNEE WALL PLANS
17-19	STRUCTURAL DETAILS
20	BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING
21	TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS
22	TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
23	TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
24	TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN
25-37	CROSS SECTIONS

**IDOT HIGHWAY STANDARDS**

SHEET	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-01	CHAIN LINK FENCE
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph
701901	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
728001	TELESCOPING STEEL SIGN SUPPORT
731001	BASE FOR TELESCOPING STEEL SIGN SUPPORT

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
NORTHBOUND KNEE WALLS (PERSHING RD TO 35TH ST)  
**SUMMARY OF QUANTITIES**  
**INDEX OF SHEETS**  
**HIGHWAY STANDARDS**  
SCALE: NONE DRAWN BY: JDC  
DATE: 02/08/08 CHECKED BY: DDM

S00-1

2/12/2008 2:58:28 PM