

F. A. D. E.C.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00113-00-PK	COOK	012	002
STA.		TO STA.		
FED. ROAD DIST. NO.	BLKNO.	FED. AID PROJECT		

CONTRACT NO. 63006

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTING				
S.P.	S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
						I000	SFTY-1D	Y002-1C	Y003	Y030-1E			
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14				14				
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	21				21				
		20101000	TEMPORARY FENCE	FOOT	50				50				
		20101200	TREE ROOT PRUNING	EACH	7				7				
		20200500	EARTH EXCAVATION (WIDENING)	CU YD	205	205							
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	23.5	23.5							
△		20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	23.5	23.5							
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	71	71							
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	167				167				
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3				3				
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3				3				
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3				3				
		25200100	SODDING	SQ YD	167				167				
		25200200	SUPPLEMENTAL WATERING	UNIT	5				5				
		28000400	PERIMETER EROSION BARRIER	FOOT	500				500				
		28000510	INLET FILTERS	EACH	3				3				
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	415	415							
		40600100	BITUMINOUS MATERIAL (PRIME COAT)	GAL	118	118							
		40600300	AGGREGATE (PRIME COAT)	TON	2	2							
		40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	394	394							
		42001300	PROTECTIVE COAT	SQ YD	452	452							
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3170								
		42400800	DETECTABLE WARNINGS	SQ FT	12	12							
		44000100	PAVEMENT REMOVAL	SQ YD	96	96							
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	445	445							
		44000600	SIDEWALK REMOVAL	SQ FT	50	50							
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	445	445							
		67100100	MOBILIZATION	L SUM	1	1							
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1							
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1							
		72000100	SIGN PANEL - TYPE 1	SQ FT	4.88			4.88					
		72900200	METAL POST - TYPE B	FOOT	14			14					
*		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1013		1013						
*		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	35		35						
*		81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	500				500				
*		83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	14				14				
△	*	XX001399	UNIT DUCT, BORED AND PULLED	FOOT	460				460				
△	*	XX005669	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2				
△	*	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	2				2				
△	*	X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1				1				
△	*	X0322178	REMOVE EXISTING LIGHT POLE FOUNDATION	EACH	2				2				

* - INDICATES SPECIALTY ITEMS △ - INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IVANHOE METRA COMMUTER KISS 'N RIDE
SUMMARY OF QUANTITIES & GENERAL NOTES

SCALE: VERT. NONE DRAWN BY PS/EDG
 HORIZ. NONE CHECKED BY PKB
 DATE 11-1-07

ROBINSON ENGINEERING, LTD.
 17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
 (708) 321-6700 FAX (708) 321-3800
 ILLINOIS DESIGN FIRM REGISTRATION NO. 184001128 04824-QUAN-01 - P01