F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1678	07-00064-00-RS	COOK	17	3
STA. ---		TO STA. ---		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 63009

SUMMARY OF QUANTITIES

LOCATION OF WORK				STP - LAPP		
				LEMOYNE ST. 80% FED. 20% LOCAL	DODD AVE. 100% LOCAL	HAROLD AVE. 100% LOCAL
FUNDING SOURCE				STP	LOCAL	LOCAL
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
ITEM #	ITEM	UNIT	TOTAL QUANTITIES	I000-2A	I000-2A	I000-2A
28000510	INLET FILTERS	EACH	71	66	0	5
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	50	30	10	10
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	350	250	50	50
35800200	AGGREGATE BASE REPAIR	TON	50	50	0	0
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	300	200	50	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2255	1945	110	200
40600300	AGGREGATE (PRIME COAT)	TON	48	40	3	5
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2265	1955	110	200
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	305	240	30	35
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1945	1675	100	170
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	100	50	25	25
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	3500	2500	500	500
42400400	PORTLAND CEMENT CONCRETE SIDEWALK, 7 INCH	SQ FT	1000	600	200	200
42400800	DETECTABLE WARNINGS	SQ FT	104	64	20	20
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	21460	18540	1045	1875
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	450	300	75	75
44000600	SIDEWALK REMOVAL	SQ FT	4500	3100	700	700
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3800	3350	200	250
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	21460	18540	1045	1875
~~58100200~~	~~WATERPROOFING MEMBRANE SYSTEM~~	~~SQ YD~~	~~210~~	~~210~~	~~0~~	~~0~~
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	6	6	0	0
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	19	17	0	2
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	0	0
60266800	VALVE BOXES TO BE REPLACED	EACH	1	1	0	0
67100100	MOBILIZATION	L. SUM	1	1	0	0
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	0	0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	1	0	0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1	1	0	0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	1	0	0
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2255	2125	65	65
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	575	575	0	0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	465	435	15	15
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	212	212	0	0
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	71	66	0	5
XX006392	CLASS D PATCHES, 6" (SPECIAL)	SQ YD	585	445	50	90
*Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	1	0	0
Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	14	13	0	1
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	29	27	0	2
Z0018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	8	8	0	0
XX006940	CLASS C PATCHES, 6" (SPECIAL)	SQ YD	585	445	50	90

* INDICATES SPECIALTY ITEM

REVISIONS	
NAME	DATE
AMP	3/19/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CITY OF NORTHLAKE
LEMOYNE SREET

SCALE N.T.S. DRAWN BY EDT

DATE 3/19/2008 CHECKED BY MW

CHRISTOPHER B. BURKE ENGINEERING LTD.
9575 West Higgins Road, Suite 600
Rosemont, Illinois 60018
(847) 823-0500

PLAN — NOTE BOOK NO. ____ SURVEYED ____ PLOTTED ____ ALIGNMENT CHECKED ____ RT. OF WAY CHECKED ____ P-400 FILE NAME ____ BY ____ DATE ____

PROFILE — NOTE BOOK NO. ____ SURVEYED ____ PLOTTED ____ GRADES CHECKED ____ B.M. NOTED ____ STRUCTURE NOTATNS CHKD ____ BY ____ DATE ____