

# SUMMARY OF QUANTITIES

CONTRACT NO. 64C35				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
17	15T-2	CARROLL	71	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				RURAL	
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	Y007	Y007
				80% FED/ 20% STATE	80% FED/ 20% STATE
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,883	4,892	1,991
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,336	1,639	697
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,361	713	648
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	975	613	362
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	10,772	8,550	2,222
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	23	20	3
78300100	PAVEMENT MARKING REMOVAL	SQ FT	865	603	262
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	23	20	3
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	11	11	
X4810100	TEMPORARY SHOULDERS	SQ YD	526	252	274
XX005298	REMOVE EXISTING TIMBER WALL	FOOT	105		105
Z0005400	BREAKER-RUN CRUSHED STONE	TON	1,538	1044	494
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0
Z0023600	FILLING EXISTING CULVERTS	EACH	1		1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9	6	3
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	2	2
*SPECIALTY ITEMS					

PLOT DATE = Mon, Jan 28, 18:32:41, 2008  
 FILE NAME = C:\Projects\p207686\1807086\vr.dgn  
 PLOT SCALE = 800/2002 in / IN  
 USER NAME = hennings