

SP

CODE NUMBER	PAY ITEM	UNIT	RURAL 80% FED. 20% STATE Y007 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1866
25000210	SEEDING, CLASS 2A	ACRE	0.71
25000310	SEEDING, CLASS 4	ACRE	0.18
25000350	SEEDING, CLASS 7	ACRE	0.24
25000750	MOWING	ACRE	0.89
25100115	MULCH, METHOD 2	ACRE	0.89
25100900	TURF REINFORCEMENT MAT	SQ YD	1689
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	375
28000300	TEMPORARY DITCH CHECKS	EACH	25
28000400	PERIMETER EROSION BARRIER	FOOT	220
28100107	STONE RIPRAP, CLASS A4	SQ YD	69
28200200	FILTER FABRIC	SQ YD	69
35100100	AGGREGATE BASE COURSE, TYPE A	TON	380
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	10
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	88
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	145
48101200	AGGREGATE SHOULDERS, TYPE B	TON	219
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2
50800105	REINFORCEMENT BARS	POUND	8,870
50800515	BAR SPLICERS	EACH	31
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	323
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	52.3
542D5503	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 48"	FOOT	35
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	75
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5
61140000	STORM SEWERS (SPECIAL) 8"	FOOT	76
61140100	STORM SEWERS (SPECIAL) 10"	FOOT	10

SP

CODE NUMBER	PAY ITEM	UNIT	RURAL 80% FED. 20% STATE Y007 TOTAL QUANTITY
61140400	STORM SEWERS, SPECIAL 15"	FOOT	12
61140600	STORM SEWERS, SPECIAL 18"	FOOT	196
63200310	GUARDRAIL REMOVAL	FOOT	378
63500105	DELINEATORS	EACH	2
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	15
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	270
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2083
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	834
70400100	TEMPORARY CONCRETE BARRIER	FOOT	438
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	325
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7200
78300100	PAVEMENT MARKING REMOVAL	SQ FT	636
Z0005400	BREAKER-RUN CRUSHED STONE	TON	230
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0023600	FILLING EXISTING CULVERTS	EACH	1
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0064505	SECTION CORNER MARKERS	EACH	1
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	523

* SPECIALTY ITEMS ● 100% STATE

FILE NAME = c:\projects\p210006\dl0006crr.dgn

USER NAME = grantpm	DESIGNED -	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = Thu Jan 31 06:46:42 2008	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 638	SECTION 136T	COUNTY HENRY	TOTAL SHEETS 34	SHEET NO. 3
CONTRACT NO. 64A57				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				