

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN X271-2A 80% Fed/ 20% State TOTAL QUANTITY
* 20200100	EARTH EXCAVATION	CU YD	1,123
* 20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	<del>208</del> 246
25000210	SEEDING, CLASS 2A	ACRE	1.75
25100630	EROSION CONTROL BLANKET	SQ YD	8,228
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,020
▲ 25000750	MOWING	ACRE	1.75
28000400	PERIMETER EROSION BARRIER	FOOT	2,745
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	3,875
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	1,060
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.4
40600300	AGGREGATE (PRIME COAT)	TON	14
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	355
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,344
40600990	TEMPORARY RAMP	SQ YD	<del>204</del> 331
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	1,143
* 42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	740
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,060
44000700	APPROACH SLAB REMOVAL	SQ YD	740
* 44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	816
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,379
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	3,379
50102400	CONCRETE REMOVAL	CU YD	<del>82</del> 61.2
50104650	SLOPE WALL REMOVAL	SQ YD	676
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2
50157300	PROTECTIVE SHIELD	SQ YD	1,455
50200100	STRUCTURE EXCAVATION	CU YD	233
50300225	CONCRETE STRUCTURES	CU YD	<del>260</del> 2.7
50300255	CONCRETE SUPERSTRUCTURES	CU YD	<del>260</del> 765.4
50300260	BRIDGE DECK GROOVING	SQ YD	2,208
50300300	PROTECTIVE COAT	SQ YD	2,659

\*SPECIALTY ITEMS  
▲ NP 100% STATE

REVISED 4/8/08