

PROJECT NO. FAU 2503	SECTION (35)BR-2	CITY KENDALL	SHEET NO. 129	TOTAL SHEETS 3
----------------------------	---------------------	-----------------	------------------	-------------------

SUMMARY OF QUANTITIES

CODE #	ITEM	UNITS	URBAN QUANTITY	1000-2A	X081-2A	SFTY-1B
				ROADWAY 80% FEDERAL 20% STATE	EX SN 047-0034 PR SN 047-0062 80% FEDERAL 20% STATE	NEW SIDEWALK 50% STATE 50% VILLAGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	184	184		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	206	206		
25200200	SUPPLEMENTAL WATERING	UNIT	21	21		
20200100	EARTH EXCAVATION	CU YD	195	195		
20200200	ROCK EXCAVATION	CU YD	12	12		
20400800	FURNISHED EXCAVATION	CU YD	216	216		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	282		282	
20800150	TRENCH BACKFILL	CU YD	38	38		
* 25000100	SEEDING, CLASS 1	ACRE	0.06	0.06		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26	26		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26	26		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26	26		
* 25100630	EROSION CONTROL BLANKET	SQ YD	1104	1104		
25200110	SODDING, SALT TOLERANT	SQ YD	1600	1600		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	157	157		
28000400	PERIMETER EROSION BARRIER	FOOT	670	670		
28000510	INLET FILTERS	EACH	19	19		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1115		1115	
28200200	FILTER FABRIC	SQ YD	1331		1331	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	260	260		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	75	75		
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	568	568		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	21	21		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	476	476		
40600300	AGGREGATE (PRIME COAT)	TON	8.6	8.6		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	225	225		
40600990	TEMPORARY RAMP	SQ YD	468	468		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	36	36		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	191	191		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	95	95		
42000520	PORTLAND CEMENT CONCRETE PAVEMENT, 11"	SQ YD	145	145		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	302	302		
42001300	PROTECTIVE COAT	SQ YD	302	302		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7" INCH	SQ YD	523	523		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	60	60		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	2196	180		2016
44000080	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	1284	1284		

* - SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE #	ITEM	UNITS	URBAN QUANTITY	1000-2A	X081-2A	SFTY-1B
				ROADWAY 80% FEDERAL 20% STATE	EX SN 047-0034 PR SN 047-0062 80% FEDERAL 20% STATE	NEW SIDEWALK 50% STATE 50% VILLAGE
44000100	PAVEMENT REMOVAL	SQ YD	848	848		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	547	547		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	696	696		
44000600	SIDEWALK REMOVAL	SQ FT	112	112		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	42	42		
50300300	PROTECTIVE COAT	SQ YD	661		661	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	95	95		
50200100	STRUCTURE EXCAVATION	CU YD	520		520	
50300225	CONCRETE STRUCTURES	CU YD	58		58	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	243		243	
50300260	BRIDGE DECK GROOVING	SQ YD	495		495	
50300280	CONCRETE ENCASEMENT	CU YD	5.6		5.6	
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	835		835	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4130		4130	
50800515	BAR SPLICERS	EACH	396		396	
50900105	ALUMINUM RAILING, TYPE L	FOOT	104		104	
50901125	STEEL RAILING (TEMPORARY)	FOOT	86		86	
51201610	FURNISHING STEEL PILES HP12X63	FOOT	376		376	
51500100	NAME PLATES	EACH	1		1	
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	140	140		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1	1		
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	221	221		
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	435	435		
55100500	STORM SEWER REMOVAL 12"	FOOT	70	70		
55100900	STORM SEWER REMOVAL 18"	FOOT	10	10		

* - SPECIALTY ITEMS

REVISSED 4/2/08

HAMPTON, LENZINI & RENWICK, INC.
CIVIL & STRUCTURAL ENGINEERS

HLR

3085 STEVENSON DRIVE, SUITE 201
SPRINGFIELD, ILLINOIS 62703
(217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-06-0029-1 DATE: 06/01/07
DESIGNED: LFS CHECKED: DRAWN: TWK

SUMMARY OF QUANTITIES
SECTION (35) BR-2
IL 25 OVER WAUBONSEE CREEK
KENDALL COUNTY