

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(39B)I	McDONOUGH	38	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES				ROADWAY FAP 310 80% FEDERAL 20% STATE	STRUCTURE SN.055-0005 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	133	133	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1410	1410	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT	747	747	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1410	1410	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	51	51	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	470	470	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	214	214	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	49		49
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	52	52	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	425		425
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52		52
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE
K.M	1/30/08

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
US 67 OVER TROUBLESOME CREEK
FAP 310 SECTION (39B)I
McDONOUGH COUNTY
 SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY MJS
 DATE #DATE