

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
318	(21B-11), (20BR1-1)	PUTNAM	24 3
STA. *		TO STA. *	
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT	
* 078-0003 @ Sta. 126+17.50 078-0005 @ Sta. 133+17.70			

SUMMARY OF QUANTITIES

100% STATE SAFETY - 2A PUTNAM COUNTY-RURAL					
CODE NO.	ITEM	UNIT	0003	0005	TOTAL
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	838	876	1714
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	20.5	20.5	41
42001300	PROTECTIVE COAT	SQ YD	24.7		24.7
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	245	245	490
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	501	138	639
44004250	PAVED SHOULDER REMOVAL	SQ YD	463	460	923
50102400	CONCRETE REMOVAL	CU YD	11		11
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11		11
50300260	BRIDGE DECK GROOVING	SQ YD	476	128	604
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	830		830
50800515	BAR SPLICERS	EACH	8		8

PLOT DATE = 08/15/07
 PLOT SCALE = 1/8" = 1'-0"
 PLOT REFERENCE = #REF#
 CONTRACTS\BRIDGE\CONTRACTS\68713-1\2\Draw - Summary\68713-1.dwg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE 11-07-2007

DRAWN BY CEJ
 CHECKED BY _____